

BOARD MEETING AGENDA

Coon Creek Watershed District Offices - Board Room Monday, August 12, 2024, 5:30 p.m.

Board of Managers:

Jim Hafner, President; Erin Lind, Vice President; Jason Lund, Secretary; Mary Campbell, Treasurer; Dwight McCullough, Member at Large

Note: Individuals with items on the agenda or who wish to speak to the Board are encouraged to be in attendance when the meeting is called to order.

- 1. Call to Order
- **2.** Approval of the Agenda (Additions/Corrections/Deletions)
- 3. Announcements
- 4. Open Mic/Public Comment

Members of the public at this time may address the Board, for **up to three minutes**, on a matter not on the Agenda. Individuals wishing to be heard must sign in with their name and address at the door. Additional comments may be accepted in writing. Board action or discussion should **not** be expected during the presentation of public comment/open mic. Board members may direct staff to research the matter further or take the matter under advisement for consideration at a future Board meeting.

CONSENT ITEMS

The consent agenda is considered as one item of business. It consists of routine administrative items or items not requiring discussion. Items can be removed from the consent agenda at the request of a Board member, staff member or a member of the audience.

- 5. Approval of Minutes July 29th
- 6. Receive Administrator's Report
- 7. Advisory Committee Report
- 8. Bills/Accounts Payable

POLICY ITEMS

- 9. Approve Administrator's Employment Agreement
- 10. Approve Submittal of Draft 2024-2033 Comp. Plan to BWSR
- 11. Award Work on Ditch 39 Geotechnical Services

PERMIT ITEMS

- 12.24-038 Adolfson Riverbank Stabilization
- 13.24-036 Family Promise
- 14.23-080 Les Schwab Tire Center
- 15.24-004 NSC Turf Field and Campus Improvements
- 16.23-068 Park of Four Seasons

DISCUSSION ITEMS

- 17. Draft 2025 Operating Budget
- 18.0ak Glen Creek Inspection Report
- 19. Woodcrest Creek Inspection Report

INFORMATIONAL ITEMS

ADJOURN

COON CREEK WATERSHED DISTRICT BOARD OF MANAGERS' MEETING

The Board of Managers of the Coon Creek Watershed District held a special meeting on Monday, July 29, 2024, at the Coon Creek Watershed District Office.

1. Call to Order

The meeting was called to order at 5:31 PM

Board Members Present: Jim Hafner, Mary Campbell, Jason Lund, Erin Lind & Dwight

McCullough

Staff Present: Tim Kelly, Jessica Lindemyer, Bobbie Law, Erik Bye & Michelle Ulrich

Stakeholders Present on Zoom: Abbey Shea Stakeholders Present: Michelle Jordan

2. Announcements

No announcements.

CONSENT ITEMS

3. Approval of Minutes of July 22, 2024

Board Member McCullough moved to approve the July 22nd minutes as presented. Seconded by Board Member Lund. The motion carried with 5 yeas (Board Members Campbell, Hafner, Lind, Lund, and McCullough) and no nays.

PUBLIC HEARING

4. Purpose and Scope of Hearing

President Hafner outlined the purpose and scope of the public hearing. He explained this hearing provides the District the opportunity to gather public opinion and concerns on the draft 2024-2033 Comprehensive Watershed Management Plan prior to the submittal of the document to the Minnesota Board of Water and Soil Resources (BWSR).

5. Submission of Written Documents/Exhibits into the Record

Mr. Kelly gave an overview of the planning timeline. He submitted multiple items into public record including:

- May 3rd, 2022, notice of intent
- July 2nd, 2022, public notice period ended
- January 23rd, 2023, the initial planning meeting required by statute was held by the CCWD Board of Managers
- September 25th, 2023, the Board adopted Resolution 23-04 requesting an extension to the 2013-2023 Comprehensive Watershed Management Plan
- October 30th, 2023, BWSR approved extension request
- November 27th, 2023, the Board of Managers discussed the Plan summary
- On December 21st, 2023, the Board released a draft of the Comprehensive Watershed Management Plan for 2024- 2033 for public review. The public review period ended on February 23^{rd,} 2024, and on July 29^{th,} 2024, that public hearing to receive comments was held. Notice of Hearing and Affidavit of Publication included

Minutes: Coon Creek Watershed District Board of Managers, Page 2 of 3

 On August 12th the Board will approve the Comprehensive Watershed Management Plan with updates made based on comments received

Staff recommended that the Board move to receive the public record as stated and presented.

Board Member Lund moved to receive the public record. Seconded by Board Member Lind. The motion carried with 5 yeas (Board Members Campbell, Hafner, Lind, Lund, and McCullough) and no nays.

5:34 PM Michelle Jordan joined the meeting. BWSR Board Conservationist

Mr Kelly called for a point of order. He noted that the verbal record given was not complete. He added the following points of information:

• The surveys and meetings to prioritize certain water resource issues and priorities occurred at 60+ meetings with multiple stakeholders. These meetings included the CAC and TAC. The District also conducted surveys that included other stakeholders affected by the District's Comprehensive Watershed Management Plan. The District responded to 298 official comments on the draft Plan. The Plan also includes additional exhibits including the public engagement plan, record of public engagement, the Notice of Intent regarding comments, and the comments and responses themselves, a summary of the Comprehensive Watershed Management Plan will be provided online.

Board Member Campbell moved to add additional items to the record. Seconded by Board Member Lund. The motion carried with 5 yeas (Board Members Campbell, Hafner, Lind, Lund, and McCullough) and no nays.

6. Summary of the Comprehensive Watershed Management Plan

Erik Bye the Coon Creek Watershed District Planner gave a presentation regarding the Comprehensive Watershed Management Plan. He covered many topics including:

- The planning process
- Authorization
- The current condition of the watershed, specific to impaired waters, the connections between surface and groundwater, flood risk, and TMDLs.
- The management plan goals and strategy.
- Essential tasks
- Risks and concerns identified with the implementation of this watershed management plan including funding, prolonged debate, rejection of effort due to cost, transfer of risk
- Strategies to alleviate risks and concerns including additional funding, staggered TMDL timeline, differentiation of water resources, and incremental plan review at 2.5 and 5-year marks

Mr. Kelly spoke to the importance of incremental updates to the plan. Board Member Campbell supported the big efforts planned for the next ten-year Comprehensive Watershed Management Plan cycle.

Minutes: Coon Creek Watershed District Board of Managers, Page 3 of 3

7. Call for Public Comments

President Hafner called for comments from stakeholders and meeting attendees three times. He called for comment directly from the two stakeholders in attendance and once to the general public.

8. Close Hearing

Board Member Lund moved to close the public hearing. Seconded by Board Member Lind. The motion carried with 5 yeas (Board Members Campbell, Hafner, Lind, Lund, and McCullough) and no nays.

9. Summary of Comments, Proposed Responses, and Needed Actions

Kelly noted the 298 comments are broken into 3-5 general categories

- Editorial
- Technical
- Goal specific

Kelly provided a summary of next steps and timeline for the remainder of the planning process.

ADJOURN

| Board | Member | Campbell | moved | to ad | journ a | t 6:06 | pm. | Seconde | d by | Boar | d Mer | <u>mber</u> |
|--------------|------------|------------|----------|-------|---------|--------|-------|----------|--------|--------|-------|-------------|
| Lund. | The moti | on carried | d with 5 | yeas | (Board | Memb | ers C | Campbell | , Hafı | ner, I | Lind, | Lund, |
| and M | lcCulloual | n) and no | navs. | | | | | | • | - | - | |

| President | |
|-----------|--|

MEETING DATE: August 12, 2024

AGENDA NUMBER: 6

ITEM: Administrator's Report

AGENDA: Consent

REQUESTED ACTION:

Receive report.

ADMINISTRATOR'S EVALUATION

Upcoming Board Considerations

- Public Hearing on Comprehensive Plan and Comments
- Permit Review Fee structure and amounts.

District Capacity and Capability

The District possesses the required resources and is mostly trained to undertake most of its legislative mission for which it is organized or designed.


The District can accomplish most required tasks to standard under most conditions.

MANAGEMENT SITUATION


The District averaged 3.5 Inches of precipitation in the month of July. That leaves the District 0.7 inches or 16% below for the month and 5.6 inches or 30% above for the year. Growing season precipitation (May-July) is 3.2 inches or 26% above average.

Due to recent storms, water levels and flows across the District are currently high or on the high end of normal. Lakes, ponds, and wetlands are also on the high end of normal. Soils are now saturated again, leaving the District at a slightly elevated flood risk, but no flooding is expected in the forecast.

The National Weather Service is predicting 1" of precipitation over the next 7 days.



Problems, Issues, and Concerns



Cooperator Actions

| Agency | Status |
|---------------------|--|
| BWSR | Water Storage Modeling Tool: The resources needed to identify water storage sites will be available as a toolbar that builds on data developed by BWSR's Prioritize, Target, and Measure Application (PTMApp). |
| Clean Water Council | Continuing trend of pots of money to go to LGUs Groundwater is growing in funding requests: MDH is finding that GRAPS (WRAPS for Groundwater) are effective as partnership info clearinghouse including private parties and wants to continue. MDH reports that a Regional Groundwater Specialist is being piloted to be a technical expert to synthesize groundwater information for targeted implementation. This position is expected to be hired by early fall. DNR Groundwater monitoring – continuing and expanding observation wells. |
| DNR | Conservation Partners Legacy grant program applications opened 8/1 |
| Met Council | Released "Imagine 2050- Water Policy Plan" for public review until October 12. |


Collaborator Actions

| Collaborator | Description |
|------------------------------|---|
| Anoka Conservation District | • Nearly a decade after Minnesota's buffer law was enacted in 2015, 99.8% of parcels adjacent to Minnesota waters are compliant with the law. |
| MN DOT | Highway 65 will remain in one lane in both directions between Bunker Lake Boulevard and Coon Creek Bridge through late August. This is to make room for the eventual replacement of Coon Creek Bridge." |
| Anoka County Highway Dept | AC Highways borrowed some of our stormwater, Chloride and Pet waste outreach materials for the County Fair. County staff are excited about Jim Dickinson coming on staff. The new Environmental position closed; Rebecca Haug, former CCWD & Blaine Stormwater Manager was hired. |

| Andover | • | Red Oaks Water Contamination Mitigation Construction Project: Update 8/2/24: o Irrigation repairs will continue until completed. o Mailbox installation will be completed next week. o Sod will begin on Monday (weather permitting) on Quinn St NW between 139th Ave NW and 140th Lane NW. |
|---------|---|---|
| | • | City Manager Jim Dickinson is moving to Anoka County as the new County Administrator. |
| Blaine | • | Granted a comprehensive plan amendment to change the land use designation from High Density Residential (HDR) to Medium Density Resident/l/Community Commercial (MDR/CC) and Medium Density Residential (MDR) to Medium Density Residential/Community Commercial (MDR/CC) at 12565 and 12535 Zest Street NE and 12592 Lexington Ave NE. |
| | • | Adopted the Alternative Urban Areawide Review (AUAR) for the 105th Redevelopment Project. |
| | • | Granted master plan approval for the 105th Redevelopment Project at 10550 Nassau Street NE, 105th Avenue Redevelopment Area. |
| | • | Adoption of the Alternative Urban Areawide Review (AUAR) and Mitigation Plan for the Redevelopment of Northtown Mall and surrounding area. |
| | • | Granted final plat approval to create 13 lots to be known as Northtown Revitalization at 100 Northtown Drive NE. |
| | • | Granted final plat approval to subdivide 21.52 acres into 40 single family lots and two outlots to be known as Crispin Cove at 4255 125th Ave NE and 12581 Lexington Ave NE. |
| | • | Granted a rezoning for certain parcels from Regional Recreation (RR) to 105th Redevelopment District (RD). |
| | • | Granted a comprehensive plan amendment of certain parcels from Major Recreation (MR) to Planned Commercial (PC). |
| | • | Granted final plat approval to create two lots to be known as BB Western Subdivision at 12251 Ulysses Street NE, GHS Development. |
| | • | Granted a comprehensive plan amendment to change the land use designation from High Density Residential/Community Commercial (HDR/PC_ to Medium Density Residential/Community Commercial (MDR/CC) at the Northwest Corner of Paul Parkway NE and Ulysses Street NE. |

| Columbus | No report |
|------------------|--|
| Coon Rapids | Removing all street sweepings and cleaning up city dumping area on Pleasure Creek Bunker Hills Park is tying into city sanitary sewer |
| Fridley | Fridley Mayor Scott Lund will not seek reelection |
| Ham Lake | Ham Lake Area Chamber of Commerce got a legislative review from Senator Kreun. |
| Spring Lake Park | No report |

STAFF ACTIVITIES



Special Projects

Anoka County Transition:

<u>Benefits Replacement</u>: More complete benefit options and estimated costs have been provided by our consultants. Costs are likely to be significantly higher than were initially

budgeted for 2025. Adjustments have been made to the 2025 budget based on what is known as of this date.

Comp Plan Review:

• Ready to submit to BWSR. On tonight's agenda.

MANAGEMENT DISPOSITION

Equipment and Facilities:
All equipment is in good working condition.

Financial Position:

| As of Date: | 07/31/2024 | | | | |
|---|---------------------|----------------------|---------------------|--------------|------|
| | | | | | |
| | Year Ending | Year To | Date | | |
| | 12/31/2024 | 07/31/2 | 2024 | | |
| | CCWD 2024 Budget | CCWD 2024 Budget YTD | Actual Expenses YTD | Variance YTD | |
| Revenue | | | | | |
| Property Taxes | 4,965,765.00 | 2,896,698.00 | 2,594,543.71 | 302,154.29 | -10% |
| Fees & Charges | 298,423.00 | 174,083.00 | 103,412.23 | 70,670.77 | -41% |
| Grants | 314,539.00 | 183,484.00 | | (40,772.95) | 22% |
| Other Revenue | 28,042.00 | 16,359.00 | | (69,348.91) | 424% |
| Total Revenue | 5,606,769.00 | 3,270,624.00 | 3,007,920.80 | 262,703.20 | -8% |
| Expense | | | | _ | |
| Salaries & Benefits | 1,981,605.00 | 1,155,945.00 | 945,973.30 | 209,971.70 | -18% |
| Professional Services | 589,000.00 | 343,595.00 | 175,963.82 | 167,631.18 | -49% |
| Operating Expenses | 239,164.00 | 139,524.00 | 129,586.68 | 9,937.32 | -7% |
| Program Expense | 2,757,867.00 | 1,608,768.00 | 699,001.48 | 909,766.52 | -57% |
| Capitalized Expenses | 166,708.00 | 97,251.00 | 50,333.33 | 46,917.67 | -48% |
| Total Expense | 5,734,344.00 | 3,345,083.00 | 2,000,858.61 | 1,344,224.39 | -40% |
| | | | | | |
| Coon Creek Watershed District | | | | | |
| Cash Balance | | | | | |
| As of Date: | 07/31/2024 | | | | |
| | | | | | |
| | Escrow Fund | General Fund | All Funds | | |
| | Month Ending | Month Ending | Month Ending | | |
| | 07/31/2024 | 07/31/2024 | 07/31/2024 | | |
| | | | | | |
| Cash and Cash Equivalents | | | | | |
| Cash | 1,925,606.69 | (2,339,854.58) | | | |
| Petty Cash | 0.00 | 250.00 | 250.00 | | |
| Investment Account | 2,870.00 | 5,049,628.90 | 5,052,498.90 | | |
| Total Cash and Cash Equivalents | 1,928,476.69 | 2,710,024.32 | 4,638,501.01 | | |
| | | | | | |
| July started with an operational fund bala | | ely \$380,005.32 | | | |
| Change in net cash position was +\$2,330. | | | | | |
| Balance of the escrow trust fund is \$1,939 | • | | | | |
| Five months into the fiscal year, the budg | et variance is -%32 | less than planned | | | |
| 1. 10704 | | | | | |
| updated 8.7.24 | | | | | |

Staffing:

- <u>Health</u>: Staff are generally in good health.
- <u>Personnel Manual</u>: The rewrite of the personnel manual is temporarily on hold until benefits are chosen. Earned Sick and Safe Time changes have been incorporated into the new manual and staff have been informed of changes already in effect.
- Staff Availability:
 - Over the month of August, the District staffing will be at 87%
- Vacancies/New Hires
 - One intern position has been extended, on a limited basis (16 hrs/wk), for special projects through the end of the year.

MEETING DATE: August 12, 2024

AGENDA NUMBER: 7

ITEM: Advisory Committees Report

AGENDA: Policy Discussion Information

ACTION REQUESTED

Receive Report

BACKGROUND

The Citizen Advisory Committee (CAC) did not meet in July. The Technical Advisory Committee (TAC) met on July 11th.

- The next CAC meeting scheduled: August 13th at 4:30 pm hybrid with Zoom.
- The next TAC meeting scheduled: September 12th at 8:30 am hybrid with Zoom.

ISSUES/CONCERNS

Citizen Advisory Committee (CAC)

The CAC did not meet in the month of July.

Technical Advisory Committee (TAC)

The majority of the TAC was present at the meeting; absent were Board of Soil and Water Resources (BWSR) and Columbus.

1. Management Situation

Jon Janke provided the TAC with a brief update on recent weather and hydrology.

The District is seeing a lot of water appropriation permits coming in. The recent rains have made construction challenging but for the most part sites are keeping good erosion control and dewatering practices.

2. Concerns

Jon Janke gave a brief update on the Lower Coon Creek Corridor Restoration Project at Coon Rapids Dam Regional Park stating that all landowner agreements are now in place with construction scheduled to begin next week.

Tim Himmer of Coon Rapids mentioned that the culvert work near Moore Park on Magnolia Street is moving forward.

Justine Dauphinais informed the TAC that the feasibility study for the Pleasure Creek Smart Outlet has come out favorably and is now moving into concept design.

Megan Hedstrom of Blaine noted that the Alternative Urban Areawide Reviews (AUAR) for Northtown Mall and Blaine Town Center are on the agenda for the July 15th council meeting. A building permit for the Asia Mall has been received. Ground truthing of storm pipe network in and around the Blaine Town Center area is underway.

Dave Berkowitz of Andover announced that Andover has received a grant from the DNR for the Coon Creek Corridor Trail. In 2025 the City will be building the trail along the north side of Coon Creek from Prairie Road to the Shadowbrook North Development. Survey work will start this fall.

3. Briefs

a. Changes to the Wetland Conservation Act (WCA)

Erin Margl walked the TAC through some of the changes that are most pertinent to the group and provided a written summary of BWSR's write up.

b. Hydrology Model

Jon Janke explained that the District has been using an xpswmm model for many years as a regional model for the 100-yr flood. However, xpswmm is beginning to get phased out and will soon become obsolete. As such, the District is currently exploring options for new regional models that will meet the District's current and emerging needs.

c. Comprehensive Plan

Jon Janke reminded the TAC of the Comprehensive Plan Update process that has happened to-date, thanking those who submitted comments. A public hearing on those comments, and the District's responses, is scheduled for July 29th.

Chris Lord inquired about any changes that have been made to the budget as a result of comments received. Jon Janke confirmed that to his knowledge no changes have been made to the budget based on the comments received on the comprehensive plan.

4. Other Water Management Concerns

a. EPA Chemicals of Emerging Concern (CEC) and 6PPD-quinone

Justine Dauphinais recapped the information shared at the last TAC meeting.

5. Announcements

a. Salt Symposium

Jon Janke informed the TAC that the early bird registration deadline for the Salt Symposium has been extended to Friday, July 12th.

b. Minnesota Clean Sweep Monthly Seminars

Justine Dauphinais shared information regarding the Minnesota Clean Sweep monthly seminar series, noting that the August seminar will be touching on equipment in relation to both salting and sweeping.

RECOMMENDATION

Receive Report

MEETING DATE: August 12, 2024

AGENDA NUMBER: 8

ITEM: Bills to Be Paid

FISCAL IMPACT: Budgeted POLICY IMPACT: Policy

REQUEST

Approve bills

BACKGROUND

Claims totaling \$273,937.96 on the following disbursement(s) list will be issued and released upon Board approval.

| Vendor | Amount |
|---|------------|
| V0008US BANK | 9,159.53 |
| V0015ANOKA COUNTY MN | 161,117.33 |
| V0015ANOKA COUNTY MN | 1,700.00 |
| V0015ANOKA COUNTY MN | 1,700.00 |
| V0026CITY OF COON RAPIDS | 3,395.00 |
| V0027CITY OF FRIDLEY | 3,500.00 |
| V0030CONNEXUS ENERGY | 304.48 |
| V0033DELL MARKETING LP | 1,424.62 |
| V0033DELL MARKETING LP | 1,424.62 |
| V0037ECM PUBLISHERS INC | 2,884.80 |
| V0047AH IND SCHOOL DIST 11 | 3,990.00 |
| V0052LOFFLER COMPANIES INC | 102.50 |
| V0062NORTH VALLEY INC | 2,900.00 |
| V0080METROPOLITAN COUNCIL | 5,900.00 |
| V0090CENTERPOINT ENERGY-UTILITY | 30.47 |
| V0102US GEOLOGICAL SURVEY | 8,047.25 |
| V0103BANKERS ADVERTISING CO | 2,299.20 |
| V0103BANKERS ADVERTISING CO | 439.51 |
| V0111WELL GROOMED LAWNS INC | 860.00 |
| V0128YTS COMPANIES LLC | 2,231.25 |
| V0138RMB ENVIRONMENTAL LABORATORIES INC | 2,088.00 |
| V0195STANTEC CONSULTING SERVICES INC | 2,871.90 |
| V0195STANTEC CONSULTING SERVICES INC | 7,379.50 |
| V0195STANTEC CONSULTING SERVICES INC | 27,488.28 |
| V0195STANTEC CONSULTING SERVICES INC | 2,526.50 |
| V0242METRO I NET | 5,398.00 |
| V0247POOP 911 OF MPLS STP LLC | 864.25 |
| V0313TURFCO MANUFACTURING INC. | 448.51 |
| V0314VEIT & COMPANY INC | 1,700.00 |
| V0315HFN PROPERTIES LLC | 7,891.65 |
| V0316PAUL HENNUM | 1,870.81 |
| Grand total | 273,937.96 |

| Created on: 1008284 | Coon Creek Watershed District | | | | | | | | | |
|--|--|--|--|--|--|---|--|----------------------|---|--|
| | 8/7/2024 | Bill number | | Fund name | Department name | | Capital Project ID | | | |
| | Vendorname ECMPUBLISHERS INC | 1008284 | 7/19/2024 | | Administration | 61559 | Capital Project ID | Grant ID | Transaction amount | ACCT365339 AD 1407900 COMP DRAFT24-33 |
| Sumfor 1008284 1009693 | | | | | | | | | 217.80 | |
| Sumfor 1009693 | ECMPUBLISHERS INC | 1009693 | 7/24/2024 | General Fund | Public & Governmental Affaira | 61549 | PROJ24-612 | G22-001 | 154.00 154.00 | ACCT365339 AD88137 DOORHANGERS |
| 1009694 | ECMPUBLISHERS INC | 1009694 | 7/24/2024 | General Fund | Public & Governmental Affaira | 61549 | FROJ24-612 | G22-001 | | ACCT365339 AD88136 PWSYARD SIGNS |
| Sumfor 1009694 1009695 | ECMEN IRLISHERS INC | 1009695 | | | | | | G22-001 | 385.00 | |
| Sumfor 1009695 1009696 | ECMPOBLISHERS INC | 1009695 | 7/24/2024 | Cleneral Fund | Public & Governmental Affairs | 61549 | PROJ24-612 | G22-001 | 87.00 | ACCT365339 AD88138 PWSBOOKMARKS |
| Sumfor 1009696 | ECMPUBLISHERS INC | 1009696 | 7/24/2024 | General Fund | Public & Governmental Affairs | 61549 | PROJ24-612 | G22-001 | 376.00 376.00 | ACCT 365339 AD 88142 PWS STICKERS |
| 1009697 | ECMPUBLISHERS INC | 1009697 | 7/24/2024 | General Fund | Public & Governmental Affaira | 61549 | PROJ24-612 | G22-001 | | ACCT 365339 AD 88143 PWS STICKERS |
| Sumfor 1009697 1009723 | | | | | | | | | 472.00 | |
| Sumfor 1009723 | ECMPUBLISHERS INC | 1009723 | 7/29/2024 | General Fund | Public & Governmental Affairs | 61549 | PROJ24-612 | G22-001 | 80.00 | ACCT365339 AD88196 PWS BLAINENTU |
| 1009724 Sumfor 1009724 | ECMPUBLISHERS INC | 1009724 | 7/29/2024 | General Fund | Public & Governmental Affairs | 61549 | PROJ24-612 | G22-001 | 1,028.00 | ACCT 365339 AD 88144 PWS POSTCARDS |
| 1009725 | ECMPUBLISHERS INC | 1009725 | 7/20/2024 | Connect Euro | Public & Governmental Affairs | 61549 | PROJ24-612 | G22-001 | | ACCT365339 AD88195 PWS CRNTU |
| Sumfor 1009725 1047-166981 | | | | | | | | | 85.00 | |
| | POOP911 OFMPLSSTPLLC POOP911 OFMPLSSTPLLC | 1047-166981 1047-166981 | 8/1/2024 8/1/2024 | General Fund General Fund | Public & Governmental Affaira Administration | 61549 61549 | PROJ23-602 PROJ23-602 | G22-001-M G22-001 | 675.75 | 5 WEEKS CLEAN UP SEPWICE AUG 24 5 WEEKS CLEAN UP SEPWICE AUG 24 |
| Sumfor 1047-166981 10761354869 | | | | | | | | | 864.25 | |
| Sumfor 10761354869 10761354885 | DELLMARKETINGLP | 10761354869 | 7/20/2024 | General Fund | Administration | 61101 | | | 1,424.62 | POW183474 DELL LAPTOP & BASE t |
| Sumfor 10761354885 | DELLMARKETINGLP | 10761354885 | 7/20/2024 | General Fund | Administration | 61101 | | | 1,424.63 | POW183473 DELL LAPTOP & BASE |
| 10982621-0724 | CENTERPOINT ENERGY-UTILITY | 10982621-0724 | 7/18/2024 | General Fund | Administration | 62225 | | | | ACCT 10982621-4 CCWD.LILY2024 |
| Sumfor 10982621-0724 2116 | | | | | | | | | 30.47 | · |
| Sumfor2116 | METROINET | 2116 | 8/1/2024 | General Fund | Administration | 63066 | | | 5,398.00 5,398.0 0 | MTHLYIT SEPMICES AUG 24 |
| 2263603 | STANTEC CONSULTING SERVICES INC | 2263603 | 7/26/2024 | General Fund | Water Quality | 63595 | PROJ-24-516 | G23-001-M | 2,706.90 | CRDLCCCRFRO.I227708629 WQ 7/24 |
| Sumfor2263603 2263988 | STANTEC CONSULTING SERVICES INC | 2263603 | 7/26/2024 | General Fund | Water Quality | 63595 | PROJ-24-522 | | 165.00 2,871.90 | PCPOND OUTLETMOD PROJE27706629 WQ 7/24 |
| | | 2263988 2263988 | 7/20/2024 | Connect Europi | Administration Planning | 63246 63246 | PROJ24-302 | | 147.00 | CENL ENCRFROLE27706627 FLAN7/24 CCD39 PFOLE27706627 FLAN7/24 |
| | STANTEC CONSULTING SERVICES INC STANTEC CONSULTING SERVICES INC STANTEC CONSULTING SERVICES INC | 2263988 2263988 2263988 | 7/26/2024 7/26/2024 | General Fund General Fund General Fund | Planning Planning Planning | 63246 63246 | PROJ24-302 PROJ24-310 PROJ24-311 | | 4,557.00 |) CD 39 FFCJE27708627 FLAN 7/24) MODEL INPMMTFPCJE27708627 FLAN 7/24) AOP PH2 PFCJE27708627 FLAN 7/24 |
| Sumfor2263988 | STANTEC CONSULTING SERVICES INC | 2263988 2263988 | 7/26/2024 | General Fund | Administration | 63246 | 27-911 | | 1,666.00 7,379.50 | GENL ENGRPRIO.227708627 PLAN 7/24 |
| 2263989 | STANTEC CONSULTING SERVICES INC | 2263989 | 7/26/2024 | General Front | Watershed Development | 63246 | | | | 3 PROJE27708623 PERMIT PROG7/24 |
| Sumfor 2263989 | | | | | | | | | 27,488.28 | |
| Sumfor 2264000 | STANTEC CONSULTING SERVICES INC | 2264000 | 7/29/2024 | General Fund | Watershed Development | 63246 | | | 2,526.50 2,526.50 | PROJE27708624 WCA7/24 |
| 25648 | WELL GROOMED LAWNS INC | 25648 | 7/30/2024 | General Fund | Administration | 61250 | | | 860.00 | CCWDMOWJULY2024 |
| Sumfor 25648 | | | | | | | | | 860.00 | |
| Sumfor34477 | YISCOMPANIESLLC | 34477 | 7/10/2024 | General Fund | Operations & Maintenance | 61549 | PROJ24-421 | | 2,231.25 2,231.25 | 24NONROUTMAINT ISS 24-085 LCC FORESTRY |
| 4763441 | LOFFLERCOMPANIES INC | 4763441 | 8/1/2024 | General Fund | Administration | 62124 | | | 102.50 | ACCTCC16 CCWD.JJLY24 |
| Sumfor4763441 828846-2537587/24 | | | | | | | | | 102.50 | |
| Sumfor828846-2537587/24 | CONNEXUS ENERGY | 828846-2537587/24 | 7/24/2024 | General Fund | Administration | 62226 | | | 304.48 304.48 | ACCT828846-253758 CCWD.J.L.Y24 |
| 837054 Sumfor837054 | BANKERS ADVERTISING CO | 837054 | 7/18/2024 | General Fund | Public & Governmental Affairs | 61549 | PROJ24-612 | G22-001 | 2,299.20 | ACCTW191903 ORDERW629836 POOCHINTS |
| 837333 | BANKERS ADVERTISINGCO | 837333 | 7/25/200 | General C | Public & Covernmental Affairs | 61549 | PROJ-24-612 | G22-001 | 2,299.20 | ACCTW191903 ORDERW630306 KEYCHAIN |
| Sumfor837333 91176576 | BANKENSADVERTISINGCO | 637333 | 7725/2024 | Canena runo | PUBLIC & COMPRIMENTAL ATTAINS | 61549 | PT40.024-612 | G22-001 | 439.51 | |
| 91176576 Sumfor91176576 | USGEOLOGICAL SURVEY | 91176576 | 7/10/2024 | General Fund | Water Quality | 61549 | PROJ-24-515c | | 8,047.25 8,047.25 | CUST 6000007418 3FD QTR2024 |
| B013607 | RMB ENVIRONMENTAL LABORATORIES INC | P013607 | 7/22/2024 | General Fund | Water Cuality | 61549 | PROJ-24-515b | | | WOB013607 MONITORING |
| Sumfor B013607 B013779 | THE STATE OF THE S | 13007 | 772272024 | California P Grid | - Vinta Collins | 01548 | 110024-5130 | | 207.00 | o vectoristic vect |
| Sumfor B013779 | RMB ENVIRONMENTAL LABORATORIES INC | B013779 | 7/25/2024 | General Fund | Water Quality | 61549 | PROJ-24-515b | | 1,125.00 | WOB013779 MONITORING |
| B013835 | RMB ENVIRONMENTAL LABORATORIES INC | B013835 | 7/25/2024 | General Fund | Water Quality | 61549 | PROJ-24-515b | | | WOB013835 MONITORING |
| Sumfor B013835 B013836 | | | | | | | | | 24.00 | |
| Sumfor B013836 | FIMB ENVIRONMENTAL LABORATORIES INC | B013836 | 8/1/2024 | General Fund | Water Quality | 61549 | PROJ24-515b | | 207.00 | WOB013836 MONITORING |
| E013981 | RMB ENMRONMENTAL LABORATORIES INC | B013981 | 8/6/2024 | General Fund | Water Quality | 61549 | PROJ24-515b | | 237.00 | WOB013981 MONITORING |
| Sumfor B013981 B013982 | | | | | | | | | 237.00 | |
| Sumfor B013982 | RMB ENVIRONMENTAL LABORATORIES INC | B013982 | 8/5/2024 | General Fund | Water Quality | 61549 | PROJ24-515b | | 144.00 | WOB013982 |
| E013983 Sumfor E013983 | RMB ENVIRONMENTAL LABORATORIES INC. | B013983 | 8/5/2024 | General Fund | Water Quality | 61549 | PROJ24-515b | | 144.00 | WOB013983 MONITORING |
| CCWD-0724 | ANOKACOUNTYMN | CCWD-0724 | 0.000000 | | Administration | 60720 | | | | DENTALINS SALARVIBENEFITS EXP. JULY2024 |
| | ANIOKA COLINIDAMI | CCMD 0734 | 8/7/2024 | General Fund | Administration | 60716 | | | 8,951.57 114.939.56 | ERABA ARYBENETIS EM-LLY2024 SALARYSELETIS EM-LLY2024 LIFE INSSALARYSELETIS EM-LLY2024 LIFE INSSALARYSELETIS EM-LLY2024 |
| | | CCWD-0724 CCWD-0724 CCWD-0724 | 8/7/2024 | General Fund | Administration Administration Administration | 60110 60715 60714 | | | | |
| | ANOKACOUNTYMN ANOKACOUNTYMN | CCWD-0724 CCWD-0724 | 8/7/2024 | General Fund General Fund | Administration Administration | 60713 60260 | | | 5,927.7 | HRASALARY/BENEFITS DIP_LILY2024 TEMPSALARY/SALARY/BENEFITS DIP_LILY2024 |
| | | | | General Fund | Administration | 60721 | | | | LITDINSSALARYBENEFITSER-LLLY2024 PROFFIESSALARYBENEFITSER-LLLY2024 PERA SALARYBENEFITSER-LLLY2024 |
| | ANOKACOUNTYMN | CCWD-0724 | 8/7/2024 | | | 60717 | | | | PERASALARY/BENEFITS EXP-JULY2024 |
| Sumfor CCWD-0724 | ANOKACOUNTYMN | CCWD-0724 CCWD-0724 CCWD-0724 | 8/7/2024 8/7/2024 8/7/2024 | General Fund General Fund | Administration | | | | 8,747.99 161,117.33 | s ⁱ |
| Sumfor CCWD-0724 Charge payoffs - 752 | ANOKACOUNTYMN ANOKACOUNTYMN ANOKACOUNTYMN | CCWD-0724 CCWD-0724 CCWD-0724 | 8/7/2024 8/7/2024 8/12/2024 | General Fund | | | | | 161,117.33 | |
| Sumfor CCWD-0724 Charge payoffs - 752 | ANCKACCUNTYMN ANCKACCUNTYMN ANCKACCUNTYMN USBANK USBANK USBANK | CCWD-0724 CCWD-0724 CCWD-0724 Charge payoffs - 752 Charge payoffs - 752 Charge payoffs - 752 | 8/7/2024 8/7/2024 8/12/2024 8/12/2024 8/12/2024 | General Fund General Fund | Administration Administration Administration | 20020 20020 20020 | | | 161,117.33 112.84 38.00 505.41 | |
| Sumfor CCWD-0724 Charge payoffs - 752 | ANCKACOLITYMN ANCKACOLITYMN ANCKACOLITYMN USBANK USBANK USBANK USBANK USBANK | CCWD-0724 CCWD-0724 CCWD-0724 Chargepayoffs - 752 | 8/7/2024 8/7/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 | General Fund General Fund General Fund General Fund General Fund | Administration Administration Administration Administration Administration Administration | 20020 20020 20020 20020 20020 | | | 161,117.33 112.84 38.00 505.41 1,311.82 49.95 | |
| Sumfor CCWD-0724 Charge payoffs - 752 | ANDKACOUNTYNN ANDKACOUNTYNN ANDKACOUNTYNN USBANK USBANK USBANK USBANK USBANK USBANK USBANK | CCWD-0724 CCWD-0724 CCWD-0724 Chargepayoffs - 752 | 8/7/2024 8/7/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 | General Fund General Fund General Fund General Fund General Fund | Administration Administration Administration Administration Administration Administration | 20020 20020 20020 20020 20020 20020 20020 | | | 161,117.33 112.84 38.00 505.41 1,311.85 49.95 | |
| Sumfor CCWD-0724 Charge payoffs - 782 | ANDIGOGRAPHINA ANDIGOGRAPHINA ANDIGOGRAPHINA USBANK USBANK USBANK USBANK USBANK USBANK USBANK USBANK | CCWD-0724 CCWD-0724 CCWD-0724 CCWD-0724 Charge psyoffs - 752 | 8/7/2024 8/7/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 | Qineral Fund Qineral Fund Qineral Fund Qineral Fund Qineral Fund Qineral Fund Qineral Fund Qineral Fund | Administration | 20020 20020 20020 20020 20020 20020 20020 20020 20020 | | | 161,117.33 112.84 38.00 505.47 1,311.86 49.96 310.00 145.48 129.47 | |
| Sumfor CCMD-0724 Change payoffs - 782 | ANDIACOUNTYMA ANDIACOUNTYMA ANDIACOUNTYMA ANDIACOUNTYMA USBANK USBANK USBANK USBANK USBANK USBANK USBANK USBANK USBANK USBANK USBANK USBANK USBANK USBANK USBANK USBANK | CCWD-0724 CCWD-0724 CCWD-0724 CCWD-0724 Charge payoffs - 752 | 8/7/2024 8/7/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 | Qineral Fund Qineral Fund | Administration | 20020 20020 20020 20020 20020 20020 20020 20020 20020 20020 20020 20020 | | | 161,117.3: 112.8- 38.00 505.4- 1,311.82 49.95 310.00 145.44 129.47 84.22 30.44 | |
| Sumfor CCWD-0724 Charge payoffs-752 | ANGOLOGIANTAN ANGOLOGIANTAN ANGOLOGIANTAN LIBIDARA | CCMND-0724 CCMND-0724 CCMND-0724 CCMND-0724 CDMS-0724 CD | 8/7/2024 8/7/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 | Ceneral Fund Ceneral Fund | Administration | 20020 20020 20020 20020 20020 20020 20020 20020 20020 20020 20020 20020 20020 20020 | | | 161,117.3: 112.8: 38.00 505.4: 1.311.8: 49.92: 310.00 145.44: 129.4: 84.20: 30.48: 49.22: 86.4: 295.5: | |
| Sumfor CCWD-9724 Charge payoffs - 752 | ANGOLOGIANTAN ANGOLOGIANTAN ANGOLOGIANTAN LIBIDARK | COMD-0724 COMD-0724 COMD-0724 COMD-0724 COMD-0724 Charge payoffs - 752 | 8/7/2024 8/7/2024 8/7/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 | General Fund General Fund | Administration | 20020 20020 20020 20020 20020 20020 20020 20020 20020 20020 20020 20020 20020 20020 20020 20020 20020 | | | 161,117.3: 112.8: 38.00 505.4: 1,311.8: 49.92 310.00 145.44 129.4: 84.22 30.44 49.22 86.44 295.5: 70.11 17.90 | |
| Sumfor CCWD-9724 Change payoffs - 752 | ANGOLOGIANTAN ANGOLOGIANTAN LEBANA | COMD-0724 COMD-0724 COMD-0724 COMD-0724 Charge payoffs - 752 Charge payo | 8/7/2024 8/7/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 | Comeral Fund Ceneral Fund | Administration | 20020 20020 20020 20020 20020 20020 20020 20020 20020 20020 20020 20020 20020 20020 20020 20020 20020 20020 20020 | | | 161,117.3: 112.8: 38.00 5.31.311.8: 49.90 510.00 145.4: 129.4: 64.4: 30.4: 49.9: 66.4: 295.5: 77.7: 57.7: 148.5: 148.5: 84.00 | |
| Sunfor CCWD-0724 Charge payoffs - 762 | ANGOLOGIANTAN ANGOLOGIANTAN ANGOLOGIANTAN LEBARA | COMID-0724 | 8/7/2024 8/7/2024 8/12/2024 | Comeral Fund | Administration | 20020 | | | 161,117.3: 38: 05 505.4* 1.311.8: 49: 05 310.00 145.44 129.43 94.20 95.20 86.44 205.5: 70.15 17.90 59.41 | |
| Sumfor COWD-9724 Change payoffs - 782 | ANGOLOGIANTAN ANGOLOGIANTAN ANGOLOGIANTAN LEBDARK LEBD | COM-0724 COM | 8/17/2024 8/12/2024 | Cemeral Fund | Administration Admini | 20020 | | | 161.177.3 112.8 39.0 4 505.4 1.311.6 49.0 310.0 145.4 49.2 20.5 50.5 19.0 19.0 19.0 19.0 19.0 19.0 19.0 19.0 | |
| Sumfor CCWD-9724 Chunge payoffs - 792 | ANGOLOGIANTAN ANGOLOGIANTAN LEBANK | COMMOTOR COM | 8/17/2024 8/12/2024 | Cemeral Fund | Administration United States St | 20020 | | | 161.177.3 38.00 505.4 1.311.66 310.00 145.44 125.44 125.45 145.45 145.45 145.45 146.55 | |
| Sumfor COWD-9724 Change payoffs - 792 | ANGOLOGIANTAN ANGOLOGIANTAN ANGOLOGIANTAN LIBIDARA | COMMO 2724 Churapenine ffa - 782 | 8/7/2024 8/7/2024 8/12/2024 | Cemeral Fund | Administration Admini | 20020 | | | 161,177.3 38,00 505.4 1,311.6 310,00 145.4 125.4 | |
| Bumfor COWD-9724 Change payoffs - 792 | ANGOLOGIANMAN AN | COMMO 2724 Churaperine ffe - 752 | 8/7/2024 8/7/2024 8/12/2024 8/12/2024 8/12/2024 8/12/2024 9/12/2024 9/12/2024 9/12/2024 8/12/2024 | Centered Fund Ce | Administration Conference United and Development Operations & Manistration Operations & Manistration Operations & Manistration Operations & Manistrations Operations & Operations | 20020 | | | 112.8 38.00 505.4* 1.3.05.4 1. | |
| Bumfor COWD-9724 Chunga payoffs - 782 | ANGOLOGIANMAN ANGOLOGIANMAN ANGOLOGIANMAN ANGOLOGIANMAN LEBANG | COMB-0724 COMPO-0724 Charge pringerfia - 752 Charge pringerfia - 752 | 8/7/2024 8/7/2024 8/1/2/2024 | Canness Fund Ganess Fund | Administration Observation Administration Observation Administration Observation | 20020 | | | 101.117.2.8 | |
| Sumfor CCWD-9724 Charge payoffs - 752 | ANGOLOGIANTAN ANGOLOGIANTAN ANGOLOGIANTAN LEBANK | COMMOTOR COMMOTOR COMMOTOR COMPONITION COM | 8/7/2024 8/7/2024 8/12/2024 | Ceneral Fund General Fund | Administration Object Conference Uniformatical Object Conference Object Confer | 20020 | | | 112.8-330.6 300.4 100.4 | |
| Bumfor COND-9724 Change payoffs - 792 | ANGOLOGIANMAN AN | COMMO 2724 Churape mined fra . 752 Churape m | 8/1/2/024 | Cameral Fund Canness Fund Canne | Administration Admini | 20020 | | | 112.8-200 (1.00 (1 | |
| Sumfor COWD-9724 Ohinga pagadfu - 752 | MEGNACIONIMAN MACINACIONIMAN MACINACIONIMAN LEBANK | COMMO 2794 COMMO 2794 Charge pringerfia - 782 | 8/1/2/024 | Cemeral Fund. Canness Fund. Ca | Administration Conference Administration Administration Administration Conference Co | 20020 | | | 112.8 38.0 49.9 49.9 49.9 49.9 49.9 49.9 49.9 49 | |
| Sumfor COWD-9724 Ohinga pagadfin 752 | MEGNACIONIMAN MEGNACIONIMAN MEGNACIONIMAN LEBANK LEBANK LEBANK LEBANK LEBANK LEBANK LEBANK LEBANK LEBANK | COMMO 2724 COMMO 2724 Charles princeffs - 752 | 8/12/2024 | Canward Fund Canwa | Administration Composition Administration Composition Administration Composition Administration Composition Administration Administration Administration Composition Administration Composition | 20020 | PNOJ24-520 | | 112.8-38.00 | |
| Bumfor COWD-0724 Charge payoffs - 792 | ANGORACIONIMA ANGORACIONIMA ANGORACIONIMA ANGORACIONIMA LIBRARE | COMMO 2724 Churapenine F. 782 | 8/12/2024 8/12/2 | Canward Fund Canwa | Administration Admini | 20020 | PFG124-520 | | 112.8- 380.00 1.311.86 380.00 1.311.86 380.00 1.48.46 1.50.41 | |
| Bumfor COWD-9724 Change payoffs - 782 | ANGOLOGIANTAN ANGOLOGIANTAN ANGOLOGIANTAN LEBARK LE | COMMO 2794 COMMO 2794 Churape properfier 7,782 | 8/19/2024 | Canward Fund Claneard Fund Cla | Administration Conference Administration Administration Administration Administration Administration Administration Conference C | 20020 | | GSS-001 | 112.8 380.0 1.311.8 40.9 310.4 1.311.8 40.9 310.4 1.311.8 40.9 310.4 1.311.8 40.2 50.4 1.311.8 40.2 50.4 1.311.8 40.2 50.4 1.311.8 1.3 | |
| Sumfor CCWD-9724 Chunge payoffs - 792 | ANCHOLOGISTAMA ANCHOLOGISTAMA ANCHOLOGISTAMA ANCHOLOGISTAMA LEIDARA LE | COMMO 0724 Churape prince ffa - 752 Churap | 8/12/2024 | Canward Fund Canwa | Administration Conference Administration Administration Conference | 20020 | | G22-001 | 112.8-38.06.112.8- | |
| Sumfor Charge payoffs - 752 PAN 13-064 | MACHACOLOMINAN ANCIACOLOMINAN MACHACOLOMINAN LEBARA | COMMO 0724 Churape princeffe - 752 Churape p | 8/17/2024 8/13/2024 | Canware Fund Canwa | Administration Admini | 20020 | | CE2-001 | 111.2.8 38.00 38.00 3.10 3.11.8 40.00 3.10 3.11.8 40.00 3.10 40.00 3.10 40.00 | PTS-064 ESCROWEET-ENAMMENDOWSSOUTH |
| Samfor COWD-9724 Change payoffs - 782 Samfor Change payoffs - 782 Samfor PWN 13-084 | ANGORACIONIMAN ANGORACIONIMAN ANGORACIONIMAN ANGORACIONIMAN LEBARK LEBAR | COMMO 2724 Chursperimenter 782 | 8/12/2004 | Canward Fund. | Administration Conference Conferen | 20020 | | G22-001 | 112.8- 380.00 1.311.86 380.00 1.311.87 380.00 | PTI3-064 ESCROWINEF-HENNIAMEACOWS SOUTH |
| Sumfor Charge payoffs - 782 Sumfor Charge payoffs - 782 PAN 13-004 Sumfor PAN 13-070 | MACHACOLOMINAN ANCIACOLOMINAN MACHACOLOMINAN LEBARA | COMMO 0724 COMMO 0724 Charape prince file 1782 Charape prince file | 8/12/2004 | Canward Fund. | Administration Admini | 20020 | | G22-001 | 112.8- 380.00 1.311.86 380.00 1.311.87 380.00 | PTI3-064 ESCROWRET-RENNAMEADOWS SOUTH |
| Sumfor Charge payoffs - 752 Sumfor Charge payoffs - 752 PAN 13-054 Sumfor PAN 13-050 Sumfor PAN 13-070 Sumfor PAN 13-070 | ANGORACIONIMAN ANGORACIONIMAN ANGORACIONIMAN ANGORACIONIMAN LEBARK LEBAR | COMMO 2724 Chursperimenter 782 | 8/1/2024 8/1/2024 8/1/2024 8/1/2024 8/1/2024 8/1/2024 8/1/2024 8/1/2024 8/1/2024 8/1/2024 8/1/2024 8/1/2024 8/1/2024 8/1/2024 8/1/2024 | Canward Fund. Ca | Administration Conference Conferen | 20020 | | G22-001 | 11-11-2-8 | PTS-0004 ESCROWINET-RENNLAMMEADOWS/SOUTH PTS-070 ESCROWINET-RODEN POPEST NORTH PTS-070 ESCROWINET-CANCLENCYEEX |
| Samfor COMD-9724 Change payoffs - 792 Samfor Charge payoffs - 792 PMN 13-094 Samfor PMN 13-094 Samfor PMN 13-070 Samfor PMN 13-070 Samfor PMN 13-076 | MEGNACIONIMAN MEGNACIONIMAN MEGNACIONIMAN LEBDARK LEBORK LEBDARK LEBD | COMMO 0724 COMMO 0724 Charapementer 782 Charapementer 783 Charapementer 783 Charapementer 783 Charapementer 783 Charapementer 783 Charapem | 8/1/2024 8/1/2024 8/1/2024 8/1/2024 8/1/2024 8/1/2024 8/1/2024 8/1/2024 8/1/2024 8/1/2024 8/1/2024 8/1/2024 8/1/2024 8/1/2024 8/1/2024 8/1/2024 | Canward Fund. Ca | Administration Operations & Manifesters United States Administration United States Uni | 20020 | | C02-001 | 112.8- 380.00 1.311.86 380.00 1.311.87 1 | P13-004 ESCROWIEF-FERNLAMEADOWSSCUTH P13-076 ESCROWIEF-ROCKLENCREST NORTH |
| Bumfor Charge payoffs - 782 Bumfor Charge payoffs - 782 PAN 13-064 Bumfor PAN 13-074 PAN 13-070 Bumfor PAN 13-070 PAN 13-076 Bumfor PAN 13-076 PAN 13-077 | MEGNACIONIMAN MEGNACIONIMAN MEGNACIONIMAN LEBARK LEBARK LEBARK LEBARK LEBARK LEBARK LEBARK LEBARK LEBARK LEBARK LEBARK LEBARK LEBARK LEBARK LEBARK LEBARK LEBARK LEBARK LEBARK LEBARK LEBARK LEBARK LEBARK LEBARK LEBARK LEBARK | COMMO 0724 COMMO 0724 Charapementer 782 | 8/1/2024 8/1/2024 8/1/2024 8/1/2024 8/1/2024 8/1/2024 8/1/2024 8/1/2024 8/1/2024 8/1/2024 8/1/2024 8/1/2024 8/1/2024 8/1/2024 8/1/2024 8/1/2024 | Canward Fund. Ca | Administration Conference United States Administration United States Administration United States | 200220 20020 200220 200 | | C02-001 | 112.8- 380.00 1.311.86 380.00 1.311.87 1 | PTS-0004 ESCROWINEF-RENNAMINEADOWS SOUTH PTS-0000 ESCROWINEF-RECENT/CREST NORTH PTS-0700 ESCROWINEF-CANCLER/CREST |
| Sumfor Charge payoffs - 782 Sumfor Charge payoffs - 782 PNN 13-084 Sumfor PNN 13-084 PNN 13-070 PNN 13-070 PNN 13-070 Sumfor PNN 13-070 PNN 13-077 Sumfor PNN 13-077 Sumfor PNN 13-077 Sumfor PNN 13-077 Sumfor PNN 13-077 | MONOCOCONNYM MONOCOCONNYM MONOCOCONNYM LEBANK LEBA | COMMO 0724 COMMO 0724 Charapementer 782 Charapementer 783 Charapementer 783 Charapementer 783 Charapementer 783 Charapementer 783 Charapem | 8/13/2004 | Canward Fund. Ca | Administration Operations & Manifesters United States Administration United States Uni | 20020 | | G22-001 | 112.8 | PT3-0004 ESCROWRET-FENNAMIEADOWS SOUTH PT3-070 ESCROWRET-FEDCEN FORESTINCKRIT PT3-077 ESCROWRET-CANCLENCYEEK PT3-077 ESCROWRET-CANCLENCYEER PT3-078 ESCROWRET-CANCLENCYEER FED-CROSSTOWNBLVD |
| Sumfor Charge payoffs - 782 Sumfor Charge payoffs - 782 PAN 1-3064 Sumfor PAN 1-3064 PAN 1-3-070 Sumfor PAN 1-3-076 PAN 1-3-076 Sumfor PAN 1-3-076 Sumfor PAN 1-3-077 PAN 1-3-077 Sumfor PAN 1-3-077 PAN 1-3-078 Sumfor PAN 1-3-077 PAN 1-3-085 Sumfor PAN 1-3-085 | MONOCOCOUNTWN MONOCOCOUNTWN LEBDARK | COMMO 2724 COMMO 2724 Charape prince from 7.782 Charape prince from 7.78 | 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 | Canward Fund Canwa | Administration Water Couldity Administration | 20020 | | G22-001 | 112.8- 39.00 1.311.85 39.00 1.46.44 1.40.45 1. | P13-064 ESCROWRET-FENNAMEADOWS SOUTH P13-070 ESCROWRET-GANGLENCEST P13-070 ESCROWRET-GANGLENCEST P13-077 ESCROWRET-GANGET PIETER, CROSSTOWNELVO P13-089 ESCROWRET-GANGET PIETER, CROSSTOWNELVO |
| Sumfor Charge payoffs - 752 Sumfor Charge payoffs - 752 PAN 13-064 PAN 13-079 Sumfor PAN 13-079 PAN 13-085 Sumfor PAN 13-085 Sumfor PAN 13-085 Sumfor PAN 13-085 Sumfor PAN 13-085 | MONOCOCONNYM MONOCOCONNYM MONOCOCONNYM LEBANK LEBA | COMMO 0724 COMMO 0724 Charapementer 782 Charapementer 783 Charapementer 783 Charapementer 783 Charapementer 783 Charapementer 783 Charapem | 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 | Canward Fund Canwa | Administration United States Administration United States Administration United States Administration United States United Stat | 20020 | | CB2-001 | 112.8- 39.00 1.311.85 39.00 1.46.44 1.40.45 1. | PT3-0004 ESCROWRET-FENNAMIEADOWS SOUTH PT3-070 ESCROWRET-FEDCEN FORESTINCKRIT PT3-077 ESCROWRET-CANCLENCYEEK PT3-077 ESCROWRET-CANCLENCYEER PT3-078 ESCROWRET-CANCLENCYEER FED-CROSSTOWNBLVD |
| Sumfor Charge payoffs - 782 Sumfor Charge payoffs - 782 PAN 13-084 Sumfor PAN 13-084 Sumfor PAN 13-070 Sumfor PAN 13-070 Sumfor PAN 13-077 PAN 13-077 Sumfor PAN 13-077 Sumfor PAN 13-077 Sumfor PAN 13-077 Sumfor PAN 13-085 Sumfor PAN 13-088 | MONOCOCOUNTWN MONOCOCOUNTWN LEBDARK | COMMO 2724 COMMO 2724 Charape prince from 7.782 Charape prince from 7.78 | 8/17/2004 | Canware Fund Canwa | Administration Water Couldity Administration | 20020 | | G22-001 | 112.8 380.6 1.811.8 380.6 1.811.8 40.95 1.812.8 1.812. | P13-064 ESCROWREF-RENAMINEADOWS SCUTH P13-070 ESCROWREF-REDEN PORESTNORTH P13-070 ESCROWREF-CANCLENCREEK P13-077 ESCROWREF-CANCLENCREEK P13-065 ESCROWREF-PETROLE MIMPACT7479 ARLE ST P13-066 ESCROWREF-PETROLE MIMPACT7479 ARLE ST P13-066 ESCROWREF-PETROLE MIMPACT7479 ARLE ST P13-066 ESCROWREF-PETROLE MIMPACT7479 ARLE ST |
| Samifor Colump payoffs - 782 Samifor Charge payoffs - 782 PMN 13-084 SAMIFOR PMN 13-084 SAMIFOR PMN 13-076 SAMIFOR PMN 13-076 SAMIFOR PMN 13-076 SAMIFOR PMN 13-076 SAMIFOR PMN 13-077 SAMIFOR PMN 13-078 SAMIFOR PMN 13-088 | MONOCOUNTWN MONOCOUNTWN LEBWAY LEBW | COMMO 2724 COMMO 2724 Charape prince from 7.782 Charape prince from 7.78 | 8/17/2004 | Canware Fund Canwa | Administration United the Administration Administration Administration United Conference United Confer | 20020 | | G22-001 | 112.8- 39.00 1.311.8- 39.00 1.311.8- 39.00 1.311.8- 39.00 1.311.8- 39.04 1.39.14 1.39. | PT3-084 ESCHOWREF-FEINLAMEADOWS SOUTH PT3-076 ESCHOWREF-ENDLEMEATERSTROKEH PT3-076 ESCHOWREF-CANDET FIRE FEITL CHOSSTOWNBLAD PT3-085 ESCHOWREF-CANDET FIRE FEITL CHOSSTOWNBLAD PT3-086 ESCHOWREF-PETALLEAMEMYCT-779 ARE ST PT3-088 ESCHOWREF-PLEASLEE CHEEKEROSCONSTABILIZATION PT3-088 ESCHOWREF-PLEASLEE CHEEKEROSCONSTABILIZATION PT3-088 ESCHOWREF-CANDENDERCHEEKEROSCONSTABILIZATION |
| Sumfor Charge payoffs - 782 Charge payoffs - 782 Charge payoffs - 782 PAN 1-3-064 Sumfor PAN 13-064 PAN 13-070 Sumfor PAN 13-070 PAN 13-070 Sumfor PAN 13-070 PAN 13-075 Sumfor PAN 13-077 PAN 13-078 Sumfor PAN 13-077 PAN 13-085 Sumfor PAN 13-085 PAN 13-088 Sumfor PAN 13-088 PAN 13-081 Sumfor PAN 13-088 Sumfor | MONOCOCOLNIYMN MONOCOCOLNIYMN LEBDARK LEBDARK | COMMO 0724 COMMO 0724 Charape prince from 7.782 Charape prince from 7.78 | 8/17/2004 | Canware Fund Canwa | Administration United States Administration Administration Administration Water Couldity Water C | 20020 | | C22-001 | 112.8- 39.00 1.311.8- 39.00 1.311.8- 39.00 1.311.8- 39.00 1.311.8- 39.04 1.39.14 1.39. | P13-064 ESCROWREF-RENAMINEADOWS SCUTH P13-070 ESCROWREF-REDEN PORESTNORTH P13-070 ESCROWREF-CANCLENCREEK P13-077 ESCROWREF-CANCLENCREEK P13-065 ESCROWREF-PETROLE MIMPACT7479 ARLE ST P13-066 ESCROWREF-PETROLE MIMPACT7479 ARLE ST P13-066 ESCROWREF-PETROLE MIMPACT7479 ARLE ST P13-066 ESCROWREF-PETROLE MIMPACT7479 ARLE ST |
| Sumfor COWD-0754 Charge payoffs - 782 Sumfor Charge payoffs - 782 PAN 13-084 Sumfor PAN 13-084 PAN 13-070 Sumfor PAN 13-070 Sumfor PAN 13-070 Sumfor PAN 13-077 PAN 13-077 Sumfor PAN 13-077 Sumfor PAN 13-078 Sumfor PAN 13-088 PAN 13-088 Sumfor PAN | MONOCOCONNYM MOCOCOCONNYM MOCOCOCONNYM LEBOWS LEBO | COMMO 2724 COMMO 2724 Charape prince from 7.782 Charape prince from 7.78 | 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 | Canward Fund Canwa | Administration United the Administration Administration Administration United Conference United Confer | 20020 | | G22-001 | 112.8 380.0 1.311.8 380.0 1.311.8 40.9 3.40.4 1.20. | PI3-084 ESCROWREF-HENRARIMEADOWS SOUTH PI3-070 ESCROWREF-HEDEN FORESTROKTH PI3-076 ESCROWREF-ONGLENCREK PI3-077 ESCROWREF-ONGLENCREK PI3-086 ESCROWREF-PETROLELMIMPACT7479 ABLEST PI3-086 ESCROWREF-PETROLELMIMPACT7479 ABLEST PI3-086 ESCROWREF-PERALPETROLEMIMPACT7479 ABLEST PI3-108 ESCROWREF-ONNWAYDSINTERCEPTOR PI3-110 ESCROWREF-CONNWAYDSINTERCEPTOR PI3-108 ESCROWREF-TUPECOMPGAGON |
| Sumfor Charge payoffs - 782 Sumfor Charge payoffs - 782 PAN 13-084 Sumfor PAN 13-074 PAN 13-070 Sumfor PAN 13-076 Sumfor PAN 13-077 Sumfor PAN 13-077 Sumfor PAN 13-078 Sumfor PAN 13-088 Sumfor | MONOCOCONNYM MOCOCOCONNYM MOCOCOCONNYM LEBDANC LEBDAN | COMMO 0724 COMMO 0724 Charape prince from 7.792 Charape prince from 7.79 | 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 8/17/2024 | Canward Fund Canwa | Administration | 20030 | | G22-001 | 112.8- 39.00 1.311.8- 39.00 1.300 | PI3-084 ESCROWREF-HENRARIMEADOWS SOUTH PI3-070 ESCROWREF-HEDEN FORESTROKTH PI3-076 ESCROWREF-ONGLENCREK PI3-077 ESCROWREF-ONGLENCREK PI3-086 ESCROWREF-PETROLELMIMPACT7479 ABLEST PI3-086 ESCROWREF-PETROLELMIMPACT7479 ABLEST PI3-086 ESCROWREF-PERALPETROLEMIMPACT7479 ABLEST PI3-108 ESCROWREF-ONNWAYDSINTERCEPTOR PI3-110 ESCROWREF-CONNWAYDSINTERCEPTOR PI3-108 ESCROWREF-TUPECOMPGAGON |
| Sumfor Charge payoffs - 792 Charge poyoffs - 792 Sumfor Charge payoffs - 792 PAN 13-094 Sumfor PAN 13-094 Sumfor PAN 13-097 PAN 13-079 Sumfor PAN 13-088 | ANGOLOGIANMAN ANGOLOGIANMAN ANGOLOGIANMAN ANGOLOGIANMAN ANGOLOGIANMAN LEBANK LE | COMMO 2724 COMMO 2724 Charapa prince file. 782 Charapa prince file. | 8/17/2004 | Canward Fund Canwa | Administration | 20030 | | 022-001 | 112.8- 39.00 1.311.8- 39.00 | P13-084 ESCHOWRET-FERNAMIEADOWSSOUTH P13-076 ESCHOWRET-HODEN POPETT WORTH P13-076 ESCHOWRET-CAUSTOFFER CONTROL P13-077 ESCHOWRET-CAUSTOFFER CHOSENSTOWNELD P13-085 ESCHOWRET-CAUSTOFFER CHOSENSTOWNELD P13-086 ESCHOWRET-CAUSTOFFER P13-086 ESCHOWRET- |
| Samfor Charge payoffs - 782 Samfor Charge payoffs - 782 Samfor Charge payoffs - 782 PAN 13-084 Samfor PAN 13-084 Samfor PAN 13-070 Samfor PAN 13-088 Samfor PA | ANGOLOGIANMAN ANGOLOGIANMAN ANGOLOGIANMAN ANGOLOGIANMAN ANGOLOGIANMAN LEBANK LE | COMMO 2724 COMMO 2724 Charapa prince file 7.792 Charapa prince file 7.79 | 8/17/2004 | Canward Fund Canwa | Administration United States Administration Administration Administration Water Couldity Volume Couldity Vol | 20030 | | G22-001 | 112.8- 39.00 1.311.8- 39.00 | PT3-064 ESCROWIEF-FERNAMEACOWS SOUTH PT3-066 ESCROWIEF-ONG ENCORED CONTROL PT3-076 ESCROWIEF-ONG ENCORED CONTROL PT3-076 ESCROWIEF-ONG ENCORED CONTROL PT3-085 ESCROWIEF-FERD LEASING CONTROL PT3-085 ESCROWIEF-FERD LEASING CONTROL PT3-086 ESCROWIEF-FERD LEASING CONTROL PT3-086 ESCROWIEF-FERD LEASING CONTROL PT3-086 ESCROWIEF-FERD CONTROL PT3 |

MEETING DATE: August 12, 2024

AGENDA NUMBER:

ITEM: Approve Administrator's Employment Agreement

AGENDA: Policy

BACKGROUND

The District has employed the current Administrator since January 8, 1990. A written employment agreement has governed the relationship between the Administrator and the District Board since his hiring.

The contract was fully executed on May 9, 2016, and was in effect until May 8, 2020. At that time, a one-time 4-year extension was exercised. The employment contract of the District Administrator has expired and needs to be updated. The agreement expired May 16, 2024.

On May 13, 2024, the Board reviewed and discussed the employment contract of the District Administrator and to generally discuss employee performance. The Board also:

- 1. Acted to extend the existing agreement by approving the contract extension of 90 days.
- 2. Appoint the President and Vice-President to a committee to review the Administrator and the revised employment contract.

On June 13, 2024, the President and Vice-President met with the Administrator and conducted a performance review.

On July 8, 2024, the Board of Managers went into closed session to review the Administrator's performance review

On July 22, 2024, the President reported and gave a summary of the closed session that occurred on July 8, 2024, with the recommendation that the Board renew the Administrator's employment agreement.

ACTION REQUESTED

Approve Administrator's Employment Agreement

COORDINATION

All actions have been taken with both the Administrator's and Board knowledge.

PERTINENT FACTS

The employment agreement has been drafted, reviewed, and approved by the Board President, Vice President, District Attorney, and District Administrator.

ISSUES/CONCERNS/RISKS

- Contract extension expired August 11.
 Employment Agreement with Exhibit 1 Position Description At dais

OPTIONS FOR ACTIONS

- 1. Approve the employment agreement
- 2. Table action with specific suggestions

RECOMMENDATION

Approve Employment Agreement

MEETING DATE: August 12, 2024

AGENDA NUMBER: 10

ITEM: Approve Submittal of Draft 2024-2033 Comprehensive

Watershed Management Plan to Board of Water and Soil

Resources

AGENDA: Policy

ACTION REQUESTED

Approve final Submittal of the Draft 2024-2033 Comprehensive Watershed Management Plan to Board of Water and Soil Resources.

BACKGROUND

Minnesota Statute 103B.231 requires the development of a comprehensive watershed management plan. MS 103B and MR 8410 stipulate the content and the general process and review procedure. The Draft plan is then reviewed and approved by the Minnesota Board of Water and Soil Resources after extensive opportunity for review by the public and state agencies.

Draft Comprehensive Plan Summary:

The 2024-2033 Comprehensive Watershed Management Plan (Plan) for the Coon Creek Watershed District (CCWD), established in 1959 and spanning 107 square miles within Anoka County, is designed to address water management challenges in the watershed. Authorized by Minnesota Statute 103B.231 and Rule 8410, the Plan intends to serve as the CCWD's strategic management plan and the platform for operational planning. The district encompasses the cities of Andover, Blaine, Columbus, Coon Rapids, Fridley, Ham Lake, Spring Lake Park.

The Plan identifies priority issues through public and agency input. These priority issues include water quality impairments and groundwater and surface water interactions. The priority issue of groundwater and surface water interaction specifically involves the quality and quantity of shallow groundwater. The Plan also outlines the need for significant pollutant load (TMDLs) reductions by 2045 to address water quality impairments and issues such as shallow groundwater chloride pollution and potentially declining groundwater.

The Plan sets watershed-wide and resource-specific goals to address priority issues. The watershed-wide goals include fostering a watershed with moderate geomorphic, hydrologic, and biotic integrity relative to its natural potential condition, improving the stability of the drainage network, and fostering a watershed that exhibits physical, chemical, and biological conditions that suggest soil, riparian, and aquatic systems, while still at risk, show signs of marginal recovery in supporting beneficial uses. The resource-specific goals are discussed in more detail in the Plan.

Anticipating future trends, the district expects increased conflicts over water management, resource scarcity, technological advancements in water monitoring, and external challenges like pandemics and political constraints. These trends underscore the importance of a strategic approach to managing water resources, including the protection of public health and ecological functions.

This Plan emphasizes a Multi-Domain Management strategic approach which enables disciplined decision-making by framing risk and continually assessing progress toward legislative goals. This approach focuses on merging the capabilities of collaborators, sharing a common understanding of the water management problems, and implementing programs that transform conflict, seek collaboration and unity of effort, maintain legitimacy, and build the capacity and capabilities to pursue those shared goals.

Sustainment and administration of the plan will require a substantial investment over the next 10 years, with revenue sources including grants, intergovernmental sources, and the CCWD tax levy. Collaboration with city engineers, public works directors, and various organizations is key to the Plan's implementation, alongside annual assessments to adjust priorities and methods. The CCWD faces significant risks and will seek to extend the EPA's 2045 deadline to meet TMDL pollutant reduction goals, increase funding levels, and reclassify impaired waters based on use attainability principles.

COORDINATION

To prioritize and sort through the priority water resource issues, develop a common understanding of those priorities, the connection of the priorities to other demands and concerns about water resources, the District:

- Held 69 meetings with citizens, technical professionals, city departments and staff and state and federal agency personnel. These meetings included discussions at Citizen Advisory Committee meetings and Technical Advisory Committee Meetings.
- Conducted surveys of the public, local professionals, and other councils and Boards.
- Received and responded to 298 official comments on the draft comprehensive plan.
- Held a public hearing on the draft plan.

PERTINENT FACTS

On May 3, 2022, the notice of intent to plan was released and a public scoping process was initiated for the Update of the Comprehensive Plan. The public and agency comment period ended July 2, 2022.

On January 23, 2023, the Board held its Initial Planning Meeting to receive any additional comments on water resource problems, issues, or concerns.

On September 25, 2023, the Board of Managers adopted resolution 2023-04 requesting an extension of the District's current comprehensive plan. The Board of Water and Soil Resources approved that request on October 30, 2023.

On December 21, 2023, the Board approved release of the Draft Comprehensive Plan for public and agency review. That review period ended February 23, 2024.

The District received 298 public comments from nine state and local agencies. The District also received informal comments from staff and one Citizens Advisory Committee (CAC) member. A summary of these comments was presented to the Board on March 11th, 2024.

On July 29, 2024, the Board held a public hearing to receive comments on the Draft 2024-2033 Comprehensive Watershed Management Plan. No new comments were submitted by the public.

The final Draft 2024-2033 Comprehensive Watershed Management Plan can be found here: https://www.cooncreekwd.org/wp-content/uploads/2024/08/2024-33-CCWD-Comprehensive-Plan Final-Draft.pdf

ISSUES/CONCERNS/RISKS

1. **BWSR Review Process**: Upon submittal, BWSR has ninety days to approve, deny, or approve portions of the Comprehensive Plan.

2. Current BWSR Review Schedule:

- August 13th CCWD releases final draft Plan
- October 7th BWSR Central Region Committee plan presentation
- October 23rd Final draft Plan goes to BWSR Board for final recommendation

OPTIONS FOR ACTIONS

- 1. Table action on the Comprehensive Plan until a later date
- 2. Approve the final submittal of the Draft Comprehensive Plan to the Board of Water and Soil Resources

RECOMMENDATION

- 1. Direct staff to submit the plan to the Board of Water and Soil Resources for their ninety-day review and approval.
- 2. Adopt the attached resolution

RESOLUTION 2024-03

COON CREEK WATERSHED DISTRICT BOARD OF MANAGERS RESOLUTION AUTHORIZING SUBMITTAL OF DRAFT WATERSHED MANAGEMENT PLAN UPDATE FOR FINAL STATE REVIEW

| Manager | offered the following resolution and moved its adoption, |
|---------------------|--|
| seconded by Manager | · |
| | |

WHEREAS the Coon Creek Watershed District (CCWD) as a metropolitan watershed district has adopted and implemented a watershed management plan in accordance with Minnesota Statutes section 103B.231 and accompanying Minnesota Rules Chapter 8410;

WHEREAS under Minnesota Statutes section 103B.231 metropolitan watershed districts are required to revise their watershed management plans at least every ten years to review and reestablish water resource goals and policies, incorporate current information, revise priorities and identify programs and projects accordingly;

WHEREAS in accordance with the Metropolitan Surface Water Management Act and accompanying Rules the CCWD prepared and adopted its first watershed management plan in 1987, years 1987-2003; a second watershed management plan, years 2003-2013; and the current third watershed management plan, years 2013- 2024 (extension approved by BWSR 10/30/2023);

WHEREAS a CCWD watershed management plan update is now warranted to reflect the past ten years of CCWD experience, land use changes within the watershed, newly acquired knowledge and changing priorities regarding water resource management within the watershed;

WHEREAS the CCWD has prepared a draft 2024-2033 comprehensive watershed management plan update. The CCWD Board of Managers finds that this watershed management plan update conforms to Minnesota Statutes sections 103B.205 through 103B.255, Minnesota Statutes Chapter 103D, Minnesota Rules Chapter 8410, and establishes a sound foundation for CCWD program efforts and resource commitments over the next ten years;

WHEREAS the CCWD in accordance with Minnesota Statutes section 103B.231 (7)(a), (11) has distributed the draft watershed management plan update for 60-day review and comment to Anoka County, the Anoka County Soil and Water Conservation District, Metropolitan Council, the Minnesota Departments of Natural Resources, Agriculture and

Health, the Minnesota Pollution Control Agency, the Minnesota Board of Water and Soil Resources, and all cities with territory within the legal boundaries of CCWD; **WHEREAS** upon the CCWD Board of Managers' review and approval for distribution of staff's written comment responses, the CCWD in accordance with Minnesota Statutes section 103B.231 (7)(b) on July 9, 2024, submitted its written response to comments from the applicable review agencies;

WHEREAS the CCWD provided notice of a public hearing on the comprehensive watershed management plan update, which was held on July 29, 2024, by the CCWD Board of Managers in conjunction with its noticed special meeting.

THEREFORE BE IT RESOLVED that in accordance with Minnesota Statutes section 103B.231 (9) the CCWD Board of Managers directs the Administrator to submit the draft 2024-2033 CCWD watershed management plan update, written comments received and written responses, a record of the public hearing, approved minutes of the public hearing, and a summary of changes incorporated as a result of the review process to the following for final review:

- Minnesota Board of Water and Soil Resources
- Metropolitan Council
- Minnesota Pollution Control Agency
- Minnesota Department of Natural Resources
- Minnesota Department of Agriculture
- Minnesota Department of Health

| Hafner Lind | | |
|----------------|--|--|
| Lind | | |
| | | |
| Lund | | |
| Campbell | | |
| McCullough | | |

MEETING DATE: August 12, 2024

AGENDA NUMBER: 11

ITEM: Request to Award Work on Ditch 39 Geotechnical Services

AGENDA: Policy

BACKGROUND

In 2024, the District prepared the Ditch 39 Subwatershed Plan in coordination with the City of Blaine, the City of Coon Rapids, and Anoka County. One of the plan's goals is the improvement of water quality and meeting TMDL requirements. An evaluation of potential actions to achieve the goal was conducted and identified three priority cost-effective regional stormwater filter projects on city or county owned land. Feasibility designs and cost estimates have been completed for each site for capital improvement planning, grant application, and budgeting purposes. The project designs and costs are highly dependent on the condition of the existing soils and groundwater elevations which are mostly unknown currently. The engineer's recommendation is to complete geotechnical exploration to further refine the design and cost estimates.

ACTION REQUESTED

Review quotes and award contract for the Ditch 39 Geotechnical Services.

COORDINATION

- 1. <u>September 11, 2023:</u> Board approved the 2024 budget including the Ditch 39 subwatershed plan
- 2. <u>June 17, 2024:</u> Annual CCWD Board Tour reviewed Ditch 39 subwatershed planning and need to complete geotechnical exploration at three locations
- 3. July 12, 2024: Request for quotes was distributed to four geotechnical companies
- 4. August 2, 2024: Quotes were due to the District by 12:00PM
- 5. August 12, 2024: Request to award work
- 6. September 30, 2024: Project completion

PERTINENT FACTS

Funding Work to be paid for through the 2024 budgeted \$76,500 for Ditch 39 subwatershed planning.

Estimate \$9,000-\$15,000 for all three sites. In the last three years, geotechnical service quotes submitted for District projects have ranged from \$3,000-\$5,000 per site. Costs vary depending on specific site considerations and requirements.

<u>District Engineer</u>-Stantec completed the feasibility designs for the proposed stormwater filters on all three sites and provided the specifications to include in the request for quotes

<u>District Attorney-reviewed</u> reviewed the request for quotes and contract to execute with the awarded company.

<u>Approvals</u>-all work is located on city or county owned land. The cities and county have been involved in the subwatershed planning efforts, are aware of the proposed work, and have provided written authorization to proceed with the proposed geotechnical exploration work. An Anoka County right-of-way permit will be executed for site access off University Avenue prior to issuance of a notice to proceed.

<u>Prequalified companies:</u> Quotes were solicited from a short list of four pre-qualified responsible companies that have experience in this type of work, have successfully worked with the District in the past and/or are highly recommended by collaborating agencies.

ISSUES/CONCERNS

<u>Neighboring properties</u>- There are approximately 20 single family residential homes in view of the proposed stormwater filter sites. Work will not directly impact these properties, however, may impact their view and usage of the city and county owned land. Staff will communicate with neighboring properties about the geotechnical work and proposed stormwater filter projects.

Bridgewater South site accessibility: The soil boring locations for this site are in an area with fluctuating water levels and unknown soil conditions. We believe the contractor can safely access the soil boring locations under normal conditions. However, should access prove problematic, we will work with the awarded company to explore and implement alternative methods to obtain the necessary data.

OUOTES

3 of the 4 solicited companies submitted quotes prior to the submittal deadline.

Quote Completeness: Staff reviewed quotes for completeness.

| Plan Holder | Quote Signed | Quote Schedule Filled Out | Quote Information Required |
|------------------------------------|-----------------|------------------------------|-------------------------------|
| American Engineering Testing, Inc. | Yes | Yes | Yes |
| Braun Intertec | Yes | Yes | Yes |
| Glacial Ridge Drilling, Inc. | | | |
| Haugo Geotechnical Services | Yes | Yes | Yes |

Costs:

| Company | Quote | Rank |
|------------------------------------|-------------|------|
| American Engineering Testing, Inc. | \$12,575.00 | 2 |
| Braun Intertec | \$13,115.00 | 3 |
| Glacial Ridge Drilling, Inc. | | |
| Haugo Geotechnical Services | \$10,020.00 | 1 |

OPTIONS FOR ACTIONS

- 1. Award contract to lowest responsible quote
- 2. Table action until next meeting with statement of reason and need
- 3. Reject all quotes
- 4. Requote project
- 5. Cancel project

CONCLUSION

Multiple competitive quotes were received in which Haugo Geotechnical Services provided the lowest responsible quote and has successfully contracted and completed similar work for the District in recent years.

RECOMMENDATION

Award Ditch 39 Geotechnical Services contract to Haugo Geotechnical Services

| Detailed Quote Summary | | | Unit Price | Unit Price | Unit Price | Unit Price |
|--|------|-----------------------|---|-------------------|---------------------------------------|-----------------------------------|
| Item | Unit | Estimated Quantity | American Engineering Testing, Inc. | Braun Intertec | Glacial Ridge Drilling, Inc. | Haugo Geotechnical Services |
| Mobilization (including health and safety, utility clearances) | LS | 1 | \$1,150.00 | \$1,645.00 | | \$2,680.00 |
| Site 1 Drilling, Sampling, & Abandonment - 15 Foot Depth | EA | 3 | \$825.00 | \$675.00 | | \$460.00 |
| Site 2 Drilling, Sampling, & Abandonment - 10 Foot Depth | EA | 3 | \$550.00 | \$650.00 | | \$340.00 |
| Site 3 Drilling, Sampling, & Abandonment - 10 Foot Depth | EA | 3 | \$550.00 | \$650.00 | | \$340.00 |
| Site 3 Drilling, Sampling, & Abandonment - 15 Foot Depth | EA | 2 | \$825.00 | \$675.00 | | \$460.00 |
| Report | LS | 1 | \$4,000.00 | \$4,195.00 | | \$3,000.00 |
| | • | | \$12,575.00 | \$13,115.00 | | \$10,020.00 |



Permit Application Review Report Date: 8/7/2024

Board Meeting Date: 8/12/2024

Agenda Item: 12

<u>Applicant/Landowner:</u> <u>Contact:</u>

Brook Adolfson Parent Custom Homes
11220 Dakotah St NW Attn: Brent Parent

Coon Rapids, MN 55433 13654 Van Buren St #400 Ham Lake, MN 55304

Project Name: Adolfson Riverbank Stabilization

Project PAN: P-24-038

Project Purpose: Bank stabilization with rip rap and native plants

Project Location: 11220 Dakota St NW, Coon Rapids

Site Size: size of parcel - 1.74 acres; size of disturbed area - 0.3 acres; size of regulated

impervious surface - 0 acres

Applicable District Rule(s): Rule 2, Rule 4, Rule 8

Recommendation: Approve with 2 Conditions and 0 Stipulations

Description: The property owner, along with Parent Custom Homes, submitted an application which is proposing a bank stabilization project that includes installation of riprap, a retaining wall and a native plant buffer. The project will disturb 0.30 acres and create no regulated impervious. The site drains to the Mississippi River. The relevant water resource concerns are erosion and sediment control and buffers which correlate with District Rules 4 and 8. See attached Figure 1: Project Location and Figure 2: Site Plan.

Conditions to be Met Before Permit Issuance:

Rule 2.7 - Procedural Requirements

1. Provide escrow in the amount of \$2,150.00.

Rule 4.0 – Soils and Erosion Control

- 2. Provide an updated Erosion and Sediment control plan that includes:
 - a. A note stating that disturbed soils will be stabilized within 7 days of inactivity.
 - b. Floating silt curtain to be placed within the river during rip rap installation and to be removed upon placement of landward perimeter control.

Stipulations: The permit will be issued with the following stipulations as conditions of the permit. By accepting the permit, the applicant agrees to these stipulations:

None

Exhibits:

| Exhibit Type | Exhibit Author | Signature Date | Received Date |
|-----------------------|---------------------|----------------|---------------|
| Project Narrative and | Parent Custom Homes | 07/11/2024 | 07/11/2024 |
| Erosion Control Plan | | | |

Findings

Fees and Escrows (Rule 2.7):

The applicant has submitted a \$760.00 application fee and deposit which corresponds with the nonrefundable application fee (\$10) and base fee for a Single-Family Lot project of 1.74 acres (\$750.00). The applicant will be required to submit a performance escrow in the amount of \$2,150.0. This corresponds to a base escrow of \$2,000, plus an additional \$500/acre of disturbance (0.3 acres of land disturbance proposed).

Stormwater Management (Rule 3.0):

The proposed project does not create a cumulative total of 10,000 sf or more of new or fully reconstructed impervious surface, or 5,000 sf or more of new or fully reconstructed impervious surface for non-residential or multifamily residential within one mile of and draining to an impaired water. The proposed project is not a public linear project where the sum of the new and fully reconstructed impervious surface is equal to one or more acres. Stormwater Management standards do not apply.

Soils and Erosion Control (Rule 4.0)

Rule 4.0 applies to the proposed project because it includes land disturbing activities of more than 5,000 square feet and within 50 feet of and drains to a waterbody.

The proposed project drains to the Mississippi River. The soils affected by the project include Nymore and does not have a soil erodibility factor of 0.15 or greater. Disturbed areas are not proposed to be stabilized within 7 days, as required. The proposed erosion and sediment control plan includes perimeter control landward of the proposed rip rap, a clear access point, and a stabilized construction entrance. The erosion control plan does not meet District Requirements because the plan does not include a floating silt curtain or a note to stabilize exposed soils within 7 days of inactivity. See attached Figure 3: Erosion and Sediment Control Plan.

Wetlands (Rule 5.0)

The proposed project does not include activities which result in the filling, draining, excavating or otherwise altering the hydrology of a wetland. Rule 5.0 does not apply.

Floodplain (Rule 6.0)

The proposed project does not include land disturbing activities within the floodplain as mapped and modeled by the District. Rule 6.0 does not apply.

Drainage, Bridges, Culverts, and Utility Crossings (Rule 7.0)

The proposed project does not include land disturbing activities which construct, improve, repair, or alter the hydraulic characteristics of a bridge profile control or culvert structure on a creek, public ditch, or major watercourse. The proposed project does not include land disturbing activities which involve a pipeline or utility crossing of a creek, public ditch, or major watercourse.

The proposed project does not include land disturbing activities which construct, improve, repair or alter the hydraulic characteristics of a conveyance system that extends across two or more parcels of record not under common ownership and has a drainage area of 200 acres or greater. Rule 7.0 does not apply.

Buffers (Rule 8.0)

Rule 8.0 applies because it includes a land disturbing activity that requires a permit under another District Rule and is on land adjacent or directly contributing to a Public Water. However, due to

how the Mississippi River is managed across the State, rip rap is an acceptable practice in place of an entirely vegetated buffer.

Variances (Rule 10.2)

The proposed project does not request a variance from the District's rules, regulations, and policies. Rule 10.2 does not apply.



Figure 1: Project Location




Figure 2: Site Plan






Figure 3: Erosion and Sediment Control Plan







13654 Van Buren Street NE Suite 400 Ham Lake MN 55304. Phone (612) 282-2380 Brent brent@parentcustomhomes.com

www.parentcustomhomes.com

Restoration / planting plan

11220 Dakotah St NW Coon Rapids Updated 7/11/24

The purpose of this work is to stop, repair & prevent the erosion occurring in the riverbank and is the minimum necessary to fix the problem. The vegetation must be removed to install riprap and retaining a wall to stop and prevent erosion. The riprap will be per the DNR's shoreline alterations riprap guideline. From the OHW there will be riprap, then a 4ft tall boulder wall (large boulders), then 6ft of 2-4" rock with an understory planted with a row of Little Bluestem spaced every 2ft (spacing from DNR), then a row of Purple Prairie Cover every 3ft (spacing from DNR), then replace existing lawn. The plant species were selected from the DNR "Restore Your Shore" list to lock & grow together.

Native Plant Encyclopedia

Little BluestemSchizachyrium scoparium var. scoparium



Recommended Planting Range

· Life Form: Grasses, Sedges and Rushes

· Habitat: Upland Moist, Upland Dry

Exposure: Full Sun

• Height: 1.0-3.0 ft

Spacing: 1.5-2 ft

· Flower Color:

· Bloom Time:

(previously: Schizachyrium scoparium)

Description

Little bluestem is a dominant grass in North American prairies, especially on drier sites, on sandy or gravelly









References & Resources

Native Plant Encyclopedia



Purple Prairie Clover Dalea purpurea var. purpurea



Recommended Planting Range

· Life Form: Ferns and Wildflowers

· Habitat: Upland Moist, Upland Dry

· Exposure: Full Sun

• Height: 1.0-2.0 ft

• Spacing: 2(3 ft)

· Flower Color: Purplish Pink

· Bloom Time: June July

(previously: Dalea purpurea)

Description

Purple prairie clover grows in dry to mesic prairies on sandy loam or loam soil. It can do well in slightly



Permit Application Review Report Date: 8/7/2024

Board Meeting Date: 8/12/2024

Agenda Item: 13

Applicant/Landowner: Family Promise in Anoka County Attn: David Frei 363 Coon Rapids Blvd NW Coon Rapids, MN 55433

Project Name: Family Promise

Project PAN: P-24-036

Project Purpose: construction of a new multifamily building, parking lot and associated stormwater

treatment features

Project Location: 340 95th Avenue NW, Coon Rapids

Site Size: size of parcel - 1.51 acres; size of disturbed area - 0.97 acres; size of regulated impervious

surface - 0.47 acres

Applicable District Rule(s): Rule 2, Rule 3, Rule 4

Recommendation: Approve with 2 Conditions and 3 Stipulations

Description: The project proposes the construction of a new multifamily building, parking lot and associated stormwater treatment feature. This project will disturb 0.97 acres and includes 0.47 acres of total regulated impervious. The parcel drains toward Pleasure Creek. The relevant water resource concerns are stormwater treatment and erosion and sediment control. This corresponds to District Rules 3 and 4. See attached Figure 1: Project Location and Figure 2: Site Plan.

Conditions to be Met Before Permit Issuance:

Rule 2.7 – Procedural Requirements

1. Submittal of a performance escrow in the amount of \$2,485.00.

Rule 3.0 – Stormwater Management

2. Provide proof of recording of a fully executed Operations and Maintenance Agreement for the perpetual inspection and maintenance of all proposed stormwater management practices after review and approval by the District.

Stipulations: The permit will be issued with the following stipulations as conditions of the permit. By accepting the permit, the applicant agrees to these stipulations:

1. Submittal of as-builts for the stormwater management practices and associated structures listed in Tables 2 and 3, including volume, critical elevations and proof of

- installation for hydrodynamic separators.
- 2. Completion of a post construction infiltration test on the Infiltration Basin by filling the basin to a minimum depth of 6 inches with water and monitoring the time necessary to drain, or multiple double ring infiltration tests to ASTM standards. The Coon Creek Watershed District shall be notified prior to the test to witness the results.
- 3. If dewatering is required, provide a DNR dewatering permit prior to construction. If a DNR permit is not required, provide well-field location, rates, discharge location, schedule and quantities prior to construction.

Exhibits:

| Exhibit Type | Exhibit Author | Signature Date | Received Date |
|--------------------|-----------------------|----------------|---------------|
| Updated Sheet C101 | LHB | 07/08/2024 | 07/24/2024 |
| Phase 1 ESA | Terracon | 05/14/2024 | 07/16/2024 |
| Geotechnical Memo | Terracon | 05/31/2024 | 07/08/2024 |
| Geotechnical | Terracon | 05/03/2024 | 07/08/2024 |
| Engineering Report | | | |
| Construction Plans | LHB | 07/08/2024 | 07/16/2024 |
| Stormwater | LHB | 07/16/2024 | 07/16/2024 |
| Management Report | | | |

Findings

Fees and Escrows (Rule 2.7): The applicant has submitted a \$3,310.00 application fee and deposit which corresponds with the nonrefundable application fee (\$10), base fee for a Commercial/Industrial Development project of 1.51 acres (\$3,000.00). The applicant will be required to submit a performance escrow in the amount of \$2,485.00. This corresponds to a base escrow of \$2,000, plus an additional \$500/acre of disturbance (0.97 acres of land disturbance proposed).

Stormwater Management (Rule 3.0):

Rule 3.0 applies to the proposed project because it includes land disturbing activities creating a cumulative total of 10,000 sf or more of new or fully reconstructed impervious surface.

The Hydrologic Soil Group (HSG) of soils on site are HSG B. The proposed project incorporates soil amendments in accordance with District guidelines.

Rate Control: Peak stormwater flow rate at each point of site discharge does not increase from the pre-development condition for the 24-hour precipitation event with a return frequency of 2-, 10-, 100- years as shown in Table 1. The project will not impact Drainage Sensitive Use areas. The rate control standard is met.

| Point of | 2-year (cfs) | | 10-year (cfs) | | 100-year (cfs) | |
|-----------|--------------|----------|---------------|----------|----------------|----------|
| Discharge | Existing | Proposed | Existing | Proposed | Existing | Proposed |
| 95th Ave | 0.59 | 0.59 | 1.35 | 1.35 | 3.26 | 3.26 |
| 94th Ave | 1.39 | 0.7 | 3.62 | 1.58 | 9.47 | 9.37 |

Table 1.

Volume Control:

The application proposes redevelopment which disturbs more than 50% of the site or reconstructs more than 50% of the existing impervious surface, therefore the volume reduction requirement is equal to 1.1 inches over the area of all impervious surface including existing impervious surface that is not proposed to be reconstructed. The amount of proposed impervious required to be treated is 20,604 ft².

The applicant is proposing the Stormwater Management Practices (SMPs) described below:

| Drainage Area | Impervious required to be treated (ft²) | Proposed SMP | TP Removal Factor | Required Water Quality Volume (ft ³) | Water Quality Volume Provided (ft ³) |
|----------------------------|---|--|----------------------|---|---|
| Untreated (P1) | 1,307 | none | 0 | 119 | 0 |
| Infiltration Basin (P3) | 15,638 | Infiltration Basin | 1 | 1,433 | 4,340 |
| P2 | 3,659 | Overland flow per section 3.3.3.3 of District Rules | 1 | 335 | 335 |
| Totals: | 20,604 | | | 1,887 | 4,675 |

Table 2.

The following pretreatment has been provided:

| SMP ID | Pretreatment Device/Method | Percent TSS Removal |
|---------------|----------------------------|---------------------|
| Rain Guardian | Rain Guardian | 80 |

Table 3.

Pretreatment is required to be designed such that the device/method provides removal of 80% TSS entering an infiltration or filtration Stormwater Management Practice. The proposed project meets pretreatment requirements as shown in Table 3.

The volume control standard has not been met as shown in Table 2. A small portion of the drive entrance cannot be routed to a treatment feature; therefore, the volume control standard has been met to the maximum extent practicable.

Water Quality: The total Water Quality Volume has been provided in aggregate.

Stormwater treatment on site must remove at least 80% of the average annual post development TSS per discharge location. The following TSS removal has been provided:

| Discharge Point | TSS Removal Provided | | |
|-----------------|----------------------|--|--|
| 94th Ave | 100 | | |
| 95th Ave | 100 | | |

Table 4.

The TSS removal standard is met at each discharge point as shown in Table 4.

Discharges to Wetlands: Stormwater from the proposed project is not being discharged into any wetlands, therefore this section does not apply.

Landlocked Basins: The proposed drainage system does not outlet to a landlocked basin, therefore this section does not apply.

Low Floor Freeboard: The proposed project is new development which includes buildings and habitable structures. Therefore, SMPs must be designed such that the lowest basement floor elevations are at least 2 feet above the 100-yr high water level and 1 foot above the emergency overflow. The lowest basement floor elevation proposed is 892 ft MSL. The applicable 100-year high water level is at 888.8 ft MSL and the applicable emergency overflow is at 888.25 ft MSL. The freeboard requirement is met.

Access: Sufficient maintenance access has been provided on the plans for all stormwater management practices.

Maintenance Agreements: The proposed stormwater management practices will not be maintained as part of standard municipal public work activities. Therefore, a maintenance agreement that meets District standards will be required.

Soils and Erosion Control (Rule 4.0)

Rule 4.0 applies to the proposed project because it is a land disturbing activity that requires a permit under another District rule.

The proposed project drains to Pleasure Creek. The soils affected by the project includes Sartell and does not have a soil erodibility factor of 0.15 or greater. Disturbed areas are proposed to be stabilized within 7 days, as required. The proposed erosion and sediment control plan includes rock construction entrance, perimeter control, street sweeping and inlet protection. The erosion control plan meets District Requirements. See attached Figure 3: Erosion & Sediment Control Plan.

Wetlands (Rule 5.0)

The proposed project does not include activities which result in the filling, draining, excavating, or otherwise altering the hydrology of a wetland. Rule 5.0 does not apply.

Floodplain (Rule 6.0)

The proposed project does not include land disturbing activities within the floodplain as mapped and modeled by the District. Rule 6.0 does not apply.

Drainage, Bridges, Culverts, and Utility Crossings (Rule 7.0)

The proposed project does not include land disturbing activities which construct, improve, repair, or alter the hydraulic characteristics of a bridge profile control or culvert structure on a creek, public ditch, or major watercourse. The proposed project does not include land disturbing activities which involve a pipeline or utility crossing of a creek, public ditch, or major watercourse.

The proposed project does not include land disturbing activities which construct, improve, repair or alter the hydraulic characteristics of a conveyance system that extends across two or more parcels of record not under common ownership and has a drainage area of 200 acres or greater. Rule 7.0 does not apply.

Buffers (Rule 8.0)

The proposed project does not include a land disturbing activity on land adjacent or directly contributing to a Public Water, Additional Waters, High or Outstanding Ecological Value Waters, a Public Ditch, or Impaired Waters/waters exceeding state water quality standards. Rule 8.0 does not apply.

Variances (Rule 10.2)

The proposed project is not requesting a variance from the District's rules, regulations, and policies. Rule 10.2 does not apply.



Figure 1: Project Location






Figure 2: Site Plan



Figure 3: Erosion and Sediment Control Plan







FAMILY PROMISE IN ANOKA COUNTY

363 COON RAPIDS BLVD NW COON RAPIDS, MN 55433

THIS SQUARE APPEARS 1/2" x 1/2"
ON FULL SIZE SHEETS

RE
SS

2 07/08/2024 CITY & WATERSHED SUBMITTAL
1 06/11/2024 SCHEMATIC DESIGN
NO DATE ISSUED FOR

NO DATE REVISION



DDO FOT NAME


FAMILY PROMISE

340 95TH AVE NW COON RAPIDS, MN 55433

DRAWING TITLE

REMOVALS & INITIAL EROSION CONTROL PLAN

DRAWN BY: DPG
CHECKED BY: MMW
PROJ. NO: 230138
DRAWING NO:






- SEDIMENT AND EROSION CONTROL MEASURES INDICATED ON SHEET C101 ARE TO BE INSTALLED PRIOR TO THE START OF CONSTRUCTION.
- REFER TO LANDSCAPE PLAN FOR PERMANENT TURF ESTABLISHMENT
- SEE SHEETS C101 FOR INITIAL EROSION CONTROL PLAN.
- 4. SLOPES TO BE STABILIZED WITH MNDOT CATEGORY 20 BLANKET AND BIODEGRADABLE STAPLES OR APPROVED EQUAL. NETTING AND METAL

STORMWATER BMP NOTES

- 1. EXCAVATION OF INFILTRATION AREAS SHALL BE COMPLETED USING A BACKHOE WITH A TOOTHED BUCKET. WHERE POSSIBLE, EXCAVATION SHALL BE DONE FROM THE SIDES AND OUTSIDE THE FOOTPRINT OF THE
- 2. NATIVE SOILS IN INFILTRATION AREAS SHALL BE DE-COMPACTED TO A MINIMUM DEPTH OF 18 INCHES BELOW THE SUBGRADE.
- 3. CONTRACTOR SHALL NOT COMPACT THE SUBGRADE BENEATH THE
- 4. INFILTRATION PERIMETER CONTROL AND EROSION CONTROL PRACTICES SHALL REMAIN IN PLACE UNTIL THE FINAL COMPLETION OF THE PROJECT
- 5. INSTALLATION OF INFILTRATION PRACTICES SHALL BE DONE DURING PERIODS OF DRY WEATHER AND COMPLETED BEFORE A RAINFALL EVENT.
- 6. THE BOTTOM EXCAVATION SURFACE OF INFILTRATION/FILTRATION AREAS
- DURING CONSTRUCTION, STORMWATER MUST BE ROUTED AROUND INFILTRATION AREAS UNTIL ALL CONSTRUCTION ACTIVITY HAS CEASED AND TRIBUTARY SURFACES ARE CLEANED OF SEDIMENT. IT IS REQUIRED THAT IMPERVIOUS AREA CONSTRUCTION IS COMPLETED, AND PERVIOUS AREA ESTABLISHED WITH DENSE AND HEALTHY VEGETATION PRIOR TO INTRODUCTION OF STORMWATER INTO A VEGETATED INFILTRATION PRACTICE.
- 8. ENGINEERED SOIL SHALL REMAIN UNCONTAMINATED (NOT MIXED WITH OTHER SOIL) BEFORE AND DURING INSTALLATION.
- 9. TESTING DURING CONSTRUCTION: PRIOR TO COMPLETION OF THE STORMWATER INFILTRATION BEST MANAGEMENT PRACTICES (BMPs), FIELD INFILTRATION TESTS SHALL BE COMPLETED TO CONFIRM THE INFILTRATION RATE. REFER TO SPECIFICATION SECTION 31 2323 FOR ADDITIONAL REQUIREMENTS.




FAMILY PROMISE IN **ANOKA COUNTY**

363 COON RAPIDS BLVD NW COON RAPIDS, MN 55433

| 2 | 07/08/2024 | CITY & WATERSHED SUBMIT |
|----|------------|-------------------------|
| 1 | 06/11/2024 | SCHEMATIC DESIGN |
| NO | DATE | ISSUED FOR |
| | | |
| | | |
| | | |
| | | |
| | | |

THIS SQUARE APPEARS 1/2" x 1/2"




FAMILY PROMISE

340 95TH AVE NW COON RAPIDS, MN 55433

PROPOSED EROSION CONTROL PLAN

DRAWN BY: DPG CHECKED BY: MMW PROJ. NO: 230138 DRAWING NO:





FAMILY PROMISE IN ANOKA COUNTY

363 COON RAPIDS BLVD NW COON RAPIDS, MN 55433

ON FULL SIZE SHEETS 07/08/2024 CITY & WATERSHED SUBMITTAL 06/11/2024 SCHEMATIC DESIGN

THIS SQUARE APPEARS 1/2" x 1/2"

ISSUED FOR DATE REVISION




COPYRIGHT 2024 BY LHB, INC. ALL RIGHTS RESERVED FAMILY PROMISE

340 95TH AVE NW COON RAPIDS, MN 55433

DRAWING TITLE:

UTILITY PLAN

DRAWN BY: DPG CHECKED BY: MMW PROJ. NO: 230138





FAMILY PROMISE IN ANOKA COUNTY

363 COON RAPIDS BLVD NW COON RAPIDS, MN 55433

THIS SQUARE APPEARS 1/2" x 1/2"
ON FULL SIZE SHEETS

2 07/08/2024 CITY & WATERSHED SUBMITTAL
1 06/11/2024 SCHEMATIC DESIGN
NO DATE ISSUED FOR

NO DATE REVISION



COPYRIGHT 2024 BY LHB, INC. ALL RIGHTS RESERVED

FAMILY PROMISE


340 95TH AVE NW COON RAPIDS, MN 55433

DRAWING TITLE:

GRADING PLAN

DRAWN BY: DPG
CHECKED BY: MMW
PROJ. NO: 230138

DRAWING NO:



FAMILY PROMISE IN ANOKA COUNTY

363 COON RAPIDS BLVD NW COON RAPIDS, MN 55433

ON FULL SIZE SHEETS 07/08/2024 SCHEMATIC DESIGN

THIS SQUARE APPEARS 1/2" x 1/2"

CITY & WATERSHED SUBMITTAL ISSUED FOR

> DATE REVISION

PRELIMINARY
NOT FOR CONSTRUCTION
07|08|2024

COPYRIGHT 2024 BY LHB, INC. ALL RIGHTS RESERVED


FAMILY PROMISE

340 95TH AVE NW COON RAPIDS, MN 55433

DRAWING TITLE:


SITE PLAN

DRAWN BY: DPG CHECKED BY: MMW PROJ. NO: 230138




CONSTRUCTION ENTRANCE SPECIFICATIONS


- * STONE SIZE: USE 1"-2" CRUSHED ROCK OR RECLAIMED OR
- RECYCLED CONCRETE EQUIVALENT.
- * THICKNESS: NOT LESS THAN 6-INCHES.
- * FILTER CLOTH: SHALL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING OF STONE.
- * MAINTENANCE: THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHT-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHT-OF-WAYS MUST BE REMOVED IMMEDIATELY.
- * WASHING: WHEELS SHALL BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC RIGHT-OF-WAY. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH STONE AND WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE.
- * PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER EACH RAIN EVENT.



TREE PROTECTION FENCING



- 1. THE FENCE SHALL BE LOCATED AT THE DRIP LINE OF THE TREE TO BE SAVED AND IN NO CASE CLOSER THAN 5 FEET TO THE TRUNK OF ANY TREE. FENCE POSTS SHALL BE EITHER STANDARD STEEL POSTS OR WOOD POSTS WITH A MINIMUM CROSS SECTIONAL AREA OF
- 3.0 SQ. IN. 3. THE FENCE MAY BE EITHER 48" HIGH CHAINLINK FENCE, 48" HIGH SNOW FENCE, OR ANY OTHER MATERIAL AS APPROVED BY THE ENGINEER OR LANDSCAPE ARCHITECT.
- 4. THE CONTRACTOR SHALL INSTALL AND MAINTAIN THROUGHOUT CONSTRUCTION A PROTECTIVE LAYER OF MULCH AT A MINIMUM DEPTH OF 12" FOR VEHICLE ACCESS.




NOTE: EROSION CONTROL BLANKET ON 4:1 SLOPES OR STEEPER AND SWALES WITH LONGITUDINAL SLOPES OF 2.0% OR GREATER

EROSION CONTROL BLANKET



FAMILY PROMISE IN ANOKA COUNTY

363 COON RAPIDS BLVD NW COON RAPIDS, MN 55433



POINT "A" MUST BE HIGHER THAN POINT "B" TO ENSURE THAT WATER FLOWS OVER THE DIKE

AND NOT AROUND THE ENDS.



PLASTIC ZIP TIES (50 LB. TENSILE) LOCATED IN TOP 8"


2'-0" MIN.

POST

EMBEDMENT

DIRECTION OF


RUNOFF FLOW




NOTE: CRUSHED CONCRETE OR BITUMINOUS SHALL NOT BE USED FOR OPEN GRADED AGGREGATE.

5" DIAMETER GEOTEXTILE SOCK, TYPE WOVEN MONOFILAMENT CONFORMING TO SPEC. 3886, TABLE 3886-1. MACHINE SLICE

FILL ROCK LOG WITH 45 LBS. OF OPEN GRADED AGGREGATE CONSISTING OF SOUND, DURABLE PARTICLES OF CRUSHED QUARRY ROCK OR GRAVEL CONFORMING TO THE FOLLOWING GRADATION.





TYPE I




<u>TYPE II</u>

INLET PROTECTION - TYPE I & II







ANCHOR INSTALLATION INSTRUCTIONS:

1. PUSH SPADE THROUGH SOIL WITH STAKE OR BY OTHER MEANS TO MINIMUM DEPTH OF 18". SPADE MUST BE INSTALLED INTO FIRM SOILS. 2. LOOP STRAP TROUGH SCOURSTOP MAT. 3. PULL STRAP TIGHT AND PUSH ON ONE-WAY STOP UNTIL SNUG.

4. TRIM EXCESS STRAP IF NECESSARY.

TURF TRANSITION MAT (SCOURSTOP OR APPROVED EQUAL




FAMILY PROMISE

340 95TH AVE NW COON RAPIDS, MN 55433

DRAWING TITLE:

CIVIL DETAILS

DRAWN BY: CHECKED BY: PROJ. NO: 230138 DRAWING NO:





FAMILY PROMISE IN ANOKA COUNTY

363 COON RAPIDS BLVD NW COON RAPIDS, MN 55433

THIS SQUARE APPEARS 1/2" x 1/2"
ON FULL SIZE SHEETS

2 07/08/2024 CITY & WATERSHED SUBMITTAL
1 06/11/2024 SCHEMATIC DESIGN
NO DATE ISSUED FOR



DDO JECT NAME.


FAMILY PROMISE

340 95TH AVE NW COON RAPIDS, MN 55433

DRAWING TITLE:

CIVIL DETAILS

DRAWN BY:
CHECKED BY:
PROJ. NO: 230138
DRAWING NO:



PLANT SCHEDULE

LANDSCAPE NOTES

THE LANDSCAPE ARCHITECT.

ON THE PLANT SCHEDULE.

SPECIFIED ON CIVIL SHEETS.

RESTORATION REQUIREMENTS.

GENERAL LANDSCAPE NOTES:

1. THIS DRAWING DOES NOT CONSTITUTE AN OFFICIAL SURVEY OF THE SITE. CONFIRM

ALL LOCATIONS OF SURFACE AND SUB-SURFACE FEATURES BEFORE BEGINNING

CONFIRM ALL QUANTITIES, SHAPES, AND LOCATIONS OF LANDSCAPE AREAS, AND

VERIFY LOCATIONS OF ALL UNDERGROUND UTILITIES PRIOR TO DIGGING. NOTIFY

THE LANDSCAPE ARCHITECT OF ANY CONFLICTS WITH PLANT INSTALLATION.

5. REFER TO SECTION 31 2323 FILL FOR SOIL REQUIREMENTS. DO NOT BEGIN PLANTING

REMOVE FROM THE SITE ALL TURF WHICH HAS BEEN REMOVED FOR NEW PLANT

STAKE TREE AND PLANTING BED LAYOUT IN-FIELD FOR LANDSCAPE ARCHITECT

AVOID DAMAGING EXISTING TREES. DO NOT STORE OR DRIVE HEAVY MATERIALS

KEEP PAVEMENTS, FIXTURES AND BUILDINGS CLEAN AND UNSTAINED. ANY DAMAGE

TO EXISTING FACILITIES WILL BE REPAIRED AT THE CONTRACTOR'S EXPENSE. KEEP

BEDS. LONG-TERM STORAGE OF MATERIALS OR SUPPLIES ON-SITE IS NOT ALLOWED. THE PLAN TAKES PRECEDENCE OVER THE PLANT SCHEDULE IF DISCREPANCIES

OPERATIONS IF SOIL CONDITIONS ARE NOT AS SPECIFIED.

APPROVAL PRIOR TO PLANTING OPERATIONS.

EXIST. ADVISE LANDSCAPE ARCHITECT OF ANY DISCREPANCIES.

OVER TREE ROOTS. DO NOT DAMAGE TREE BARK OR BRANCHES.

THE PROJECT SITE CLEAR OF CONSTRUCTION WASTES AND DEBRIS. 10. PROVIDE AND MAINTAIN INLET AND PERIMETER EROSION CONTROL BMPS AS

11. ALL AREAS OF THE SITE DISTURBED BY CONSTRUCTION WILL BE RESTORED WITH SEED OR SOD UNLESS OTHERWISE NOTED. SEE SPECIFICATIONS FOR TURF

4. THE CONTRACTOR IS RESPONSIBLE FOR ALL MULCHES AND SOIL QUANTITIES TO COMPLETE THE WORK SHOWN IN THE DRAWINGS. VERIFY ALL QUANTITIES SHOWN

ADJUST TO CONFORM TO THE SITE CONDITIONS. CONFIRM ANY ADJUSTMENTS WITH

INSTALLATION. ADVISE LANDSCAPE ARCHITECT OF ANY DISCREPANCIES.

| SYMBOL | <u>QTY</u> | BOTANICAL / COMMON NAME | CONT | SIZE |
|---|-------------|--|--------------------|---------------------|
| TREES | | | | |
| | 1 | Amelanchier x grandiflora `Autumn Brilliance` / `Autumn Brilliance` Serviceberry | B & B | 2.5"Ca |
| | 3 | Gleditsia triacanthos inermis 'Imperial' / Imperial Honey Locust | B & B | 2.5" C _i |
| AND OFFICE OF THE PROPERTY OF | 7 | Pinus alba / White Pine | B & B | 2.5" C _i |
| \bigcirc | 1 | Quercus ellipsoidalis / Northern Pin Oak | B & B | 2.5" C _i |
| | 2 | Tilia americana 'Greenspire' / Greenspire® Linden | B & B | 2.5" C _i |
| SYMBOL | <u>QTY</u> | BOTANICAL / COMMON NAME | CONT | <u>NOTE</u> |
| GROUND CO | <u>VERS</u> | | | |
| | 2,987 sf | Detention Basin / See section | Seed Mix | |
| | 314 sf | Engineered Wood Fiber | None | |
| | 356 sf | Hardwood Mulch | See Specifications | |
| | 1,327 sf | Landscape Bed | None | |
| × × × × × × × × × × × × × × × × × × × | 13,927 sf | Low Maintenance Turf | Seed | |
| | 419 sf | Rock Mulch Maintenance Edger | None | |
| | 7,066 sf | Short Prairie Native Seed Mix | Seed Mix | |



701 Washington Ave. N, Ste 200 | Minneapolis, MN 55401 | 612.338.2029

FAMILY PROMISE IN ANOKA COUNTY

363 COON RAPIDS BLVD NW COON RAPIDS, MN 55433

| 2 07/08/2024 CITY & WATERSHED S 1 06/11/2024 SCHEMATIC DESIGN |
|--|
| 1 06/11/2024 SCHEMATIC DESIGN |
| |
| NO DATE ISSUED FOR |

13. NO SUBSTITUTIONS OF PLANT MATERIAL WILL BE ACCEPTED UNLESS APPROVED IN 14. THE LANDSCAPE ARCHITECT RESERVES THE RIGHT TO REJECT ANY PLANTS WHICH

16. HEEL IN AND WATER ANY PLANT STOCK NOT PLANTED WITHIN 24 HOURS OF DELIVERY UNTIL INSTALLATION. PLANTS NOT MAINTAINED IN THIS MANNER WILL BE REFER TO SPECIFICATIONS FOR WARRANTY REQUIREMENTS AND OTHER PLANTING

NURSERY STOCK", ANSI-Z60. LATEST EDITION, OF THE AMERICAN ASSOCIATION OF

12. PLANT TREE ROOT BALLS FLUSH WITH FINAL GRADE AND THE TOP OF ROOT FLARE

15. ALL PLANTING STOCK SHALL CONFORM TO THE "AMERICAN STANDARD FOR

ACCESSORIES.

NURSERYMEN, INC.

EXPOSED, PER PLANTING DETAILS.

ARE DEEMED UNSATISFACTORY.

WRITING BY THE LANDSCAPE ARCHITECT.

- MAINTENANCE AND CARE 18. BEGIN PLANT MAINTENANCE IMMEDIATELY AFTER EACH PORTION OF THE WORK IS IN
- 19. MAINTENANCE INCLUDES WATERING, WEEDING, MULCHING, REMOVAL OF DEAD MATERIAL PRIOR TO GROWING SEASON, RE-SETTING PLANTS AND PROPER GRADE, AND KEEPING PLANTS IN A PLUMB POSITION.
- 20. REFER TO SPECIFICATIONS FOR FULL INSPECTION, MAINTENANCE, AND WARRANTY REQUIREMENTS.



REVISION

COPYRIGHT 2024 BY LHB, INC. ALL RIGHTS RESERVED.

PROJECT NAME:
FAMILY PROMISE

DATE

340 95TH AVE NW COON RAPIDS, MN 55433

DRAWING TITLE:

LANDSCAPE PLAN

DRAWN BY: KAT CHECKED BY: LAM PROJ. NO: tosave DRAWING NO:

LANDSCAPE PLAN



Permit Application Review Report Date: 8/7/2024

Board Meeting Date: 8/12/2024

Agenda Item: 14

Applicant/Landowner:
GHS Development
Attn: Nick Gervais

2935 County Dr STE 100 Little Canada, MN 55117

Project Name: Les Schwab Tire Center

Project PAN: P-23-080

Project Purpose: construction of a new commercial building, parking areas and associated

stormwater treatment features

Project Location: 12401 Ulysses St NE, Blaine

Site Size: size of parcel - 1.39 acres; size of disturbed area - 1.24 acres; size of regulated impervious

surface - 0.92

Applicable District Rule(s): Rule 2, Rule 3, Rule 4

Recommendation: Approve with 3 Conditions and 4 Stipulations

Description: The applicant proposed the construction of a new tire center with associated stormwater treatment features. Overall, it will disturb 1.24 acres and create 0.92 acres of new and regulated impervious. The parcel drains to County Ditch 41-8-A which drains to County Ditch 60-2. The relevant water resource concerns are stormwater treatment and erosion and sediment control. This corresponds to District Rules 3 and 4. See attached Figure 1: Project Location and Figure 2: Site Plan.

Conditions to be Met Before Permit Issuance:

Rule 2.7 – Procedural Requirements

1. Submittal of a performance escrow in the amount of \$2,620.00.

Rule 3.0 – Stormwater Management

2. Provide proof of recording of a fully executed Operations and Maintenance Agreement for the perpetual inspection and maintenance of all proposed stormwater management practices after review and approval by the District.

Rule 4.0 – Soils and Erosion Control

3. Updated the erosion and sediment control plan to include a note that soils and soil stockpiles will be stabilized within 7 days of inactivity.

Stipulations: The permit will be issued with the following stipulations as conditions of the permit. By accepting the permit, the applicant agrees to these stipulations:

- 1. Submittal of as-builts for the stormwater management practices and associated structures listed in Tables 2 and 3, including volume, critical elevations and proof of installation for hydrodynamic separators.
- 2. Completion of post construction infiltration test on the East and West Filtration Basins by filling the basin to a minimum depth of 6 inches with water and monitoring the time necessary to drain, or multiple double ring infiltration tests to ASTM standards. The Coon Creek Watershed District shall be notified prior to the test to witness the results.
- 3. If dewatering is required, provide DNR dewatering permit prior to construction. If a DNR permit is not required, provide well-field location, rates, discharge location, schedule and quantities prior to construction.
- 4. The applicant must apply for coverage under the Minnesota Pollution Control Agency's (MPCA's) Construction Stormwater Permit (Permit No: MNR100001).

Exhibits:

| Exhibit Type | Exhibit Author | Signature Date | Received Date |
|-----------------------------------|-----------------------|----------------|---------------|
| MnDOT Drainage Permit | MnDOT | 07/23/2024 | 07/23/2024 |
| Geotechnical Evaluation Report | Braun Intertec | 04/06/2023 | 12/21/2023 |
| Stormwater Management Plan | KLJ | 07/18/2024 | 07/18/2024 |
| Construction Plans | KLJ | 07/12/2024 | 07/18/2024 |

Findings

Fees and Escrows (Rule 2.7): The applicant has submitted a \$3,310.00 application fee and deposit which corresponds with the nonrefundable application fee (\$10), base fee for a Commercial/Industrial Development project of 1.39 acres (\$3,300.00). The applicant will be required to submit a performance escrow in the amount of \$2,620.00. This corresponds to a base escrow of \$2,000, plus an additional \$500/acre of disturbance (1.24 acres of land disturbance proposed).

Stormwater Management (Rule 3.0):

Rule 3.0 applies to the proposed project because it includes land disturbing activities creating a cumulative total of 10,000 sf or more of new or fully reconstructed impervious surface.

The Hydrologic Soil Group (HSG) of soils on site are HSG A. Curve Numbers have been shifted down ½ classification to account for the impacts of grading on soil structure.

Rate Control: Peak stormwater flow rate at each point of site discharge does not increase from the pre-development condition for the 24-hour precipitation event with a return frequency of 2-, 10-, 100- years as shown in Table 1. The small rate increase for the 2 year event is within model tolerance. The project will not impact Drainage Sensitive Use areas. The rate control standard is met.

| Point of | 2-year (cfs) | | 10-year (cfs) | | 100-year (cfs) | |
|------------|--------------|----------|---------------|----------|----------------|----------|
| Discharge | Existing | Proposed | Existing | Proposed | Existing | Proposed |
| East Swale | 0.31 | 0.42 | 0.91 | 0.63 | 4.83 | 1.19 |

Table 1.

Volume Control: The proposed project is new development; therefore, the volume reduction requirement is equal to 1.1 inches over the area of all impervious surface. The amount of proposed impervious required to be treated is 39,982 ft².

| The applicant is p | proposing the | Stormwater | Management | Practices (| (SMPs) | described below: |
|--------------------|---------------|------------|------------|-------------|--------|------------------|
| | | | | | | |

| Drainage Area | Impervious required to be treated (ft²) | Proposed SMP | TP Removal Factor | Required Water Quality Volume (ft ³) | Water Quality Volume Provided (ft ³) |
|-----------------------|---|-----------------------|----------------------|---|---|
| untreated | 1,241 | none | 0 | 175 | 0 |
| E biofiltration basin | 26,692 | E biofiltration basin | 0.65 | 3,764 | 4,230 |
| W Biofiltration basin | 12,049 | W biofiltration basin | 0.65 | 1,699 | 2,634 |
| Totals: | 39,982 | | | 5,638 | 6,864 |

Table 2.

The following pretreatment has been provided:

| SMP ID | Pretreatment Device/Method | Percent TSS Removal |
|-------------|----------------------------|---------------------|
| RG Turret 4 | Rain Guardian | 80 |
| RG Turret 3 | Rain Guardian | 80 |
| RG Turret 2 | Rain Guardian | 80 |
| RG Turret 1 | Rain Guardian | 80 |

Table 3.

Pretreatment is required to be designed such that the device/method provides removal of 80% TSS entering an infiltration or filtration Stormwater Management Practice. The proposed project meets pretreatment requirements as shown in Table 3.

Infiltration may not be used as a volume control practice because the practice(s) would need to be placed in areas in an Emergency Response Area (ERA) within a Drinking Water Supply Management Area (DWSMA). Because the volume reduction standard cannot be met due to these site constraints, the project proposes the use of the stormwater management practices and their corresponding TP conversion factors listed in Table 2. A small portion of the site entrances remains untreated and cannot be routed to a treatment features. The volume control standard has been met to the maximum extent practicable.

Water Quality: The total Water Quality Volume has been provided in aggregate.

Stormwater treatment on site must remove at least 80% of the average annual post development TSS per discharge location. The following TSS removal has been provided:

| Discharge Point | TSS Removal Provided | | |
|------------------|----------------------|--|--|
| E drainage swale | 80 | | |

Table 4.

The TSS removal standard is met at each discharge point as shown in Table 4.

Discharges to Wetlands: Stormwater from the proposed project is not being discharged into any wetlands, therefore this section does not apply.

Landlocked Basins: The proposed drainage system does not outlet to a landlocked basin, therefore this section does not apply.

Low Floor Freeboard: The proposed project is new development which includes buildings and habitable structures. Therefore, SMPs must be designed such that the lowest basement floor elevations are at least 2 feet above the 100-yr high water level and 1 foot above the emergency overflow. The lowest basement floor elevation proposed is 906.3 MSL. The applicable 100-year high water levels are 903.6 and 903.7 ft MSL and the applicable emergency overflows are both at 904 ft MSL. The freeboard requirement is met.

Maintenance:

Access: Sufficient maintenance access has been provided on the plans for all stormwater management practices.

Maintenance Agreements: The proposed stormwater management practices will not be maintained as part of standard municipal public work activities. Therefore, a maintenance agreement that meets District standards will be required.

Soils and Erosion Control (Rule 4.0)

Rule 4.0 applies to the proposed project because it is a land disturbing activity that requires a permit under another District rule.

The proposed project drains to County Ditch 41-8-A. The soils affected by the project include Zimmerman and do not have a soil erodibility factor of 0.15 or greater. Disturbed areas are not proposed to be stabilized within 7 days, as required. The proposed erosion and sediment control plan includes perimeter control, inlet protection, rock construction entrance, erosion control blanket and street sweeping. The erosion control plan does not meet District requirement because soils and soil stockpiles are not proposed to be stabilized within 7 days of inactivity. See attached Figure 3: Erosion and Sediment Control plan.

Wetlands (Rule 5.0)

The proposed project does not include activities which result in the filling, draining, excavating, or otherwise altering the hydrology of a wetland. Rule 5.0 does not apply.

Floodplain (Rule 6.0)

The proposed project does not include land disturbing activities within the floodplain as mapped and modeled by the District. Rule 6.0 does not apply.

Drainage, Bridges, Culverts, and Utility Crossings (Rule 7.0)

The proposed project does not include land disturbing activities which construct, improve, repair, or alter the hydraulic characteristics of a bridge profile control or culvert structure on a creek, public ditch, or major watercourse. The proposed project does not include land disturbing activities which involve a pipeline or utility crossing of a creek, public ditch, or major watercourse.

The proposed project does not include land disturbing activities which construct, improve, repair or alter the hydraulic characteristics of a conveyance system that extends across two or more parcels of record not under common ownership and has a drainage area of 200 acres or greater. Rule 7.0 does not apply.

Buffers (Rule 8.0)

The proposed project does not include a land disturbing activity on land adjacent or directly contributing to a Public Water, Additional Waters, High or Outstanding Ecological Value Waters, a Public Ditch, or Impaired Waters/waters exceeding state water quality standards. Rule 8.0 does not apply.

Variances (Rule 10.2)

The proposed project is not requesting a variance from the District's rules, regulations, and policies. Rule 10.2 does not apply.



Figure 1: Project Location




Figure 2: Site Plan






Figure 3: Erosion and Sediment Control Plan





NOTES:

- 1. THESE NOTES APPLY TO THE ENTIRE PROJECT EXCEPT AS INDICATED OTHERWISE. CONTRACTOR SHOULD NOTE THAT ADDITIONAL CONSTRUCTION NOTES ARE INCLUDED ON INDIVIDUAL DRAWINGS.
- 2. THESE NOTES ARE FOR GENERAL REFERENCE IN CONJUNCTION WITH AND AS A SUPPLEMENT TO THE WRITTEN SPECIFICATIONS, DETAILS, ADDENDA AND CHANGE ORDERS ASSOCIATED WITH THE CONTRACT DOCUMENTS.
- 3. ANY ERRORS OR OMISSIONS DISCOVERED BY THE CONTRACTOR IN THE PLANS OR SPECIFICATIONS SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER WHEN DISCOVERED. THE CONTRACTOR SHALL ALLOW TIME FOR CLARIFICATION PRIOR TO PROCEEDING WITH THE WORK IN QUESTION.
- 4. REQUESTS FOR SUBSTITUTIONS OR DEVIATIONS FROM THE PLANS OR SPECIFICATIONS BY THE CONTRACTOR OR OWNER SHALL BE APPROVED IN WRITING BY THE ENGINEER OR ARCHITECT PRIOR TO IMPLEMENTATION.
- 5. THE OWNER SHALL EMPLOY AND PAY FOR THE SERVICES OF AN INDEPENDENT TESTING LABORATORY TO PERFORM ALL INSPECTIONS, TESTS, OR APPROVALS REQUIRED BY THE CONTRACT DOCUMENTS AND FOR COMPLETION OF ALL PHASES OF THE WORK. CONTRACTOR SHALL COORDINATE SCHEDULE WITH OWNER'S TESTING AGENCY.
- 6. THE CONTRACTOR SHALL HIRE AN ENGINEERING OR SURVEYING FIRM TO PROVIDE CONSTRUCTION STAKING SERVICES. CONTACT KLJ AT 651-222-2176 TO REQUEST A QUOTE.
- 7. THE CONTRACTOR SHALL PROTECT ALL SURVEY MONUMENTS. ANY MONUMENTS DISTURBED OR DESTROYED SHALL BE REPLACED BY A REGISTERED LAND SURVEYOR AT THE CONTRACTOR'S EXPENSE.
- 8. CONTRACTOR SHALL PROVIDE A ONE (1) WEEK NOTICE TO ENGINEER, OWNER, AND PROPERTY OWNERS PRIOR TO BEGINNING ANY CONSTRUCTION.
- 9. THE LOCATION OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY THE OWNER OR THEIR REPRESENTATIVES. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. UNDERGROUND LOCATES SHALL BE MADE BY USING MINNESOTA "ONE CALL" NUMBER <u>1-800-252-1166 OR 811.</u>
- 10. THIS PLAN SET INCLUDES A LEGEND OF GENERAL ABBREVIATIONS, SYMBOLS AND MATERIALS. SOME SYMBOLS, MATERIALS, AND ABBREVIATIONS MAY NOT BE UTILIZED ON THIS SPECIFIC PROJECT.
- 11. THE CONTRACTOR SHALL BE REQUIRED TO OBTAIN ALL NECESSARY PERMITS.
- 12. CONTRACTOR SHALL REVIEW AND FOLLOW THE RECOMMENDATIONS FROM THE GEOTECHNICAL REPORT.
- 13. THE CONTRACTOR SHALL MAINTAIN INGRESS/EGRESS ACCESS TO THIS PROPERTY AND ADJACENT PROPERTIES AT ALL TIMES. THE CONTRACTOR SHALL COORDINATE DETOURS AND ANY TEMPORARY CLOSURES WITH THE OWNER. THE CONTRACTOR SHALL KEEP THE DURATION OF ALL CLOSURES AND DETOURS TO A MINIMUM. CONTRACTOR SHALL PROVIDE FLAGGERS AS NEEDED. ALL DETOURS AND CLOSURES SHALL BE INSTALLED PER MUTCD REQUIREMENTS AND SHALL HAVE CITY OF BLAINE APPROVAL.


REMOVALS & DEMOLITION:


- 14. CONTRACTOR SHALL FULL DEPTH SAW CUT ALL CURB AND GUTTER, SIDEWALK, AND PAVEMENT PRIOR TO REMOVAL.
- 15. ANY EXISTING STRUCTURES DISTURBED BY CONSTRUCTION AND NOT CALLED FOR REMOVAL ARE TO BE RESTORED TO THEIR ORIGINAL LOCATION AND CONDITION. THIS INCLUDES ALL STRUCTURES SUCH AS CURB AND GUTTER, ADJACENT PAVEMENT, SIDEWALKS, ETC.
- 16. MISCELLANEOUS ITEMS INCLUDING, BUT NOT LIMITED TO, MAILBOXES, STREET LIGHTS, TRAFFIC LIGHTS, SIGNS, FENCES, POLES, ETC. SHALL BE PROTECTED OR REMOVED AND REINSTALLED BY THE CONTRACTOR WITH THE OWNERS AND PROPERTY OWNERS PERMISSION, AND THIS WORK SHALL BE INCIDENTAL TO THE CONTRACT.
- 17. IF ENCOUNTERED, CONTRACTOR SHALL PROTECT EXISTING IRRIGATION SYSTEMS WHETHER SHOWN ON PLANS OR NOT. ANY DAMAGE TO EXISTING IRRIGATION SYSTEM(S) CAUSED BY CONSTRUCTION SHALL BE REPAIRED/RESTORED AT CONTRACTOR'S EXPENSE.
- 18. EXCESS EXCAVATED MATERIAL INCLUDING PIPE, STUMPS, ROOTS, SOIL MATERIALS OR ANY OTHER ITEMS THE OWNER DOES NOT WISH TO SALVAGE SHALL BECOME THE CONTRACTOR'S PROPERTY AND SHALL BE REMOVED FROM THE SITE AND DISPOSED OF PROPERLY, INCIDENTAL TO THE CONTRACT. ALL CONCRETE SHALL BE LEGALLY DISPOSED OF OFFSITE, INCIDENTAL TO THE CONTRACT.
- 19. THE CONTRACTOR SHALL COORDINATE WITH THE CONSTRUCTION MANAGER AND THE APPROPRIATE UTILITY COMPANIES TO OBTAIN APPROVAL FOR AND DETERMINE THE EXTENTS OF REMOVAL, RELOCATION OR ABANDONMENT OF EXISTING ELECTRICAL, GAS AND COMMUNICATIONS LINES.

| | LLOLIND | |
|--|---------------------------------------|---|
| EXISTING | ITEM | PROPOSED |
| Υ | FIRE HYDRANT | * |
| 8 | GATE VALVE | • |
| Ø | CURB STOP | (|
| 4) | YARD HYDRANT | |
| MM MM | BEND | |
| \bowtie | TEE | |
| <u> </u> | CROSS | • |
| \bowtie | REDUCER | |
| \square | VERTICAL BEND | × |
| (S) | SANITARY MANHOLE | <u> </u> |
| <u>(i)</u> | SANITARY FORCEMAIN MANHOLE CLEANOUT | ™ |
| <u> </u> | STORM SEWER MANHOLE | <u> </u> |
| | CURB INLET | <u> </u> |
| | CATCH BASIN | |
| <u> </u> | POWER POLE | |
| $\stackrel{\longrightarrow}{\longrightarrow}$ | GUY WIRE | |
| * | LIGHT POLE | •-□□-•-□ * |
| Ē | ELECTRICAL PEDESTAL | · · · · · · · · · · · · · · · · · · · |
| E | ELECTRICAL METER | |
| E | ELECTRICAL BOX | |
| E | ELECTRICAL MANHOLE | (E) |
| T | TELEPHONE MANHOLE | Ū |
| Ī | TELEPHONE PEDESTAL | |
| <u>P</u> | CABLE TV PEDESTAL | |
| <u>©</u> | FIBER OPTIC PEDESTAL | |
| <u> </u> | UTILITY MARKER GAS METER | |
| G \ | GAS WETER | |
| \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ | TREES CONIFEROUS/ DECIDUOUS | |
| ### | BUSH/SHRUB | |
| | SIGN | 4 |
| <u> </u> | CONTROL POINT | |
| ★ | BENCHMARK | |
| <u> </u> | PIPE CAP PROPERTY PIN | |
| © | - ASPHALT EDGE | |
| | - BUILDING | |
| | - BUILDING CANOPY | |
| TV | - CABLE TV - UNDERGROUND | TV TV |
| | - CENTERLINE | |
| | CONCRETE EDGE | |
| | CONSTRUCTION LIMITS | |
| POH — | - ELECTRICAL - OVERHEAD | E(O) E(O) |
| PUG | ELECTRICAL - UNDERGROUND | E |
| x | FENCE - BARBED WIRE | xxx |
| 0 0 | FENCE - CHAINLINK | <u> </u> |
| 11 11 11 | FENCE - PLASTIC, VINYL | - |
| 0 0 | FENCE - WOOD | |
| F0 ———————————————————————————————————— | FIBER - UNDERGROUND GAS - UNDERGROUND | F0 F0 F0 |
| <u> </u> | - PROPERTY LINE | |
| SAN | - SANITARY SEWER SERVICE LINE | |
| SAN — | - SANITARY SEWER (24" OR LESS) | |
| SAN | - SANITARY SEWER (24" OR MORE) | · » · » · » · » · » · » |
| | STORM SEWER EDGEDRAIN | |
| ST0 — | STORM SEWER (24" OR LESS) | >> |
| STO — | STORM SEWER (24" OR MORE) | > |
| T(O) - | TELEPHONE - OVERHEAD | T(O) T(O) |
| Т — | TELEPHONE - UNDERGROUND | |
| | - WATER SERVICE LINE | |
| ——— WAT ——— | - WATER MAIN | |

LEGEND








MRR

2314-00145.

04/09/2024



PLAN KEY NOTES:

- (1) STANDARD ASPHALT PAVEMENT SEE DETAIL 1/C702
- HEAVY DUTY ASPHALT PAVEMENT SEE DETAIL 2/C702
- HEAVY DUTY CONCRETE PAVEMENT SEE DETAILS 3/C702 & 4/C702
- (4) CATCH CURB AND GUTTER SEE DETAILS 4/C702 & 5C702
- CONCRETE SIDEWALK SEE DETAILS 4/C702 & 8/C702
- ACCESSIBLE RAMP SEE DETAILS 4/C702 & 9/C702
- 4" YELLOW PAINTED PAVEMENT MARKING
- HANDICAP ACCESSIBLE STALL PAVEMENT MARKING SEE DETAIL 4/C703
- 9 STANDARD HANDICAP PARKING SIGN SEE DETAIL 5/C703
- 10) VAN ACCESSIBLE PARKING SIGN SEE DETAIL 5/C703
- 11) 6" DIA. BOLLARD SEE DETAIL 7/C702
- (12) BENCH SEE DETAIL 2/C703
- TRASH RECEPTACLE SEE DETAIL 3/C703
- NOSE DOWN CURB SEE DETAIL 10/C702
- 15 KEY KEEPER WITH STAND SEE DETAIL 1/C703
- 16) TRASH ENCLOSURE SEE ARCHITECTURAL PLANS
- 17 LIGHT POLE SEE ELECTRICAL PLANS
- TRANSFORMER SEE ELECTRICAL PLANS
- 9) STOOP SEE STRUCTURAL
- (20) PYLON SIGN SEE ATTACHED ARCHITECTURAL PLANS
- 21) DROP CURB & GUTTER SEE DETAILS 4/C702 & 6/C702
- (22) BUILDING SETBACKS
- (23) PARKING SETBACKS
- 4" WHITE STRIPPING
- 25) DRIVEWAY LANE STRPIING
- DIVIVEWAT LANE STREETING
- (26) CROSSWALK PAVEMENT MARKING SEE DETAIL 11/C702
- STOP SIGN SEE DETAIL 2/C701

| ABBREVIATI | ONS: | O.C. | ON CENTER |
|------------|---------------------------|-------|--------------------------------|
| ALT | ALTERNATE | OCS | OUTLET CONTROL STRUCTUR |
| APPROX | APPROXIMATE | PERF | PERFORATED |
| ASPH | ASPHALT | PVC | POLYVINYL CHLORIDE |
| C.C. | CENTER TO CENTER | RCP | REINFORCED CONCRETE PIPE |
| CY | CUBIC YARD | REINF | REINFORCED |
| ELEV | ELEVATION | SAN | SANITARY |
| EX | EXISTING | ST | STORM |
| FES | FLARED END SECTION | SVC | SERVICE |
| FFE | FIRST FLOOR ELEVATION | TA | TOP OF ASPHALT |
| FG | FINISHED GRADE | TBC | TOP BACK OF CURB |
| FL | FLOWLINE | TC | TOP OF CONCRETE |
| HDPE | HIGH DENSITY POLYETHYLENE | TG | TOP OF GRAVEL |
| HP | HIGH POINT | TS&V | TAPPING SLEEVE & VALVE |
| INV | INVERT | | (STAINLESS STEEL) |
| LF | LINEAR OR LINEAL FEET | TYP. | TYPICAL |
| LP | LOW POINT | UC | UTILITY CONFLICT |
| | | | |

VERIFY

WATERMAIN

SITE REQUIREMENTS:

PROPERTY ADDRESS: 1241 ULYSSES AVE NE - BLAINE, MN 55434
PROPERTY DESCRIPTION: LOT 1, BLOCK 2, OUTLOT B, BLAINE SQUARE

LOT AREA: 60,812 SF ~ 1.40 ACRES IMPERVIOUS AREA: 41,556 SF ~ 0.95 ACRES ~ 68.3% PERVIOUS AREA: 19,256 SF ~ 0.44 ACRES ~ 31.7%

ZONING: B-3, REGIONAL COMMERCIAL

MATCH EXISTING

LOT COVERAGE:

REQUIRED: NO MAXIMUM PERCENTAGE OF LOT COVERAGE

FRONT YARD BUILDING SETBACK:.

REQUIRED: 50.00 FT

PROVIDED: 83.78 FT (WEST)

SIDE YARD BUILDING SETBACK: REQUIRED: 20.00 FT

PROVIDED: 50.39 FT (NORTH)
PROVIDED: 20.00 FT (SOUTH)

REAR YARD BUILDING SETBACK:

REQUIRED: 50.00 FT PROVIDED: 87.27 FT (EAST)


PARKING REQUIREMENTS:

CITY REQUIREMENT: 4 SPACES + 2 PER SERVICE BAY 4 + 7 BAYS x 2 SPACES/BAY = 18 SPACES REQUIRED

TOTAL STALLS PROVIDED = 46 STALLS (INCLUDES 2 ADA STALLS)

NOTES:

- 1. A NOTICE OF INTENT TO OBTAIN A STORM WATER POLLUTION CONTROL PERMIT SHALL BE ACQUIRED BY THE CONTRACTOR AND OWNER FROM THE MINNSOTA POLLUTION CONTROL AGENCY (MPCA) A MINIMUM OF 7 DAYS PRIOR TO CONSTRUCTION. THIS NOTICE OF INTENT SHALL BE PROVIDED WITH THE BUILDING PERMIT APPLICATION.
- 2. ALL WORK WITHIN THE CITY ROW SHALL FOLLOW THE CITY OF BLAINE STANDARD SPECIFICATIONS.
- 3. DIMENSIONS LISTED ARE TO FACE OF CURB UNLESS NOTED OTHERWISE.
- 4. THE CONTRACTOR SHALL FOLLOW THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD) STANDARDS AND GUIDES FOR TRAFFIC CONTROL FOR STREET AND HIGHWAY CONSTRUCTION.
- 5. THE CONTRACTOR SHALL FOLLOW CITY OF BLAINE AND MNDOT STANDARD DRAWINGS WHEN SETTING UP THE TRAFFIC CONTROL DEVICES.



REVIEWED


MRR


PROJECT NUMBER

2314-00145.1

04/09/2024

CENTE





SANITARY SEWER & WATER:

- 1. ALL WORK WITHIN THE CITY ROW SHALL FOLLOW THE CITY OF BLAINE STANDARD SPECIFICATIONS.
- 2. ALL PIPE DIMENSIONS ARE LISTED TO CENTER OF STRUCTURE.
- 3. CONTRACTOR SHALL FIELD VERIFY ALL EXISTING PIPE MATERIALS, SIZES, AND LOCATIONS AT ALL LOCATIONS.
- 4. SITE UTILITY CONTRACTOR SHALL COORDINATE WITH BUILDING MECHANICAL CONTRACTOR FOR UTILITY CONNECTIONS, LOCATIONS, AND ELEVATIONS.
- 5. TRACER WIRE SHALL BE INSTALLED ON SANITARY SEWER SERVICES & WATER SERVICES.
- 6. SEE SHEETS C700-C701 FOR UTILITY DETAILS.
- 7. SEE SHEET C401 FOR STORM SEWER LAYOUT
- 8. MINIMUM WATER BURY DEPTH 7'-6"

STRUCTURE SUMMARY TABLE

| STRUCTURE NO. | SAN MH-1 |
|-----------------|----------------|
| SIZE/TYPE | 48" MANHOLE |
| MANUFACTURER | CONCRETE |
| CASTING - FRAME | NEENAH R-1733 |
| CASTING - GRATE | SOLID |
| | EX. 6" 139° 6" |

MODELS AND MANUFACTURES INCLUDED IN CASTING SCHEDULE ARE "OR EQUAL" ITEMS, CONTRACTOR MAY SUBMIT SIMILAR ALTERNATE PRODUCTS FOR REVIEW BY THE ENGINEER.



DEF REVIEWED

MRR PROJECT NUMBER 2314-00145.1 04/09/2024


SCHWAB TIRE CENTER
LES SCHWAB
BLAINE, MINNESOTA

CERTIFICATION

I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION, OI
REPORT WAS PREPARED BY ME OR UNDER MY DIRECT
SUPERVISION AND THAT I AM A DULY LICENSED
PROFESSIONAL ENGINEER UNDER THE LAWS OF THE
STATE OF MINNESOTA.

NAVD 88

PRINTED NAME: DOUGLAS FOSTER




STORM SEWER:

- 1. ALL WORK WITHIN THE CITY ROW SHALL FOLLOW THE CITY OF BLAINE STANDARD SPECIFICATIONS.
- 2. ALL PIPE DIMENSIONS ARE LISTED TO CENTER OF STRUCTURE.
- 3. CONTRACTOR SHALL FIELD VERIFY ALL EXISTING PIPE MATERIALS, SIZES, AND LOCATIONS AT ALL LOCATIONS.
- 4. SITE UTILITY CONTRACTOR SHALL COORDINATE WITH BUILDING MECHANICAL CONTRACTOR FOR UTILITY CONNECTIONS, LOCATIONS, AND ELEVATIONS.
- 5. SEE SHEETS C700-C701 FOR UTILITY DETAILS.
- 6. SEE SHEET C400 FOR SANITARY SEWER & WATER LAYOUT
- 7. WATER QUALITY LEVEL:
- 7.1. WEST BIORETENTION POND ELEV = 901.547.2. EAST BIORETENTION POND ELEV = 902.05
- 8. THE HIGH WATER LEVEL IN THE UNDERGROUND TANK FOR THE 100 YEAR STORM EVENT IS 901.13.

STRUCTURE SUMMARY TABLE

| OTTOOTOTE COMMINICT TABLE | | | | | |
|---------------------------|-------------------------------|--|-----------------------|---------------|---------------|
| STRUCTURE NO. | ST MH-1 | ST MH-2 | ST MH-3 | ST MH-4 | |
| SIZE/TYPE | 48" MANHOLE | 48" MANHOLE | 48" MANHOLE | 48" MANHOLE | |
| MANUFACTURER | CONCRETE | CONCRETE | CONCRETE | CONCRETE | |
| CASTING - FRAME | NEENAH R-1733 | NEENAH R-1733 | NEENAH R-1733 | NEENAH R-1733 | |
| CASTING - GRATE | SOLID | SOLID | SOLID | SOLID | |
| | 8" 90° 8" | 12" 90° 12" 90° 90° 12" | 12" 90° 12" | 12" | |
| STRUCTURE NO. | ST MH-5 | ST MH-6 | ST MH-7 | CB-1 | CB-2 |
| SIZE/TYPE | 48" MANHOLE | 48" MANHOLE | 96" MANHOLE | 48" MANHOLE | 48" MANHOLE |
| MANUFACTURER | CONCRETE | CONCRETE | CONCRETE | CONCRETE | CONCRETE |
| CASTING - FRAME | NEENAH R-1733 | NEENAH R-1733 | NEENAH R-1733 | NEENAH R-1733 | NEENAH R-1733 |
| CASTING - GRATE | SOLID | SOLID | SOLID | SOLID | SOLID |
| | 12" 180° 180° 12" | 12" | 12" (| 12" (| 4" (|


MODELS AND MANUFACTURES INCLUDED IN CASTING SCHEDULE ARE "OR EQUAL" ITEMS, CONTRACTOR MAY SUBMIT SIMILAR ALTERNATE PRODUCTS FOR REVIEW BY THE ENGINEER.





DEF


MRR
PROJECT NUMBER
2314-00145.1


04/09/2024











THE PROJECT CONSISTS OF A NEW BUILDING, UNDERGROUND UTILITIES, PARKING LOT, AND LANDSCAPING. THE PROJECT IS LOCATED ON OUTLOT B IN LOT 1, BLOCK 2, OF BLAINE SQUARE, LOCATED IN THE NORTHWEST QUARTER OF SECTION 8, TOWNSHIP 31 NORTH, RANGE 23, TO THE CITY OF BLAINE, ANOKA COUNTY, MINNESOTA. THE SITE IS LOCATED ON A 1.39 ACRE PARCEL WITH AN ESTIMATED DISTURBANCE OF 1.24 ACRES.

THE SITE IS CURRENTLY A VACANT LOT AND CONTAINS MOSTLY PERVIOUS AREA AND GENERALLY DRAINS TO THE SOUTHEAST AT GRADUAL GRADES.

THE PROPOSED SITE WILL CONSIST MAINLY OF IMPERVIOUS SURFACES, SUCH AS THE NEW BUILDING AND PARKING LOT. STORMWATER WILL BE COLLECTED BY INLETS AND STORM SEWER WHICH WILL DRAIN TO THE CITY STORM SEWER.

CONSTRUCTION SCHEDULE

1. INSTALL TEMPORARY EROSION CONTROL (I.E. CONSTRUCTION ENTRANCE, SILT FENCE, INLET PROTECTION, ETC.)

- 2. STRIP TOPSOIL AND STOCKPILE ONSITE.
- 3. INSTALL TEMPORARY SOIL STABILIZATION ON DISTURBED AREAS
- 4. EXCAVATE AND INSTALL BUILDING FOUNDATION SITE GRADING
- 6. INSTALL WATER, SANITARY SEWER, AND STORM SEWER
- 7. INSTALL INLET PROTECTION ON NEW INLETS.
- 8. COMPLETE FINAL GRADING ACTIVITIES 9. COMPLETE PAVING OPERATIONS
- 10. MULCH AND SEED ALL DISTURBED AREAS WITHIN 14 DAYS OF TOPSOIL PLACEMENT AND GRADING.

THE EXISTING SOILS FOR THE SITE CONSISTING PRIMARILY OF ZIMMERMAN FINE SANE..

MISSISSIPPI RIVER THE ULTIMATE RECEIVING WATER FOR THE SITE AND IS AN IMPAIRED WATER FOR ANY CONSTRUCTION RELATED ACTIVITIES AND IS GREATER THAN 1 MILE FROM THE CONSTRUCTION ACTIVITY.

OPERATIONAL CONTROLS

- 1. THE CONTRACTOR SHALL PREPARE AND SUBMIT THE SWPPP PERMIT AND A NOTICE OF INTENT AND EROSION CONTROL PLAN TO THE OWNER 35 DAYS PRIOR TO THE START OF CONSTRUCTION ACTIVITIES FOR REVIEW.
- 2. THE CONTRACTOR AND OWNER ARE JOINTLY REQUIRED TO SUBMIT A NOTICE OF INTENT (NOI) TO THE MINNESOTA POLLUTION CONTROL AGENCY AT LEAST 7 DAYS PRIOR TO THE START OF CONSTRUCTION ACTIVITIES.
- 3. THE CONTRACTOR IS RESPONSIBLE FOR IMPLEMENTING THE SWPPP AS REQUIRED BY THE MINNESOTA POLLUTION CONTROL AGENCY. THE PLAN PROVIDES STRUCTURAL CONTROLS AND/OR STABILIZATION PRACTICES DESIGNED TO MINIMIZE POLLUTANTS IN THE STORMWATER DISCHARGE, TO MINIMIZE EROSION ON THE SITE, AND TO ELIMINATE TRACKING OF SOILS OFFSITE BY VEHICLES.
- 4. A REGULAR PROGRAM OF INSPECTION AND MAINTENANCE OF THE EROSION, SEDIMENT AND POLLUTION CONTROLS WILL BE MAINTAINED, MODIFIED, AND SUPPLEMENTED BY ADDITIONAL MEASURES IN ORDER TO ADEQUATELY MINIMIZE POLLUTANTS.
- 5. THE CONTRACTOR SHALL UPDATE SWPPP IF DIFFERENT FROM SWPPP PLAN THROUGHOUT CONSTRUCTION.
- 6. THE CONTRACTOR AND OWNER ARE JOINTLY REQUIRED TO SUBMIT A NOTICE OF TERMINATION (NOT) AFTER THE SITE HAS BEEN STABILIZED, CONSTRUCTION IS COMPLETE, AND TEMPORARY EROSION CONTROL MEASURES HAVE BEEN REMOVED.
- 7. STORMWATER MANAGEMENT CONTROLS IN ADDITION TO THOSE SHOWN ON THE PLANS SHALL BE PLACED, MAINTAINED, AND REMOVED AT THE DISCRETION OF THE CONTRACTOR OR AT THE DIRECTION OF THE ENGINEER AS NECESSARY.

- 1. PRODUCTS WILL BE KEPT IN THEIR ORIGINAL CONTAINERS WITH THE ORIGINAL MANUFACTURER'S LABEL, UNLESS THE CONTAINER IS NOT RE-SEALABLE. ORIGINAL LABELS AND MATERIAL SAFETY DATA WILL BE RETAINED FOR IMPORTANT PRODUCT SAFETY INFORMATION.
- 2. ALL HAZARDOUS MATERIALS STORAGE AREAS SHALL HAVE RESTRICTED ACCESS TO PREVENT VANDALISM. 3. WHENEVER POSSIBLE, ALL OF A PRODUCT WILL BE USED UP BEFORE DISPOSING OF THE CONTAINER. IF SURPLUS PRODUCT MUST BE DISPOSED OF,
- MANUFACTURER'S OR AGENCY-RECOMMENDED METHODS OF PROPER DISPOSAL WILL BE FOLLOWED.
- 4. MANUFACTURES' RECOMMENDATIONS FOR PROPER USE AND DISPOSAL WILL BE FOLLOWED.
- 5. ALL NON-HAZARDOUS WASTE MATERIALS WILL BE COLLECTED AND STORED IN SECURELY LIDDED METAL DUMPSTERS OR OTHER APPROVED CONTAINMENT METHOD AT THE END OF EACH DAY.
- 6. ALL TRASH AND CONSTRUCTION DEBRIS FROM THE SITE WILL BE DEPOSITED IN THE DUMPSTER. THE DUMPSTER WILL BE EMPTIED AS NECESSARY TO FUNCTION AS INTENDED FOR DEBRIS COLLECTION. NO CONSTRUCTION MATERIALS WILL BE BURIED ONSITE. ALL PERSONNEL WILL BE INSTRUCTED BY THE CONTRACTOR'S EROSION CONTROL SUPERVISOR REGARDING THE CORRECT PROCEDURE FOR WASTE DISPOSAL
- 7. ALL SANITARY WASTE WILL BE COLLECTED FROM THE PORTABLE UNITS AT A RATE NECESSARY TO MAINTAIN DESIGNED FUNCTION, BY A LICENSED SANITARY WASTE MANAGEMENT CONTRACTOR.
- 8. GOOD HOUSEKEEPING AND SPILL CONTROL PRACTICES WILL BE FOLLOWED DURING CONSTRUCTION TO MINIMIZE STORMWATER CONTAMINATION FROM PETROLEUM PRODUCTS, FERTILIZERS, PAINTS, CONCRETE, AND ANY OTHER PRODUCTS USED IN CONSTRUCTION ACTIVITIES.
- 9. FERTILIZERS WILL BE STORED IN A COVERED SHED AND PARTIALLY USED BAGS WILL BE TRANSFERRED TO A SEALABLE BIN TO AVOID SPILLS.

OPERATOR SHALL UTILIZE ROCK CONSTRUCTION ENTRANCE(S) AND WASH-DOWN STATIONS AS NEEDED TO MINIMIZED OFFSITE TRACKING. THE OPERATOR SHALL, AT THE END OF EACH SHIFT OR MORE FREQUENTLY IF REQUIRED, UTILIZE A STREET CLEANER TO REMOVE ANY ACCUMULATED SEDIMENT

OPERATOR SHALL USE SUFFICIENT WATER DURING SITE CLEARING AND GRADING ACTIVITIES TO MINIMIZE THE GENERATION OF DUST AND BLOWING SOILS.

SITE INSPECTIONS SHALL BE PERFORMED BY THE OPERATOR BEGINNING WITH THE INITIAL SITE CLEARING AND GRADING THROUGH THE COMPLETION OF ALL PROJECT ACTIVITIES. UPON INSPECTION OF PROBLEM AREAS, CORRECTIVE ACTION SHALL BE TAKEN WITHIN 24 HOURS. INSPECTION AND CORRECTIVE ACTIONS TAKEN SHALL BE RECORDED BY THE OPERATOR AND SHALL BE INCLUDED WITH THE PROJECT FILE. INSPECTIONS SHALL BE PERFORMED AT LEAST ONCE EVERY SEVEN DAYS AND FOLLOWING A 0.5 INCH RAIN EVENT WITHIN A 24-HOUR PERIOD.

SEDIMENTATION CONTROL DEVICES SHALL BE REPAIRED, REPLACED, OR SUPPLEMENTED WHEN THEY BECOME NONFUNCTIONAL FOLLOWING SECTION 11.1-11.2 INSEPECTIONS AND MAINTENANCE OF THE CSW PERMIT. THE PARTY RESPONSIBLE FOR MAINTENANCE SHALL BE NOTIFIED OF DEFICIENT SEDIMENTATION CONTROL DEVICES AND CORRECTIVE ACTIONS SHALL BE TAKEN WITHIN 24 HOURS OF DISCOVER OF THE PROBLEM.

SPILL PREVENTION AND RESPONSE PROCEDURES

- 1. ALL VEHICLES ONSITE WILL BE MONITORED FOR LEAKS AND RECEIVE REGULAR MAINTENANCE TO REDUCE THE CHANCE OF LEAKAGE.
- 2. PETROLEUM PRODUCTS WILL BE STORED IN TIGHTLY SEALED CONTAINERS WHICH ARE CLEARLY LABELED. 3. SPILL KITS WILL BE INCLUDED WITH ALL FUELING SOURCES AND MAINTENANCE ACTIVITIES. SECONDARY CONTAINMENT MEASURES WILL BE INSTALLED
- AND MAINTAINED BY THE CONTRACTOR.
- 4. ANY ASPHALT SUBSTANCES USED ONSITE WILL BE APPLIED ACCORDING TO THE MANUFACTURER'S RECOMMENDATION. 5. ALL PAINT CONTAINERS AND CURING COMPOUNDS WILL BE TIGHTLY SEALED AND STORED WHEN NOT REQUIRED FOR USE. EXCESS PAINT WILL NOT BE
- DISCHARGED TO THE STORM SEWER SYSTEM, BUT WILL BE PROPERLY DISPOSED ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS OR 6. MATERIALS AND EQUIPMENT NECESSARY FOR SPILL CLEANUP WILL BE KEPT IN THE TEMPORARY MATERIAL STORAGE TRAILER ONSITE. EQUIPMENT

WILL INCLUDE, BUT NOT BE LIMITED TO, BROOMS, DUST PANS, MOPS, RAGS, GLOVES, GOGGLES, KITTY LITTER OR OIL ABSORBENTS, SAND, SAW DUST,

- OIL ABSORBENT BOOMS AND DIAPERS AND PLASTIC AND METAL TRASH CONTAINERS DEDICATED TO SPILL CLEANUP. 7. ALL SPILLS WILL BE CLEANED UP IMMEDIATELY UPON DISCOVERY. SPILLS LARGE ENOUGH TO REACH THE STORM
- CONVEYANCE SYSTEM WILL BE REPORTED TO THE MINNESOTA POLLUTION CONTROL AGENCY
- 8. THE SPILL PREVENTION PLAN SHALL BE ADJUSTED TO INCLUDE MEASURES TO PREVENT THIS TYPE OF SPILL FROM REOCCURRING AND HOW TO CLEAN UP THE SPILL IF THERE IS ANOTHER ONE. A DESCRIPTION OF THE SPILL, WHAT
- CAUSED IT, AND THE CLEANUP MEASURES WILL ALSO BE INCLUDED. 9. SPRAY GUNS WILL BE CLEANED ON A REMOVABLE TARP OR OTHER APPROVED METHOD.
- 10. CONCRETE TRUCKS WILL NOT BE ALLOWED TO WASH OUT OR DISCHARGE SURPLUS CONCRETE OR DRUM WASH
- WATER ON THE SITE, UNLESS DONE IN AN ENGINEERED CONTAINMENT SYSTEM. 11. FORM RELEASE OIL USED FOR DECORATIVE STONE OR CONCRETE WORK WILL BE APPLIED OVER A PALLET COVERED WITH AN ABSORBENT MATERIAL TO COLLECT EXCESS FLUID. THE ABSORBENT MATERIAL WILL BE
- REPLACED AND DISPOSED OF PROPERLY WHEN SATURATED.

EMPLOYEE TRAINING

REQUIREMENTS OF SECTIONS 5.20 AND 21.2 FOR CONTRACT APPROVAL.

THE OPERATOR SHALL PROVIDE PROPER TRAINING AND EDUCATION TO THEIR RESPECTIVE EMPLOYEES AND SUBCONTRACTORS WITH RESPECT TO SPILL RESPONSE PROCEDURES, GOOD HOUSE KEEPING PRACTICES, AND

CONCRETE GRINDINGS AND SLURRY


OPERATOR SHALL ESTABLISH AND MAINTAIN A CONCRETE WASHOUT AREA THAT WILL NOT ALLOW WASH WATER, GRINDINGS, OR SLURRY TO EXIT THE SITE WASTE MATERIAL FROM THE WASH OUT SHALL BE TRUCKED OFFSITE BY THE OPERATOR AND DISPOSED OF PROPERLY AT NO TIME SHALL THE WASTE MATERIAL BE USED AS ENGINEERED FILL MATERIAL OR DISPOSED

OF IN THE GRADING ACTIVITIES AT THE SUBJECT PROJECT LOCATION.

DEWATERING AND BASIN DRAINING OPERATIONS

EROSION AND SEDIMENT CONTROL PRACTICES.

THE OPERATOR SHALL EMPLOY APPROPRIATE METHODS TO ENSURE THAT NO SEDIMENT LADEN WATER IS ALLOWED TO INFILTRATE THE EXISTING DRAINAGE SYSTEM AND THAT NO EROSION IS CAUSED BY THE DISCHARGE OF THE DE-WATERING METHODS.



SIONAL ENGINEER UNDER THE LAWS OF TH STATE OF MINNESOTA.

DEF


REVIEWED


MRR


PROJECT NUMBER


2314-00145.1

04/09/2024









Weight: 87 lbs., Shipping: 1 Carton, ships via UPS

Installation Time: I hour on average Compartment Size: Holds approx. 100 sets of keys
Security: '/s'' plate steel fabrication, Master 6210 High Security padlock
Mounting: Bolts to concrete using four high tensile Spikes

1-800-666-1283 SECURE INDUSTRIES / KEYKEEPER

NOTE: 1. SEE SHEET A151 FOR MANUFACTURER, MAKE, AND MODEL INFORMATION.

2. INSTALL PER MANUFACTURER'S RECOMMENDATIONS.

3. SEE SHEET A150 FOR LOCATION(S)

KEYKEEPER WITH STAND

NOT TO SCALE



NOTE:
1. GLOBAL INDUSTRIAL: 6' OUTDOOR PARK BENCH WITH BLACK,

STEE SLAT, BLACK #T9F694854BK.
INSTALL PER MANUFACTURER'S RECOMMENDATIONS. 3. SEE SHEET A150 FOR LOCATIONS(S).







1. GLOBAL INDUSTRIAL: OUTDOOR SLATTED STEEL TRASH CAN WITH RAIN BONNET LID, 36 GALLON, BLACK #T9F260804BK.

INSTALL PER MANUFACTURER'S RECOMMENDATIONS.
 SEE SHEET A150 FOR LOCATIONS(S).





ACCESSIBLE PARKING STRIPING NOT TO SCALE



1. PROVIDE (1) SIGN PER HANDICAP SPACE. SEE SITE PLAN FOR EXACT LOCATION.


ISOLATION JOINT NOT REQUIRED WITH FLEXIBLE PAVEMENT OR GRASS.
 SIGNS MAY BE MOUNTED TO SURFACE OF BUILDING WHERE POST MOUNTING IS

4. SIGNS SHALL BE 60" MIN. ABOVE GROUND SURFACE, MEASURED TO BOTTOM OF

THE SIGN. IF PLACED IN SIDEWALKS, SIGNS SHALL BE 84" ABOVE GROUND

5. SIGN SHALL BE PLACED 3' FROM BACK OF CURB AND GUTTER.





1. IF A STOOP IS WITHIN "BACKFILL ZONE A" THE 5' AREA MAY BE OMITTED TO MAINTAIN A CONSISTENT TRANSITION SLOPE.

AREAS NOT IDENTIFIED AS "BACKFILL ZONE A" MAY BE BACKFILLED WITH NATIVE SOILS OR NON-FROST SUSCEPTIBLE FILL. 3. IF TRANSITION SLOPES EXTENDS INTO LANDSCAPED AREAS, CAP THE SURFACE WITH 12" OF CLAY MATERIALS TO PREVENT

INFILTRATION.

BACKFILL ZONE A

NOT TO SCALE

SCHWAB TIRE CENTER
LES SCHWAB


DEF REVIEWED MRR PROJECT NUMBER 2314-00145.1


04/09/2024

CERTIFICATION


I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION, C
REPORT WAS PREPARED BY ME OR UNDER MY DIREC'
SUPERVISION AND THAT I AM A DULY LICENSED
PROFESSIONAL ENGINEER UNDER THE LAWS OF THE
STATE OF MINNESOTA.

PRINTED NAME: DOUGLAS FOSTER





NOT TO SCALE






NOT TO SCALE




RAIN GUARDIAN TURRET 12" CROSS-SECTION VIEW U.S. PATENT NOS. 8,501,016 AND 8,858,804




RAIN GUARDIAN TURRET 12" PLAN VIEW U.S. PATENT NOS. 8,501,016 AND 8,858,804


BIORETENTION WITH LINER





4 RAIN GUARDIAN TURRET

DEF REVIEWED DEF PROJECT NUMBER 2314-00145.1 04/09/2024 TIRE CENTE










CERTIFICATION

I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION, REPORT WAS PREPARED BY ME OR UNDER MY DIREC SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

PRINTED NAME: ______ DOUGLAS FOSTER

SIGNATURE: ______ LICENSE NUMBER: 6118



PLANTING NOTES:

- 1. GENERAL NOTES APPLY.
- 2. SEE SPECIFICATIONS 32 9113 SOIL PREPARATION AND 32 9300 PLANTS.
- 3. EVALUATE EXISTING SITE CONDITIONS AND REMEDY AS REQUIRED TO PROVIDE FOR HEALTHY PLANT GROWTH AND MITIGATE UNSIGHTLY CONDITIONS.
- 4. RE-GRADE, PREPARE SOIL AND PLANT ALL AREAS DISTURBED BY CONSTRUCTION ACTIVITY. PLANT PER PLANTING PLAN. FOR DISTURBANCES BEYOND PLAN, MATCH EXISTING PLANTS AND ACCESSORIES. A DISTURBED AREA SHALL BE WHERE CONSTRUCTION ACTIVITIES INCLUDING TRENCHING, DEMOLITION, EARTHWORK, MATERIAL STORAGE, STAGING AND PARKING OR ANY OTHER FORM OF EXCAVATION, COMPACTION, OR TRAFFIC RESULTS IN THE REMOVAL OR DISPLACEMENT OF EXISTING GROUNDCOVER OR GRADE. PROVIDE SMOOTH AND CLEAN TRANSITION BETWEEN EXISTING AND DISTURBANCES. IRRIGATION DISTURBANCE AREAS ARE CONCEPTUAL, COORDINATE ACTUAL.
- 5. PERFORM SOIL SAMPLING AND TESTING AS SPECIFIED.
- 6. PREPARE SUBGRADE AND PLACE SOIL PER SPECIFICATION 329113 'SOIL PREPARATION' FOR PLANTING SOIL. COORDINATE TOPSOIL INSTALLATION WITH OTHER TRADES. IF SUBSOIL CONDITIONS SHOW EVIDENCE OF UNEXPECTED WATER SEEPAGE OR RETENTION NOTIFY LANDSCAPE ARCHITECT IMMEDIATELY AND MITIGATE AS REQUIRED.
- 7. AMEND PLANTING SOIL AS SPECIFIED. SEE SPEC 329113 SOIL PREPARATION. FOR COMPACTED AREAS (PREVIOUSLY PAVED/HARDPAN AREAS), SCARIFY SOILS AS SPECIFIED AND MODIFY PLANTING PIT AS SPECIFIED & DETAILED.
- 8. ALL PLANT MATERIAL SHALL RECEIVE AN ADEQUATE AMOUNT OF WATER TO MEET ITS WATERING REQUIREMENTS AND SHALL BE SUPPLIED BY AN AUTOMATIC UNDERGROUND IRRIGATION SYSTEM. SEE SPEC 328400 PLANTING IRRIGATION AND IRRIGATION PLAN.
- 9. PRIOR TO PLANTING, IRRIGATION SYSTEM SHALL BE FULLY OPERATIONAL AND PLANTING AREAS SHALL BE HAVE APPROPRIATE MOISTURE FOR INSTALLING PLANTS
- 10. INSTALL PLANTINGS AND ACCESSORIES AS DETAILED AND PER PROJECT MANUAL SPECIFICATIONS.
- 11. CONTRACTOR SHALL SELECT PLANT SPECIES APPROPRIATE TO THE AREA, LOCALLY AVAILABLE AND COMPLIANT WITH CITY REQUIREMENTS. SUBMIT SPECIES LAYOUT TO THE LANDSCAPE ARCHITECT FOR APPROVAL.

TREE, SHRUB, AND PERENNIAL NOTES:

- 12. PRIOR TO PLANTING INSTALLATION, CONTRACTOR TO CONFIRM CONTACT LANDSCAPE ARCHITECT FOR REVIEW OF PLANT LAYOUT PRIOR TO DIGGING PLANTING HOLES.
- 13. ALL PLANT MATERIAL SHALL BE INSTALLED AS DETAILED AND SPECIFIED AND CONFORM TO THE CURRENT AMERICAN NURSERY AND LANDSCAPE ASSOCIATION STANDARD FOR NURSERY STOCK.
- 14. CONTRACTOR SHALL VERIFY ALL PLANT QUANTITIES. THE ILLUSTRATED LOCATION SHALL DICTATE COUNT.
- 15. NO PLANT SUBSTITUTIONS WILL BE ALLOWED WITHOUT WRITTEN CONSENT FROM THE LANDSCAPE ARCHITECT.
- 16. WARRANTY PLANT MATERIAL AS SPECIFIED.

MULCH NOTES:

- 17. ALL LANDSCAPE BEDS WITH CONTAINER PLANTS ARE TO RECEIVE MULCH AS SPECIFIED. MODIFY FINISH GRADE ADJACENT TO WALKING SURFACES TO PREVENT MULCH FROM MIGRATING OR WASHING ONTO SUCH SURFACES DURING RAIN EVENTS
- 18. SUBMIT SAMPLE OF MULCH TO LANDSCAPE ARCHITECT FOR REVIEW PRIOR TO INSTALLATION.
- 19. EDGING LOCATION AS NOTED ON DRAWINGS AND DETAILS.

GENERAL NOTES:

- 20. VERIFY EXISTING CONDITIONS AND LOCATE ALL EXISTING UTILITIES INCLUDING ANY THAT MAY NOT BE INDICATED ON THIS PLAN. NOTIFY LANDSCAPE ARCHITECT OF ANY DISCREPANCIES.
- 21. PROTECT ALL EXISTING IMPROVEMENTS TO REMAIN AND REPAIR BACK TO ORIGINAL CONDITION AT CONTRACTOR'S EXPENSE IF DAMAGE OCCURS RESULTANT FROM CONTRACTOR'S OPERATIONS OR NEGLIGENCE.
- 22. PROVIDE ALL DEMOLITION INCIDENTAL TO OR REQUIRED FOR NEW CONSTRUCTION WHETHER OR NOT IT IS SPECIFICALLY NOTED.
- 23. DO NOT SCALE DRAWINGS. CONTRACTOR TO FIELD VERIFY ALL DIMENSIONS AND EXISTING CONDITIONS PRIOR TO BEGINNING WORK. START OF WORK CONSTITUTES ACCEPTANCE OF CONDITIONS.


- 24. CHANGES OR DEVIATIONS FROM THE DRAWINGS MADE WITHOUT THE WRITTEN CONSENT OF THE LANDSCAPE ARCHITECT AND/OR AN APPROVED CHANGE ORDER WILL BE CONSIDERED UNAUTHORIZED. COORDINATE NECESSARY MODIFICATIONS WITH ARCHITECT PRIOR TO EXECUTING CONSTRUCTION. SEE SPECIFICATIONS FOR CONTRACT MODIFICATION PROCEDURES AND AS-BUILT REQUIREMENTS.
- 25. REVIEW ALL DISCIPLINE DRAWINGS AND COORDINATE WITH GENERAL CONTRACTOR AND ALL TRADE CONTRACTORS FOR WORK SHOWN ON LANDSCAPE DRAWINGS AND SPECIFICATIONS.
- 26. NOTIFY LANDSCAPE ARCHITECT AND OWNER IN WRITING OF ANY EXPECTED DISRUPTIONS IN SERVICE OR CHANGES IN CONSTRUCTION SCHEDULE AND OBTAIN WRITTEN PERMISSION AS SPECIFIED.
- 27. IN THE EVENT OF ANY DISCREPANCIES, NOTIFY THE LANDSCAPE ARCHITECT IMMEDIATELY.
- 28. NO SUBSTITUTIONS WILL BE ALLOWED WITHOUT WRITTEN CONSENT FROM THE LANDSCAPE ARCHITECT.
- 29. PROVIDE ALL COMPONENTS AND ACCESSORIES FOR A COMPLETE AND FINISHED INSTALLATION FOR PRODUCTS SHOWN ON THE DRAWING SHEETS.
- 30. THE PROJECT MANUAL SPECIFICATIONS ARE AN INTEGRAL PART OF THESE DOCUMENTS. REVIEW ALL PROJECT INFORMATION.
- 31. ELECTRONIC FILES FOR LAYOUT AVAILABLE UPON WRITTEN REQUEST.
- 32. DURING ALL INSTALLATION, KEEP ADJACENT PAVING, CONSTRUCTION AREAS, AND WORK AREAS CLEAN AND IN ORDERLY CONDITION. PROTECT ALL STRUCTURES, UTILITIES, AND SITE IMPROVEMENTS, INCLUDING PLANT AND IRRIGATION MATERIALS FROM DAMAGE DUE TO LANDSCAPE OPERATIONS OR ACTIVITIES BY OTHER CONTRACTORS AND TRADES. MAINTAIN PROTECTION DURING INSTALLATION AND MAINTENANCE PERIODS. TREAT, REPAIR, OR REPLACE ANY DAMAGED IMPROVEMENTS, INCLUDING PLANTINGS OR IRRIGATION EQUIPMENT.


GENERAL DEMOLITION NOTES

- 33. SEE CIVIL FOR ALL SITE DEMOLITION, INCLUDING TREE REMOVAL AND TOPSOIL STOCKPILE
- 34. REMOVE EXISTING GROUNDCOVER AND PLANTINGS IN UNDISTURBED AREAS PROPOSED FOR NEW GROUND COVER AND PLANTINGS. SEE SPECIFICATIONS FOR
- 35. SEE PLANTING PLANS, PLANTING DETAILS AND PLANT PROTECTION SPECIFICATION FOR PLANTINGS TO REMAIN.

GENERAL IRRIGATION NOTES:

- 1. ALL PLUMBING AND ELECTRICAL WORK SHALL BE COMPLETED AS PER ALL LOCAL CODES.
- 2. ALL MATERIALS SHALL BE NEW, WITHOUT FLAWS AND CONSIDERED THE BEST AVAILABLE IN STOCK. THE COMPLETE SYSTEM SHALL HAVE A ONE-YEAR WARRANTY AFTER FINAL PROJECT ACCEPTANCE ON ALL PARTS AND LABOR.
- 3. PRIOR TO FINAL PROJECT ACCEPTANCE, THE CONTRACTOR SHALL INSTRUCT THE OWNER, OR HIS REPRESENTATIVE, IN THE PROPER OPERATION, MAINTENANCE, AND WINTERIZATION OF THE ENTIRE IRRIGATION SYSTEM.
- 4. THE IRRIGATION SYSTEM SHALL BE ZONED AS TO PROVIDE THE APPROPRIATE AMOUNT OF WATER SUPPLY TO EACH TYPE OF LANDSCAPE PLANT AS REQUIRED BY SIZE, SPECIES, SOIL CONDITIONS, AND EXPOSURE TO SUN AND WIND.
- 5. WHEN THE SYSTEM IS COMPLETE, THE CONTRACTOR SHALL PERFORM A COVERAGE TEST. THE IRRIGATION SYSTEM SHALL PROVIDE 100% COVERAGE OF ALL LAWN & LANDSCAPE PLANTING AREAS.
- 6. THE IRRIGATION SYSTEM SHALL BE CONSTRUCTED FOR WINTERIZATION BY THE CONTRACTOR.
- 7. ALL IRRIGATION VALVES SHALL BE LOCATED IN PROFESSIONAL GRADE VALVE BOXES. SIZE OF VALVE BOXES SHALL VARY WITH NUMBER OF VALVES LOCATED IN BOX. ALL VALVE BOX LID ELEVATIONS SHALL BE SET FLUSH WITH FINISHED GRADE. PROVIDE BOX SIZE THAT WILL ALLOW 6" CLEARANCE AROUND ALL SIDES OF VALVES. PROVIDE BOLTS PER MANUFACTURER'S RECOMMENDATIONS AND SECURE EACH VALVE BOX.
- 8. WIRE CONNECTORS SHALL BE USED ON ALL FIELD WIRE SPLICES AND CONNECTIONS.
- 9. ALL CONTROL WIRE SHALL BEAR A U/L APPROVED LABEL FOR DIRECT UNDERGROUND BURIAL IN NATIONAL ELECTRIC CODE CLASS IT CIRCUITS. AWG SIZES. ALL CONTROL WIRE RUNS LESS THAN 1000' SHALL HAVE NO SPLICES. IF A SPLICE OCCURS ON A FIELD CONTROL WIRE, THE CONTRACTOR SHALL INSTALL THE SPLICE IN A 6" ROUND VALVE BOX USING APPROVED WATERTIGHT CONNECTORS. IF APPROVED BY THE LANDSCAPE ARCHITECT OR DESIGN PROFESSIONAL.
- 10. IRRIGATION VALVE BOXES ARE TO BE INSTALLED IN LANDSCAPE PLANTING AREAS OR OTHER PROTECTED SPACES WHEN POSSIBLE. VALVE BOXES SHALL NOT BE INSTALLED IN LAWN AREAS IF IT CAN BE AVOIDED.
- 11. THE CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL UNDERGROUND UTILITIES PRIOR TO ANY CONSTRUCTION. THE ACQUISITION OF ALL NECESSARY PERMITS ASSOCIATED WITH CONSTRUCTION SHALL BE THE CONTRACTORS RESPONSIBILITY.
- 12. NO ¾" PIPE SHALL BE USED ANYWHERE ON THE SPRAY IRRIGATION SYSTEM. (EXCEPT FOR ¾" SWING JOINT ASSEMBLIES FOR ROTOR OR POP-UP SPRAY HEADS).
- 13. THE CONTRACTOR SHALL EXPOSE ENDS OF ALL IRRIGATION SLEEVES. ANY BROKEN OR SHATTERED ENDS OF THE IRRIGATION SLEEVES SHALL BE CUT TO A CLEAN END BEFORE INSTALLATION OF EITHER MAINLINE PIPE, LATERAL LINES OR DRIP IRRIGATION TUBING.
- 14. FINAL CONNECTION OF THE VALVE WIRES TO THE CONTROLLER SHALL BE THE CONTRACTOR'S RESPONSIBILITY.
- 15. THE CONTRACTOR SHALL, AT HIS OWN EXPENSE, LOCATE ALL UNDERGROUND UTILITIES, WHICH MAY AFFECT HIS OPERATION DURING CONSTRUCTION AND SHALL TAKE ALL NECESSARY PRECAUTIONS TO AVOID DAMAGE TO THE SAME.
- 16. THE CONTRACTOR SHALL USE EXTREME CAUTION WHEN WORKING NEAR OVERHEAD OR UNDERGROUND POWER AND/OR TELEPHONE, WATER, GAS AND SEWER FACILITIES SO AS TO SAFELY PROTECT ALL UTILITIES, PERSONNEL, AND EQUIPMENT, AND SHALL BE RESPONSIBLE FOR ALL COSTS AND LIABILITY IN CONNECTION THEREWITH.
- 17. THE CONTRACTOR SHALL TAKE ALL PRECAUTIONARY MEASURES NECESSARY TO PROTECT EXISTING IMPROVEMENTS, WHICH ARE TO REMAIN IN PLACE FROM DAMAGE AND ALL SUCH IMPROVEMENTS DAMAGED BY THE CONTRACTOR'S OPERATIONS SHALL BE REPAIRED OR RECONSTRUCTED TO THE OWNER'S SATISFACTION AT THE CONTRACTOR'S EXPENSE.
- 18. ALL MAINLINES SHALL BE PRESSURE TESTED AT 1.5 TIMES THE STATIC PRESSURE FOR A MINIMUM 2 HOUR PERIOD PRIOR TO BACKFILLING OF TRENCHES. TEST WILL BE CONSIDERED SUCCESSFUL IF NO PRESSURE LOSS OCCURS DURING THE TWO HOURS. IF ANY LEAKS ARE PRESENT, THEY SHALL BE CORRECTED AND LINES SHALL BE RE-TESTED PRIOR TO BACKFILLING TRENCHES.
- 19. PIPE SIZES SHALL CONFORM TO THOSE SHOWN ON THE DRAWINGS. NO SUBSTITUTIONS OF SMALLER PIPE SIZES SHALL BE PERMITTED, BUT SUBSTITUTIONS OF LARGER SIZES MAY BE APPROVED. ALL DAMAGED AND REJECTED PIPE SHALL BE REMOVED FROM THE SITE AT THE TIME OF SAID REJECTION.
- 20. THE CONTRACTOR SHALL FLUSH ALL LATERALS AND EMITTER LINES PRIOR TO INSTALLING EMITTERS.
- 21. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO FAMILIARIZE HIMSELF WITH ALL GRADE DIFFERENCES, LOCATION OF WALLS, STRUCTURES AND UTILITIES. THE IRRIGATION CONTRACTOR SHALL REPAIR OR REPLACE ALL ITEMS DAMAGED BY HIS WORK. HE SHALL COORDINATE HIS WORK WITH OTHER CONTRACTORS FOR THE LOCATION AND INSTALLATION OF PIPE SLEEVES AND LATERALS UNDER SIDEWALKS AND PAVING.
- 22. SHOULD DISCREPANCIES ARISE BETWEEN THESE PLANS AND ACTUAL FIELD CONDITIONS, WHICH REQUIRE FIELD MODIFICATIONS OR PLAN REVISIONS, THE LANDSCAPE ARCHITECT, DESIGN PROFESSIONAL, OR OWNER'S REPRESENTATIVE SHALL BE CONTACTED PRIOR TO CONSTRUCTION FOR RESOLUTION OR PLAN REVISION.
- 23. DO NOT WILLFULLY INSTALL THE IRRIGATION SYSTEM AS SHOWN ON THE DRAWINGS WHEN IT IS OBVIOUS IN THE FIELD THAT UNKNOWN OBSTRUCTIONS, GRADE DIFFERENCES OR DIFFERENCES IN THE AREA DIMENSIONS EXIST THAT MIGHT NOT HAVE BEEN CONSIDERED IN THE DESIGN. SUCH OBSTRUCTIONS OR DIFFERENCES SHOULD BE BROUGHT TO THE ATTENTION OF THE LANDSCAPE ARCHITECT, DESIGN PROFESSIONAL OR THE OWNER'S REPRESENTATIVE. IN THE EVENT THIS NOTIFICATION IS NOT PERFORMED, THE CONTRACTOR SHALL ASSUME FULL RESPONSIBILITY FOR ANY REVISIONS NECESSARY.
- 24. THE IRRIGATION CONTROLLER SHALL BE WIRED DIRECTLY TO A 110 VOLT POWER SOURCE. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO PROVIDE IRRIGATION CONTROLLER WIRING TO THE POWER SOURCE. CONNECTING THE CONTROLLER TO THE POWER SOURCE SHALL BE THE RESPONSIBILITY OF A LICENSED ELECTRICAL CONTRACTOR. THE INSTALLATION SHALL BE IN ACCORDANCE WITH THE NATIONAL ELECTRICAL CODE AND ANY LOCAL CODES OR ORDINANCES THAT APPLY. IT SHALL BE THE ELECTRICAL CONTRACTOR'S RESPONSIBILITY TO COORDINATE THE POWER SOURCE AND EXACT LOCATION OF THE CONTROLLER WITH OWNER'S REPRESENTATIVE.






____ LICENSE NUMBER: 61186

SHEET L200

PMB

2314-00145.

1SSUE DATE 04/09/2024





Permit Application Review Report Date: 8/7/2024

Board Meeting Date: 8/12/2024

Agenda Item: 15

Applicant/Landowner: National Sports Center Attn: Neil Ladd 1700 105th Ave NE Blaine, MN 55449

Project Name: Turf Field and Campus Improvements

Project PAN: P-24-004

Project Purpose: Conversion of natural turf fields to artificial turf and a 30-foot-wide roadway

Project Location: Numerous locations across National Sports Center Campus, 1700 105th Ave

NE, Blaine

Site Size: size of parcel - 300 acres; size of disturbed area - 34.29 acres; size of regulated

impervious surface - 0.67

Applicable District Rule(s): Rule 2, Rule 3, Rule 4, Rule 6

Recommendation: Approve with 2 Conditions and 4 Stipulations

Description: The National Sports Center is proposing several improvements to the campus including widening of an existing roadway, regrading of multiple soccer fields, roadway and sidewalk reconfiguring, and reconstruction of an existing pond. An interim grading permit was approved (3/11/24) and issued on March 13, 2024, which encompassed the proposed soccer field grading. This approval is for the remainder of the proposed work. The total disturbance is 34.29 acres. The project will create 0.67 acres of regulated impervious. The project area drains to County Ditch 41. The relevant water resource concerns are stormwater management, erosion and sediment control, and floodplain. These correlate to District Rules 3, 4, and 6. See attached Figure 1: Project Location and Figure 2: Site Plan.

Conditions to be Met Before Permit Issuance:

Rule 2.7 – Procedural Requirements

1. Submittal of a performance escrow in the amount of \$6,485.00 for increase in area of disturbance from previously approved application.

Rule 3.0 – Stormwater Management

2. Provide proof of recording of a fully executed Operations and Maintenance Agreement for the perpetual inspection and maintenance of all proposed stormwater management practices after review and approval by the District.

Stipulations: The permit will be issued with the following stipulations as conditions of the permit. By accepting the permit, the applicant agrees to these stipulations:

- 1. The applicant must apply for coverage under the Minnesota Pollution Control Agency's (MPCA's) Construction Stormwater Permit (Permit No: MNR100001)
- 2. If dewatering is required, provide DNR dewatering permit prior to construction. If a DNR permit is not required, provide well-field location, rates, discharge location, schedule and quantities prior to construction.
- 3. Submittal of grading as-builts for the project to confirm adequate floodplain compensatory storage has been provided.
- 4. Submittal of as-builts for the stormwater management practices and associated structures listed in Tables 2 and 3, including volume, critical elevations and proof of installation for hydrodynamic separators.

Exhibits:

| Exhibit Type | Exhibit Author | Signature Date | Received Date |
|--|----------------|----------------|---------------|
| MIDS | Bolton & Menk | | 06/03/2024 |
| Construction Plans | Bolton & Menk | 06/03/2024 | 06/03/2024 |
| HydroCAD Models (Existing&Proposed) | Bolton & Menk | | 07/17/2024 |
| Project Narrative & Stormwater Management Plan | Bolton & Menk | 07/17/2024 | 07/17/2024 |
| Construction Plans | Bolton & Menk | 05/31/2024 | 07/17/2024 |

Findings

Fees and Escrows (Rule 2.7): The applicant has submitted a \$4,800.00 application fee and deposit which corresponds with the nonrefundable application fee (\$10), base fee for a Commercial/Industrial Development project of 300 acres (\$4,500.00), and addition to base fee (\$300.00). The applicant will be required to submit a performance escrow in the amount of \$6,485.00. This corresponds to a base escrow of \$2,000, plus an additional \$500/acre of disturbance (8.97 acres of land disturbance proposed). The applicant has already paid escrow fees of \$14,660.00 for previously approved disturbance of 25.32 acres.

Stormwater Management (Rule 3.0):

Rule 3.0 applies to the proposed project because it includes land disturbing activities creating a cumulative total of 10,000 sf or more of new or fully reconstructed impervious surface.

The Hydrologic Soil Group (HSG) of soils on site are HSG A.

Rate Control: Peak stormwater flow rate at each point of site discharge increases from the predevelopment condition for the several precipitation events as shown in Table 1. The rate increase for the existing NSC pond discharge point results in a static bounce of less than 0.1 feet in the pond, which is entirely contained within the applicant's property. No surrounding structures would be impacted. The rate increase for the Super Rink pond was modeled in XPSWMMM and showed no adverse impacts and no increase in downstream high water levels. The project will not impact Drainage Sensitive Use areas. The rate control standard is considered met.

| Point of | 2-year (cfs) | | 10-year (cfs | 5) | 100-year (cfs) | |
|------------|--------------|----------|--------------|----------|----------------|----------|
| Discharge | Existing | Proposed | Existing | Proposed | Existing | Proposed |
| Super Rink | 0.87 | 0.07 | 1.39 | 1.53 | 2.53 | 2.64 |
| Pond | | | | | | |
| CD 41 | 0.38 | 0.24 | 0.58 | 0.36 | 1.32 | 1.22 |

| Existing NSC | 0 | 0.18 | 0.02 | 0.27 | 0.65 | 1.26 |
|--------------|---|------|------|------|------|------|
| Pond | | | | | | |

Table 1.

Volume Control:

The application proposes redevelopment which does not disturb more than 50% of the site or reconstruct more than 50% of the existing impervious surface, therefore the volume reduction requirement is equal to 1.1 inches over the area of new and fully reconstructed impervious surface. The amount of proposed impervious required to be treated is 29,338 ft².

The applicant is proposing the Stormwater Management Practices (SMPs) described below:

| Drainage Area | Impervious required to be treated (ft²) | Proposed SMP | TP Removal Factor | Required Water Quality Volume (ft ³) | Water Quality Volume Provided (ft ³) |
|---------------------------------------|---|--------------------------|----------------------|---|--|
| Access Rd Basin 1 (1S) | 11,984 | Infiltration basin 1 | 1 | 1,098 | 2,618 |
| Access Rd Basin 2 (2S) | 6,357 | Infiltration Basin 2 | 1 | 582 | 1,623 |
| Access Rd - Existing NSC Pond | 2,253 | NSC Pond | 0.5 | 413 | 413 |
| NSC Entrance Basin 3 (5S) | 4,342 | Biofiltration Basin 3 | 0.65 | 612 | 1,483 |
| NSC Entrance- Super Rink Pnd | 4,402 | Super Rink Pond | 0.5 | 807 | 807 |
| Totals: | 29,338 | | | 3,514 | 6,944 |

Table 2.

The following pretreatment has been provided:

| SMP ID | Pretreatment Device/Method | Percent TSS Removal |
|-----------------------|----------------------------|---------------------|
| Biofiltration Basin 3 | Vegetated Filter Strip | 80 |
| Infiltration Basin 2 | Vegetated Filter Strip | 80 |
| Infiltration Basin 1 | Vegetated Filter Strip | 80 |

Table 3.

Pretreatment is required to be designed such that the device/method provides removal of 80% TSS entering an infiltration or filtration Stormwater Management Practice. The proposed project meets pretreatment requirements as shown in Table 3.

The volume control standard has been met as shown in Table 2.

Water Quality: The total Water Quality Volume has been provided in aggregate.

Stormwater treatment on site must remove at least 80% of the average annual post development TSS per discharge location. The following TSS removal has been provided:

| Discharge Point | TSS Removal Provided |
|-------------------|----------------------|
| Super Rink Pond | 93 |
| CD 41 | 100 |
| Existing NSC Pond | 100 |

Table 4.

The TSS removal standard is met at each discharge point as shown in Table 4.

Discharges to Wetlands: Stormwater from the proposed project is not being discharged into any wetlands, therefore this section does not apply.

Landlocked Basins: The proposed drainage system does not outlet to a landlocked basin, therefore this section does not apply.

Low Floor Freeboard: The proposed project is not considered new development with buildings and habitable structures; therefore, this section does not apply.

Maintenance:

Access: Sufficient maintenance access has been provided on the plans for all stormwater management practices.

Maintenance Agreements: The proposed stormwater management practices will not be maintained as part of standard municipal public work activities. Therefore, a maintenance agreement that meets District standards will be required.

Soils and Erosion Control (Rule 4.0)

Rule 4.0 applies to the proposed project because it is a land disturbing activity that requires a permit under another District rule.

The proposed project drains to Ditch 41. The soils affected by the project include Rifle and Lino and have a soil erodibility factor of 0.15 or greater. Disturbed areas are proposed to be stabilized within 24 hours, as required. The proposed erosion and sediment control plan includes perimeter control, rock construction entrance, inlet protection. The erosion control plan meets District Requirements. See attached Figure 3: Erosion and Sediment Control Plan.

Wetlands (Rule 5.0)

The proposed project does not include activities which result in the filling, draining, excavating, or otherwise altering the hydrology of a wetland. Rule 5.0 does not apply.

Floodplain (Rule 6.0)

Rule 6.0 applies to the proposed project because it includes land disturbing activities within or adjacent to the boundary of the 100-year flood elevation as mapped and modeled by the District.

The regulatory floodplain elevation ranges from 895.5 to 898.4 ft MSL. The application proposes the placement of fill within the floodplain. Compensatory storage is required. The proposed project is providing compensatory storage that exceeds the required 1:1 ratio and is within the relevant reach.

Drainage, Bridges, Culverts, and Utility Crossings (Rule 7.0)

The proposed project does not include land disturbing activities which construct, improve, repair, or alter the hydraulic characteristics of a bridge profile control or culvert structure on a creek, public ditch, or major watercourse. The proposed project does not include land disturbing activities which involve a pipeline or utility crossing of a creek, public ditch, or major watercourse.

The proposed project does not include land disturbing activities which construct, improve, repair or alter the hydraulic characteristics of a conveyance system that extends across two or more parcels of record not under common ownership and has a drainage area of 200 acres or greater. Rule 7.0 does not apply.

Buffers (Rule 8.0)

The proposed project does not include a land disturbing activity on land adjacent or directly contributing to a Public Water, Additional Waters, High or Outstanding Ecological Value Waters, a Public Ditch, or Impaired Waters/waters exceeding state water quality standards. Rule 8.0 does not apply.

Variances (Rule 10.2)

The proposed project is not requesting a variance from the District's rules, regulations, and policies. Rule 10.2 does not apply.

Figure 1: Project Location





Figure 2: Site Plan









Figure 3: Erosion and Sediment Control Plan








Figure 4: Floodplain Impact

NATIONAL SPORTS CENTER




MASC - COB FIELDS

BLAINE, MN

1700 105TH AVE, BLAINE, MN, 55449



VICINITY MAP



ALL CONSTRUCTION SHALL COMPLY WITH APPLICABLE STATE AND LOCAL ORDINANCES.

GENERAL NOTES

iii. OR APPROVED EQUAL.

12. ALL EROSION CONTROL METHODS SHALL COMPLY WITH MPCA AND LOCAL REGULATIONS.

 $oxed{13}$. MINIMIZE DISTURBANCE TO SITE AND PROTECT EXISTING SITE FEATURES (INCLUDING TURF AND VEGETATION) WHICH ARE TO REMAIN.

14. PROPOSED CONTOURS AND SPOT ELEVATIONS ARE SHOWN TO FINISH GRADE UNLESS OTHERWISE NOTED.

15. PROPOSED ELEVATIONS SHOWN TYPICALLY AS 99.1 OR 99 SHALL BE UNDERSTOOD TO MEAN 899.1 OR 899.

16. SPOT ELEVATIONS SHOWN IN PARKING LOTS, DRIVES AND ROADS INDICATE GUTTER GRADES, UNLESS NOTED OTHERWISE.

17. THE CONTRACTOR WILL BE SOLELY RESPONSIBLE FOR DETERMINING QUANTITIES OF CUT, FILL AND WASTE MATERIALS TO BE HANDLED, AND FOR AMOUNT OF GRADING TO BE DONE IN ORDER TO COMPLETELY PERFORM ALL WORK INDICATED ON THE DRAWINGS. IMPORT SUITABLE MATERIAL AND EXPORT UNSUITABLE / EXCESS / WASTE MATERIAL, AS REQUIRED, AT NO ADDITIONAL COST TO THE OWNER.

18. NO FINISHED SLOPES SHALL EXCEED 3' HORIZONTAL TO 1' VERTICAL (3:1), UNLESS OTHERWISE NOTED.

19. ALL DISTURBED AREAS WHICH ARE NOT DESIGNATED TO BE PAVED OR RECEIVE TURF. SHALL RECEIVE AT LEAST 6" OF TOPSOIL AND SHALL BE SEEDED. REFER TO FINISHING PLANS FOR SEED LOCATIONS. ALL AREAS NOT DESIGNATED FOR SOD OR A SPECIFIC SEED MIX, WHICH ARE DISTURBED BY CONSTRUCTION, SHALL BE SEEDED WITH SEED MIX #1.

20. FAILURE OF TURF DEVELOPMENT: IN THE EVENT THE CONTRACTOR FAILS TO PROVIDE AN ACCEPTABLE TURF, RE-SEED ALL APPLICABLE AREAS, AT NO ADDITIONAL COST TO THE OWNER, TO THE SATISFACTION OF THE ENGINEER OR LANDSCAPE

21. ALL STORM SEWER PIPE SHALL BE PVC PIPE (ASTM D3034, SDR 35) INSTALLED IN ACCORDANCE WITH ASTM D2321, UNLESS OTHERWISE NOTED.

22. ALL STORM SEWER PIPE CROSSING WATERMAIN, OUTSIDE OF THE PUBLIC RIGHT-OF-WAY, SHALL BE ASTM D2665, SCHEDULE 40 PVC WITH SOLVENT WELD JOINTS.

23. FLEXIBLE JOINTS AT STORM SEWER PIPE CONNECTIONS TO STRUCTURES: a. IN ACCORDANCE WITH MINNESOTA PLUMBING CODE, PROVIDE FLEXIBLE JOINTS AT ALL PIPE CONNECTIONS TO ALL STORM SEWER STRUCTURES.

b. ACCEPTABLE MANUFACTURERS / PRODUCTS:

i. FERNCO, "CONCRETE MANHOLE ADAPTORS" OR "LARGE-DIAMETER WATERSTOPS" ii. PRESS-SEAL, WATERSTOP GROUTING RINGS"

26. LOCATE ALL EXISTING UTILITIES. VERIFY LOCATION, SIZE AND INVERT ELEVATION OF ALL EXISTING UTILITIES. BEFORE BEGINNING CONSTRUCTION.

27. STAKE LIMITS OF WALKS AND CURBING PRIOR TO INSTALLATION OF GATE VALVES, CATCH BASINS, AND MANHOLES. ADJUST GATE VALVE AND MANHOLE LOCATIONS TO AVOID PLACEMENT OF THESE STRUCTURES IN WALKS AND CURB AND GUTTER. STAKE CURB AND GUTTER ALIGNMENTS TO ALLOW CURB INLET TYPE CATCH BASINS TO PROPERLY ALIGN WITH CURB AND GUTTER.

28. ALL DISTURBED AREAS INCLUDING SOIL STOCKPILE SHALL BE STABILIZED WITH VEGETATION WITHIN SEVEN (7) DAYS OF ROUGH GRADING OR 24 HOURS OF INACTIVITY.

DRAWING INDEX

NATIONAL SPORTS CENTER

EXISTING CONDITIONS AND REMOVALS PLAN SITE LAYOUT AND FINISHING PLAN

GRADING AND EROSION CONTROL PLAN

DRAIN TILE AND STORM SEWER PLAN

C1.21 **EXISTING CONDITIONS AND REMOVALS PLAN**

SITE LAYOUT AND FINISHING PLAN

GRADING AND EROSION CONTROL PLAN DRAIN TILE AND STORM SEWER PLAN

EXISTING CONDITIONS AND REMOVALS PLAN SITE LAYOUT AND FINISHING PLAN

GRADING AND EROSION CONTROL PLAN

DRAIN TILE AND STORM SEWER PLAN

SITE DETAILS

SITE DETAILS C2.12

SITE DETAILS

STORMWATER POLLUTION PREVENTION PLAN


SWPPP - PROJECT DESCRIPTION

SWPPP - SOILS MAP

SWPPP - NARRATIVE

PRELIMINARY DRAFT - FOR AGENCY REVIEW ONLY










0V1.131841


| SIGNED | RWK | NO. | ISSUED FOR | DATE | NATIONAL SPORTS CENTER, MINNESOTA |
|-----------|-----|-----|------------|------|-----------------------------------|
| AWN | RWK | | | | MASC - COB FIELDS |
| CKED | JRP | _ | | | IVIASC - COB FIELDS |
| ENT PROJ. | | | | | TITLE SHEET |






- 1. REFER TO SHEET C0.01 TITLE SHEET, FOR GENERAL NOTES.
- 2. CHECK ALL PLAN AND DETAIL DIMENSIONS AND VERIFY SAME BEFORE FIELD LAYOUT.
- 4. ALL DISTURBED AREAS WHICH ARE NOT DESIGNATED TO BE PAVED OR RECEIVE SYNTHETIC TURF SHALL RECEIVE AT LEAST 6" OF TOPSOIL AND SHALL BE
- 5. FAILURE OF TURF DEVELOPMENT: IN THE EVENT THE CONTRACTOR FAILS TO PROVIDE AN ACCEPTABLE TURF, THE CONTRACTOR SHALL RE-SEED ALL APPLICABLE AREAS, AT NO ADDITIONAL COST TO THE OWNER, TO THE SATISFACTION OF THE ENGINEER.






PRELIMINARY DRAFT - FOR AGENCY REVIEW ONLY










| [| DESIGNED | RWK | NO. | ISSUED FOR | DATE | NATIONAL CROPES OFFITED AMAINIFICATA | |
|----|--------------|-------|-----|------------|------|--------------------------------------|------|
| | RVK | KVVK | | | | NATIONAL SPORTS CENTER, MINNESOTA | SHE |
| F | DRAWN | | | | | | _ |
| - | 5101111 | RWK | | | | MASC - COB FIELDS | |
| H | | | - | | | IVIASC - COD I ILLUS | |
| 19 | CHECKED | JRP | | | | | TCO. |
| | | | | | | SITE REFERENCE PLAN | |
| (| CLIENT PROJ. | NO. | | | | SHE KEI EKENCE I EAN | |
| | 0V1.1 | 31841 | | | | | |











LEGEND

TREE REMOVALS



REMOVALS KEY NOTE

PROTECTION KEY NOTE

NOTES

- 1. REFER TO SHEET C1.0, TITLE SHEET, FOR GENERAL NOTES.
- 2. MINIMIZE DISTURBANCE TO SITE AND PROTECT EXISTING VEGETATION AND SITE FEATURES (CURBS, WALKS, PAVEMENTS, OVERHEAD AND UNDERGROUND UTILITIES, SIGNAGE, ROADWAYS, ETC.) WHICH ARE TO REMAIN.
- 3. REPAIR OR REPLACE EXISTING PROPERTY AND SITE FEATURES, INCLUDING GRASS AND VEGETATION, WHICH IS TO REMAIN THAT IS DAMAGED BY THE WORK, TO THE OWNER'S SATISFACTION AND AT NO ADDITIONAL COST TO THE OWNER.
- 4. HIRE THE SERVICES OF A UTILITY LOCATOR COMPANY TO LOCATE ALL PRIVATELY OWNED UTILITIES THAT MAY BE DISTURBED BY CONSTRUCTION OPERATIONS.

KEY NOTE LEGEND

REMOVE TREE, INCLUDING STUMP

REMOVE AND SALVAGE IRRIGATION

PROTECT TREE & LANDSCAPING


PROTECT EXISTING PAVEMENT

PROTECT STORM SEWER STRUCTURE

PROTECT STRUCTURE (MOVE IF NECESSARY)


PROTECT SIGN

PROTECT IRRIGATION CONTROLS ON POST



PRELIMINARY DRAFT - FOR AGENCY REVIEW ONLY








7575 GOLDEN VALLEY ROAD, SUITE 200 MINNEAPOLIS, MN, 55427

| | DESIGNED | DVA/I/ | NO. | NO. ISSUED FOR DATE | NATIONAL CROPES OFFITER AMAINIFOOTA | |
|-----|--------------|----------------------|----------|---------------------|-------------------------------------|--|
| DPA | | RWK | | | | NATIONAL SPORTS CENTER, MINNESOTA |
| | DRAWN | | | | | |
| | Divitivit | RWK | \vdash | | | FIELDS 29-32 |
| | | | | 116603 23-32 | | |
| | CHECKED | JRP | | | | |
| CI | | | | | | EXISTING CONDITIONS AND REMOVALS PLAN |
| | CLIENT PROJ. | NO. | | | | EXISTING CONDITIONS AND REMOVALS I LAN |
| | ∩\/1_1 | 0\/1 1318 <i>4</i> 1 | | | | |



- 1. REFER TO SHEET C1.0 TITLE SHEET FOR GENERAL NOTES.
- 2. CHECK ALL PLAN AND DETAIL DIMENSIONS AND VERIFY SAME BEFORE FIELD LAYOUT.
- 3. ALL DISTURBED AREAS WHICH ARE NOT WITHIN THE FIELDS SHALL RECEIVE AT LEAST 6" OF TOPSOIL AND SHALL BE SEEDED.
- 4. FAILURE OF TURF DEVELOPMENT: IN THE EVENT THE CONTRACTOR FAILS TO PROVIDE AN ACCEPTABLE TURF, THE CONTRACTOR SHALL RE-SEED ALL APPLICABLE AREAS, AT NO ADDITIONAL COST TO THE OWNER, TO THE SATISFACTION OF THE ENGINEER.

LEGEND



REFERENCE KEY TO SITE DETAILS DETAIL I.D NUMBER (TOP) DETAIL SHEET NUMBER (BOTTOM)



SYNTHETIC TURF FIELD (1) (C2.12)






FENCING KEY NOTE




FENCING KEY NOTES

5' HIGH CHAIN LINK FENCE WITH TOP AND BOTTOM RAIL

4' WIDE, 5' HIGH SINGLE SWING GATE WITH LOCKING DEVICE










PRELIMINARY DRAFT - FOR AGENCY REVIEW ONLY







7575 GOLDEN VALLEY ROAD, SUITE 200 MINNEAPOLIS, MN, 55427

| DESIG | NED | RWK | NO. | ISSUED FOR | DATE | NATIONAL SPORTS CENTER, MINNESOTA |
|-------|---------|-------|-----|------------|------|--|
| DDAVA | /h! | | | | | 147 (11314) (E.S. OKTS CENTER, WINGINGSOT) |
| DRAW | / N | RWK | | | | FIELDS 29-32 |
| | | | | | | FIELD3 29-32 |
| CHEC | KED | JRP | | | | |
| CLIEN | T PROJ. | NO | | | | SITE LAYOUT AND FINISHING PLAN |
| - | | 31841 | | | | |

C1.22




REFERENCE KEY TO SITE DETAILS DETAIL I.D. NUMBER (TOP) DETAIL SHEET NUMBER (BOTTOM) **EXISTING CONTOUR** EXISTING SPOT ELEVATION PROPOSED CONTOUR PROPOSED SPOT ELEVATION

ME = MATCH EXISTING

EOF = EMERGENCY OVERFLOW PROPOSED GRADING LIMITS PROPOSED MANHOLE (MH) PROPOSED CATCH BASIN (CB) PROPOSED FLARED END SECTION (FES)


PRELIMINARY DRAFT - FOR AGENCY REVIEW ONLY

C1.23






| - (| | \ | | | |
|---------------|--------|-----|------------|------|--|
| SIGNED | RWK R | NO. | ISSUED FOR | DATE | 114 TIONIAL CROPTS OF LITER AND LICOTA |
| | | | | | NATIONAL SPORTS CENTER, MINNESOTA |
| AWN | | | | | |
| AVVIN | RWK | | | | FIELDS 29-32 |
| | | | , , | ! | FIELDS 29-32 |
| CKED | JRP | | | | |
| | JIVL | | | | |
| ENT PROJ. NO. | NO | 1 | , | ! | GRADING AND EROSION CONTROL PLAN |
| | 121011 | | | | |




NOTES

- 1. REFER TO SHEET CO.01, TITLE SHEET, FOR GENERAL NOTES.
- 2. ALL STORM SEWER PIPE SHALL BE PVC PIPE (ASTM D3034, SDR 35) INSTALLED IN ACCORDANCE WITH ASTM D2321, UNLESS
- 3. ALL STORM SEWER PIPE CROSSING WATERMAIN, OUTSIDE OF THE PUBLIC RIGHT-OF-WAY, SHALL BE ASTM D2665, SCHEDULE 40 PVC WITH SOLVENT WELD JOINTS.
- 4. FLEXIBLE JOINTS AT STORM SEWER PIPE CONNECTIONS TO STRUCTURES:
- a. IN ACCORDANCE WITH MINNESOTA PLUMBING CODE, PROVIDE FLEXIBLE JOINTS AT ALL PIPE CONNECTIONS TO ALL STORM SEWER STRUCTURES.
- b. ACCEPTABLE MANUFACTURERS / PRODUCTS:
- i. FERNCO, "CONCRETE MANHOLE ADAPTORS" OR "LARGE-DIAMETER WATERSTOPS"
- ii. PRESS-SEAL, WATERSTOP GROUTING RINGS"
- iii. OR APPROVED EQUAL.
- 5. INSTALL MANOLES, CATCH BASINS, STORM SEWER, SANITARY SEWER, DRAIN TILE, AND OTHER POTENTIAL SOURCES OF CONTAMINATION AT LEAST 10 FEET HORIZONTALLY FROM ANY WATERMAIN PER MN PLUMBING CODE. THIS ISOLATION DISTANCE IS MEASURED FROM THE OUTER EDGE OF THE PIPE TO THE OUTER EDGE OF THE CONTAMINATION SOURCE (OUTER EDGE OF STRUCTURES OR SIMILAR).
- 6. LOCATE ALL EXISTING UTILITIES. VERIFY LOCATION, SIZE AND INVERT ELEVATION OF ALL EXISTING UTILITIES BEFORE BEGINNING
- 7. STAKE LIMITS OF WALKS AND CURBING PRIOR TO INSTALLATION OF GATE VALVES, CATCH BASINS, AND MANHOLES. ADJUST GATE VALVE AND MANHOLE LOCATIONS TO AVOID PLACEMENT OF THESE STRUCTURES IN WALKS AND CURB AND GUTTER. STAKE CURB AND GUTTER ALIGNMENTS TO ALLOW CURB INLET TYPE CATCH BASINS TO PROPERLY ALIGN WITH CURB AND GUTTER


LEGEND





PRELIMINARY DRAFT - FOR AGENCY REVIEW ONLY







7575 GOLDEN VALLEY ROAD, SUITE 200 MINNEAPOLIS, MN, 55427

| R\ | WK | 140. | ISSOLD FOR | DATE | NATIONAL SPORTS CENTER, MINNESOTA |
|--------------|------|------|------------|------|-----------------------------------|
| wn R' | WK | | | | FIELDS 29-32 |
| CKED IF | RP | | | | 112252532 |
| NT PROJ. NO. | ** | | | | DRAIN TILE AND STORM SEWER PLAN |
| O\/1 1219 | Q/I1 | | | | |

MINNESOTA C1.24



LEGEND

TREE REMOVALS

REMOVALS KEY NOTE

PROTECTION KEY NOTE

NOTES

- 1. REFER TO SHEET CO.01, TITLE SHEET, FOR GENERAL NOTES.
- 2. MINIMIZE DISTURBANCE TO SITE AND PROTECT EXISTING VEGETATION AND SITE FEATURES (CURBS, WALKS, PAVEMENTS, OVERHEAD AND UNDERGROUND UTILITIES, SIGNAGE, ROADWAYS, ETC.) WHICH ARE TO REMAIN.
- 3. REPAIR OR REPLACE EXISTING PROPERTY AND SITE FEATURES, INCLUDING GRASS AND VEGETATION, WHICH IS TO REMAIN THAT IS DAMAGED BY THE WORK, TO THE OWNER'S SATISFACTION AND AT NO ADDITIONAL COST TO THE OWNER.
- 4. HIRE THE SERVICES OF A UTILITY LOCATOR COMPANY TO LOCATE ALL PRIVATELY OWNED UTILITIES THAT MAY BE DISTURBED BY CONSTRUCTION OPERATIONS.

KEY NOTE LEGEND

REMOVE TREE, INCLUDING STUMP

REMOVE AND SALVAGE IRRIGATION

PROTECT TREE & LANDSCAPING


PROTECT EXISTING PAVEMENT

PROTECT STORM SEWER STRUCTURE

PROTECT STRUCTURE (MOVE IF NECESSARY)

PROTECT SIGN


PROTECT IRRIGATION CONTROLS ON POST



C1.31

PRELIMINARY DRAFT - FOR AGENCY REVIEW ONLY







7575 GOLDEN VALLEY ROAD, SUITE 200 MINNEAPOLIS, MN, 55427

| | | | V | | |
|------------------|--------|-----|------------|------|--|
| DESIGNED | DVA/I/ | NO. | ISSUED FOR | DATE | NATIONAL CROPES CENTER AMAINIFICATA |
| RWK | | | | | NATIONAL SPORTS CENTER, MINNESOTA |
| DRAWN | | | | | |
| DRAWN | RWK | | | | |
| | | | | | FIELDS 55 & 56 |
| CHECKED | JRP | | | | |
| | JKP | | | | EVICTIALS CONDITION AND DENAOVALS DIAM |
| CLIENT PROJ. NO. | | - | | | EXISTING CONDITION AND REMOVALS PLAN |
| | J. NO. | | | | |




NOTES:

- REFER TO SHEET C1.0 TITLE SHEET FOR GENERAL NOTES.
- 2. CHECK ALL PLAN AND DETAIL DIMENSIONS AND VERIFY SAME BEFORE FIELD LAYOUT.
- ALL DISTURBED AREAS WHICH ARE NOT WITHIN THE FIELDS SHALL RECEIVE AT LEAST 6" OF TOPSOIL AND SHALL BE SEEDED.
- 4. FAILURE OF TURF DEVELOPMENT: IN THE EVENT THE CONTRACTOR FAILS TO PROVIDE AN ACCEPTABLE TURF, THE CONTRACTOR SHALL RE-SEED ALL APPLICABLE AREAS, AT NO ADDITIONAL COST TO THE OWNER, TO THE SATISFACTION OF THE ENGINEER.

LEGEND




REFERENCE KEY TO SITE DETAILS DETAIL I.D NUMBER (TOP)
DETAIL SHEET NUMBER (BOTTOM)




PROPOSED CONCRETE WALK $\begin{pmatrix} 10 \\ (2.11) \end{pmatrix}$





PROPOSED CHAIN LINK FENCING WITH MAINTENANCE STRIP






FENCING KEY NOTE



FENCING KEY NOTES

5' HIGH CHAIN LINK FENCE WITH TOP AND BOTTOM RAIL 4' WIDE, 5' HIGH SINGLE SWING GATE WITH LOCKING DEVICE $\begin{pmatrix} 1 \\ C2.12 \end{pmatrix}$




14' WIDE, 5' HIGH DOUBLE SWING GATE WITH LOCKING DEVICE AND PLUNGER ROD $\begin{pmatrix} 1 \\ C2.12 \end{pmatrix}$

20' WIDE, 5' HIGH DOUBLE SWING GATE WITH LOCKING DEVICE AND PLUNGER ROD








PRELIMINARY DRAFT - FOR AGENCY REVIEW ONLY








7575 GOLDEN VALLEY ROAD, SUITE 200 MINNEAPOLIS, MN, 55427

| | RWK | | | | |
|--------|-------|---|---|---|--|
| | RWK | | | | |
| | | | | | |
|) | JRP | | | | |
| ROJ. I | | | | | |
| 1 1 | 21011 | ı | I | I | |

NATIONAL SPORTS CENTER, MINNESOTA FIELDS 55 & 56 SITE LAYOUT AND FINISHING PLAN

C1.32







NOTES

- 1. REFER TO SHEET CO.01, TITLE SHEET, FOR GENERAL NOTES.
- 2. ALL STORM SEWER PIPE SHALL BE PVC PIPE (ASTM D3034, SDR 35) INSTALLED IN ACCORDANCE WITH ASTM D2321, UNLESS
- 3. ALL STORM SEWER PIPE CROSSING WATERMAIN, OUTSIDE OF THE PUBLIC RIGHT-OF-WAY, SHALL BE ASTM D2665, SCHEDULE 40 PVC WITH SOLVENT WELD JOINTS.
- 4. FLEXIBLE JOINTS AT STORM SEWER PIPE CONNECTIONS TO STRUCTURES:
- a. IN ACCORDANCE WITH MINNESOTA PLUMBING CODE, PROVIDE FLEXIBLE JOINTS AT ALL PIPE CONNECTIONS TO ALL STORM SEWER STRUCTURES.
- b. ACCEPTABLE MANUFACTURERS / PRODUCTS:
- i. FERNCO, "CONCRETE MANHOLE ADAPTORS" OR "LARGE-DIAMETER WATERSTOPS"
- ii. PRESS-SEAL, WATERSTOP GROUTING RINGS"
- iii. OR APPROVED EQUAL.
- 5. INSTALL MANOLES, CATCH BASINS, STORM SEWER, SANITARY SEWER, DRAIN TILE, AND OTHER POTENTIAL SOURCES OF CONTAMINATION AT LEAST 10 FEET HORIZONTALLY FROM ANY WATERMAIN PER MN PLUMBING CODE. THIS ISOLATION DISTANCE IS MEASURED FROM THE OUTER EDGE OF THE PIPE TO THE OUTER EDGE OF THE CONTAMINATION SOURCE (OUTER EDGE OF STRUCTURES OR SIMILAR).
- 6. LOCATE ALL EXISTING UTILITIES. VERIFY LOCATION, SIZE AND INVERT ELEVATION OF ALL EXISTING UTILITIES BEFORE BEGINNING
- 7. STAKE LIMITS OF WALKS AND CURBING PRIOR TO INSTALLATION OF GATE VALVES, CATCH BASINS, AND MANHOLES. ADJUST GATE VALVE AND MANHOLE LOCATIONS TO AVOID PLACEMENT OF THESE STRUCTURES IN WALKS AND CURB AND GUTTER. STAKE CURB AND GUTTER ALIGNMENTS TO ALLOW CURB INLET TYPE CATCH BASINS TO PROPERLY ALIGN WITH CURB AND GUTTER

LEGEND






C1.34

PRELIMINARY DRAFT - FOR AGENCY REVIEW ONLY









7575 GOLDEN VALLEY ROAD, SUITE 200 MINNEAPOLIS, MN, 55427

| RWK | NO. | . ISSUED FOR | DATE | NATIONAL SPORTS CENTER, MINNESOTA |
|-------------|-----|--------------|------|-----------------------------------|
| rwK | | | | FIELDS 55 & 56 |
| JRP | | | | |
| T PROJ. NO. | | | | DRAIN TILE AND STORM SEWER PLAN |





TURF FIELD CROSS SECTION

C2.12


NOT TO SCALE

MNDOT SEED MIX 25-121 \ AND BLANKET CAT 25 MINIMUM 6" NATIVE TOPSOIL'-DEPTH = 1.5' ¬ 4H:1V EXISTING-OR SHALLOWER GROUND UNDISTURBED, UNCOMPACTED **INSITU SOIL** ~ ~ ~ ~ ~ ~ ~ ~ ` ***** ~ \ ~ ~ SCARIFY NATIVE SAND TO MINIMUM DEPTH OF 12"

> STORMWATER INFILTRATION BASIN C2.12 **BASINS 1 & 2** NOT TO SCALE


STORMWATER INFILTRATION BASIN NOTES:

- 1. INSTALL APPROPRIATE TEMPORARY EROSION CONTROL DEVICES TO PREVENT SEDIMENT FROM LEAVING OR ENTERING THE INFILTRATION AREA DURING CONSTRUCTION.
- 2. PERFORM WEEKLY INSPECTIONS, INCLUDING AFTER EACH RAINFALL EVENT.
- 3. ROUGH GRADE THE SITE.
- COMPLETE, STABILIZE, AND VEGETATE ALL OTHER SITE IMPROVEMENTS.
- COMPLETE GRADING AND STABILIZATION OF INFILTRATION AREA ONLY AFTER THE CONTRIBUTING DRAINAGE AREA'S VEGETATION HAS REACHED 70% GROWTH OF PERMANENT PERENNIAL VEGETATION, OR PLACEMENT OF SOIL STABILIZATION AND APPROVED BY ENGINEER, AND BEFORE CONSTRUCTION AND INSTALLING VEGETATION IN INFILTRATION AREAS.
- 6. REMOVE TEMPORARY EROSION CONTROL DEVICES AFTER THE CONTRIBUTING DRAINAGE AREA AFTER VEGETATION HAS REACHED 70% GROWTH OF PERMANENT PERENNIAL VEGETATION.
- 7. IN THE EVENT THAT SEDIMENT IS INTRODUCED INTO THE BMP DURING OR IMMEDIATELY FOLLOWING EXCAVATION, THIS MATERIAL SHALL BE REMOVED FROM THE PRACTICE PRIOR TO CONTINUING CONSTRUCTION.
- 8. SUBGRADE SHALL BE PREPARED SO THAT THE AREA BENEATH THE BASINS AND EMBANKMENTS IS STRIPPED OF ALL VEGETATION, TOPSOIL, AND ORGANIC MATTER.
- 9. INSTALLATION WITH DRY SOIL CONDITIONS IS CRITICAL TO PREVENT SMEARING AND COMPACTION. SCHEDULE WORK FOR PERIODS OF DRY WEATHER. DO NOT WORK IF SOIL CONDITIONS ARE WET. EXCAVATION, SOIL PLACEMENT AND RAPID STABILIZATION OF PERIMETER SLOPES WITH METHODS SHOWN ON PLAN MUST BE COMPLETED BEFORE THE NEXT PRECIPITATION EVENT.
- 10. REMOVAL OF ACCUMULATED SEDIMENT AND DEBRIS SHALL BE DONE BY HAND OR, IF SELF-PROPELLED EQUIPMENT IS REQUIRED, FROM OUTSIDE THE PERIMETER OF THE INFILTRATION AREAS.




PRELIMINARY DRAFT - FOR AGENCY REVIEW ONLY










| RWK NO | NO. | ISSUED FOR | DATE | NATIONAL CROPTS OF STEP AMAINIFECTA | |
|----------|-------|------------|------|-------------------------------------|-----------------------------------|
| RVVK | | | | | NATIONAL SPORTS CENTER, MINNESOTA |
| VN | RWK | | | | MASC - COB FIELDS |
| | | . | | | IVIASC - COB FIELDS |
| KED | JRP | | | | CITE DETAIL C |
| IT PROJ. | NO. | | | | SITE DETAILS |
|)V1.1 | 31841 | | | | |

STORMWATER POLLUTION PREVENTION PLAN (SWPPP)

NATIONAL SPORTS CENTER - 2024

CITY OF BLAINE ANOKA COUNTY, MINNESOTA



RESPONSIBLE PARTIES:

The Contractor and Owner will be joint applicants under the MPCA's General Stormwater Permit for Construction Activity as required by the National Pollutant Discharge Elimination System (NPDES) Phase II program.

The Contractor shall provide one or more trained Construction SWPPP Manager(s) knowledgeable and experienced in the application of erosion prevention and sediment control BMPs that will oversee the implementation of the SWPPP, and the installation, inspection and maintenance of the erosion prevention and sediment control BMPs.

A Construction SWPPP Manager must be available for an on-site inspection within 72 hours upon request by the MPCA.

| | COMPANY | CONTACT PERSON | PHONE |
|--------------------------------------|------------------------|----------------|--------------|
| OWNER: | National Sports Center | Neil Ladd | 763-785-5600 |
| SWPPP DESIGNER: | Bolton & Menk, Inc. | Paul Strong | 651-247-8789 |
| CONTRACTOR: | Dimke Excavating | Tom Dimke | 612-225-7100 |
| CONSTRUCTION SWPPP MANAGER: | TBD | TBD | TBD |
| PARTY RESPONSIBLE FOR LONG TERM O&M: | National Sports Center | Neil Ladd | 763-785-5600 |

The SWPPP Designer, Construction SWPPP Manager, and BMP Installer must have appropriate training. Documentation showing training commensurate with the job duties and responsibilities is required to be included in the SWPPP prior to any work beginning on the site. Training documentation for the SWPPP Designer is included on the Narrative sheet. The Contractor shall attach training documentation to this SWPPP for the Construction SWPPP Manager and BMP Installer prior to the start of construction. This information shall be kept up to date until the project NOT is filed.

ADDITIONAL COMPENSATION

Payment for all work associated with Erosion and Sediment Control shall be as described in the Project Manual. Unless otherwise authorized by the Owner no additional payment shall be made for any work required to administer and maintain the site erosion and sediment control in compliance with the Minnesota Pollution Control Agency (MPCA) - General Stormwater Permit for Construction Activity (MN R100001) including but not limited to inspection, maintenance, and removal of BMPs or addition of BMPs to accommodate Contractor phasing.

DOCUMENT RETENTION

Permittees must make the SWPPP, including all inspection reports, maintenance records, training records and other information required by this permit, available to federal, state, and local officials within three (3) days upon request for the duration of the permit and for three (3) years following the NOT.

GENERAL STORMWATER DISCHARGE REQUIREMENTS

All requirements listed in Section 5.1 of the Permit for the design of the permanent stormwater management system and discharge have been included in the preparation of this SWPPP. These include but are not limited to:

- 1. The expected amount, frequency, intensity, and duration of precipitation.
- 2. The nature of stormwater runoff and run-on at the site
- 3. Peak flow rates and stormwater volumes to minimize erosion at outlets and downstream channel and stream bank erosion.
- 4. The range of soil particle sizes expected to be present on the site.

Permanent stormwater treatment systems for this project have been designed in accordance with the guidance in the MN Stormwater Manual in place at the time of bidding. Copies of the design information and calculations are part of this SWPPP and will be provided in digital format upon written request to the Engineer.

PROJECT AREAS:

| Total Project Size (disturbed area) = | 25.1 | ACRES |
|--|------|-------|
| Existing area of impervious surface = | 0.13 | ACRES |
| Post construction area of impervious surface = | 0.60 | ACRES |
| Total new impervious surface area created = | 0.47 | ACRES |
| · | | |

Planned Construction Start Date: Estimated Construction Completion Date:

03/18/2024 11/30/2024

PERMANENT STORMWATER MANAGEMENT SYSTEM:

Type of storm water management used if more than 1 acre of new impervious surface is created:

| | Wet Sedimentation Basin |
|----|--|
| | Infiltration/Filtration |
| | Regional Pond |
| X* | Permanent Stormwater Management Not Required |

*Less than 1 acre of land disturbed

PROJECT LOCATION:

| COUNTY | TOWNSHIP | RANGE | SECTION | LATITUDE | LONGITUDE |
|--------|----------|-------|---------|-----------|------------|
| ANOKA | T31N | R23W | 20,21 | 45.16155° | -93.22559° |
| | | | | | |

| BMP SUMMARY | QUANTITY | UNIT |
|-------------------------|----------|------|
| Construction Entrance | 1 | EACH |
| Silt Fence | 6771 | LF |
| Inlet Protection Device | 2 | EACH |
| Turf Seed Mix | 4.5000 | AC |
| Native Seed Mix | 0.9000 | AC |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |


DESCRIPTION OF CONSTRUCTION ACTIVITIES AND STORMWATER MANAGEMENT:

Construction activities include: Site grading, turf field construction, road construction, temporary erosion and sediment control, and permanent stabilization.

Numerous fields are proposed to be converted from natural turf to artificial turf. Natural turf will be excavated and the fields will be graded to prepare for artificial turf installation. A new 30' wide connecting roadway and adjacent walking path will be constructed. Shallow depressions for infiltration and rate control were designed to treat the additional impervious. Another depression was designed to treat runofff from an additional parking resulting in 0.12 acres of new impervious.

Stormwater currently sheet flows west, primarily into county ditch 41. In addition, stormwater also flows to several onsite stormwater management facilities.

After construction is complete, stormwater will flow the same as pre-construction.



RECEIVING WATERS:

Receiving waters, including surface water, wetlands, Public Waters, and stormwater ponds, within 1-mile of the project boundary are identified on the USGS 7.5 min quad map above. Receiving waters that are impaired, the impairment, and WLA are listed as follows. All specific BMPs relative to construction activities listed in the permit for special, prohibited, restricted, or impaired have been incorporated into this plan. All specific BMPs listed in approved TMDLs and those BMPs listed for construction related waste load allocations have also been incorporated.

| NAME OF WATER BODY | TYPE (ditch, pond, wetland, lake, etc.) | Special, Prohibited, Restricted Water ¹ | Flows to Impaired Water Within 1-Mile ² | USEPA Approved Construction Related TMDL ³ |
|--------------------|---|---|---|---|
| County Ditch 41 | Ditch | No | No | - |
| | | | | |

¹ Special, prohibited, and restricted waters are listed in Section 23 of the MN Construction Stormwater General Permit (MNR100001).

² Identified as impaired under section 303 (d) of the federal Clean Water Act for phosphorus, turbidity, TSS, dissolved oxygen, and/or aquatic biota.


IMPLEMENTATION SCHEDULE AND PHASING: The Contractor is required to provide an updated schedule and site management plan meeting the minimum requirements of Section 1717 of the Minnesota Standard Specifications for Construction.

³ Construction Related TMDLs include those related to: phosphorus, turbidity, TSS, dissolved oxygen, and/or aquatic biota.

- 1) Submit SWPPP Updates to Engineer. Submittal shall include any requested changes to the SWPPP, including but not limited to: Trained Personnel, Locations for Stockpiles, Concrete Washout, Sanitation Facilities, Types and Locations of Erosion & Sediment Control. Failure to submit updates shall be considered acceptance of the SWPPP as designed with no changes.
- 2) Install perimeter sediment control, inlet protection, and construction exit.
- 3) Grade site,
- 4) Construct turf fields, walking paths, and depressions
- 5) Pave roadway and parking area
- 6) Add additional temporary BMPs as necessary during construction based on inspection reports.
- Add additional temporary bivirs as necessary duri
 Ensure final stabilization measures are complete.
- 8) Provide digital copy of all Field SWPPP Documentation including Inspection Reports and SWPPP Revisions to the Owner.
- 9) Submit Notice of Termination (NOT) to MPCA. NOTE: The NOT must be submitted to MPCA before Final Stabilization is considered complete.

PRELIMINARY DRAFT - FOR AGENCY REVIEW ONLY










| DESIGNED | RWK | NO. | ISSUED FOR | DATE | NATIONAL CROPTS OF LIFE AMAINIFICATA | |
|--------------|---------|-----|------------|------|--------------------------------------|----------------|
| | KVVK | | | | NATIONAL SPORTS CENTER, MINNESOTA | SHEET |
| DRAWN | RWK | | | | | _ |
| ΓV | 11.0017 | | | | MASC - COB FIELDS | C2 11 |
| CHECKED | JRP | | | | | ∃C3. 11 |
| | •••• | | | | SWPPP - PROJECT DESCRIPTION | |
| CLIENT PROJ. | NO. | | | | SWITT TROJECT DESCRIPTION | |
| 0V1.1 | 31841 | 1 1 | | | | |



PROJECT BOUNDARY

STEEP SLOPES (>33.3%)

IMPAIRED, SPECIAL OR PROTECTED WATERS

Hyd. Soil

Group

A/D

A/D

A/D

NATIONAL WETLANDS INVENTORY

PRELIMINARY DRAFT - FOR AGENCY REVIEW ONLY

C3.12

SOIL TYPE

Soil Name

SWPPP AMENDMENTS AND SUBMITTALS

Contractor must prepare and submit to the Engineer a SWPPP amendment as necessary to include additional Best Management Practices (BMPs) to correct problems identified or address the following situations.

- 1. Contact information and training documentation for Construction SWPPP Manager and BMP Installer,
- 2. There is a change in construction method of phasing, operation, maintenance, weather or seasonal conditions not anticipated during the design of the SWPPP including but not limited to:
- a. Types and/or Locations of BMPs
- b. Material Storage and Spill Response
- c. Fueling Plans
- d. Locations for Stockpiles, Concrete Washout, and Sanitation Facilities and
- e. Project Phasing
- 3. It is determined that the SWPPP is not achieving objectives of minimizing pollutants in stormwater discharges associated with construction activity, or
- 4. The SWPPP is not consistent with the terms and conditions of the permit.

The Contractor may implement SWPPP amendments immediately and is not required to wait for Engineer review of the submittal. The responsibility for completeness of SWPPP amendments and compliance with the Permit lies with the Contractor. Review, comment, or lack of comment by the Engineer on a SWPPP amendment shall not absolve the responsibilities of the Contractor in any way.

If a change order is issued for a design change the SWPPP amendment will be prepared by the Engineer and included in the change order.

In addition to SWPPP amendments, the Contractor shall submit to the Engineer Weekly Erosion and Sediment Control Schedule meeting the requirements of MnDOT 1717.

The Contractor shall keep copies of all SWPPP amendments, Weekly Erosion and Sediment Control Schedules, inspection logs, and maintenance logs with the field copy of the SWPPP. A PDF copy of these documents will be provided along with a copy of the final Field Copy of the SWPPP to the Engineer along with the signed Notice of Termination when final stabilization is complete.

EROSION PREVENTION PRACTICES

Stormwater conveyance channels shall be routed around unstabilized areas. Erosion controls and velocity dissipation devices shall be used at outlets within and along the length of any constructed conveyance channel.

The normal wetted perimeter of all ditches or swales, including storm water management pond slopes, that drain waters from the site must be stabilized within 200' of any property edge or discharge point, including storm sewer inlets, within 24 hours of connection.

Temporary or permanent ditches or swales used as sediment containment during construction do not need to be stabilized during temporary period of use and shall be stabilized within 24 hours after no longer used as sediment containment.

Mulch, hydromulch, tackifier, or similar practice shall not be used in any portion of the wetted perimeter of a temporary or permanent drainage ditch or swale section with a continuous slope of greater than 2 percent.

Energy dissipation shall be installed at all temporary or permanent pipe outlets within 24 hours of connection to a surface water or permanent stormwater treatment system.

The Contractor shall phase construction and use construction methods to the extent practical to minimize exposed soils. The project phasing shall be documented in the Weekly Erosion and Sediment Control Schedule.

SEDIMENT CONTROL PRACTICES

Down gradient BMPs including perimeter BMPs must be in place before up gradient land- disturbing activities begin and shall remain in place until final stabilization.

All BMPs that have been adjusted or removed to accommodate short-term activities shall be re-installed or replaced the earlier of the end of the work day or before the next precipitation event even if the activity is not complete.

Inlet BMPs may be removed for specific safety concerns. The BMPs shall be replaced as soon as the safety concern is resolved. The removal shall be documented in the SWPPP as a SWPPP amendment.

Temporary stockpiles must have sediment control BMPs. The Contractor shall prepare and submit to the Engineer a SWPPP amendment showing the location of temporary stockpiles and the BMPs for each stockpile. The SWPPP amendment must meet the minimum requirements of Section 9 of the Permit.

Soil compaction shall be minimized and topsoil shall be preserved, unless infeasible or if construction activities dictate soil compaction or topsoil stripping.

The use of polymers, flocculants, or other sedimentation treatment chemicals are not proposed as part of this SWPPP as designed by the Engineer. If methods or phasing of construction require the use of any of these chemicals, the Contractor shall prepare and submit to the Engineer a SWPPP amendment that meets the minimum requirements of Section 9 of the Permit.

TEMPORARY SEDIMENTATION BASINS

A temporary sedimentation basin has not been included in this SWPPP as designed by the Engineer. If a basin is later determined to be desirable or necessary the Contractor shall prepare and submit to the Engineer a SWPPP amendment. Temporary sedimentation basins shall meet or exceed the minimum requirements of Section 14 of the Permit and shall include a basin draining plan meeting or exceeding the minimum requirements of Section 10 of the Permit. Where the site discharges to Special and/or Impaired Waters the SWPPP amendment shall also meet or exceed the minimum requirements of Section 23 of the permit.

DEWATERING

A dewatering plan has not been included in this SWPPP as designed by the Engineer. If dewatering is required for this project, the Contractor shall prepare and submit to the Engineer a SWPPP amendment. All dewatering shall meet or exceed the minimum requirements of Section 10 of the Permit.

POLLUTION PREVENTION

Products and materials that have the potential to leach pollutants that are stored on the site must be stored in a manner designed to minimize contact with stormwater. Materials that are not a source of potential contamination to stormwater or that are designed for exposure to stormwater are not required to be covered.

Hazardous materials including but not limited to pesticides, fertilizer, petroleum products, curing compounds and toxic waste must be properly stored and protected from stormwater exposure as recommended by the manufacturer in an access restricted

Solid waste must be stored, collected and disposed of in compliance with Minnesota Administrative Rules Chapter 7035.

Portable toilets must be positioned so that they are secure and will not be tipped or knocked over. Sanitary waste must be disposed of properly in accordance with Minn. R. CH 7041.

Exterior vehicle or equipment washing on the project site shall be limited to a defined area of the site. No engine degreasing is allowed on site. A sign must be installed adjacent to each washout facility that requires site personnel to utilize the proper facilities for disposal of concrete and other washout wastes.

The Contractor shall prepare and submit a SWPPP amendment detailing the location and BMPs proposed for storage of materials, solid waste, portable toilets, and exterior vehicle or equipment washing on the site. The SWPPP amendment shall include a spill prevention and response plan that is appropriate for the materials proposed to be on the site. The SWPPP amendment shall meet or exceed the minimum requirements of Section 12 of the Permit.

INSPECTION & MAINTENANCE

A trained person shall routinely inspect the entire construction site at the time interval indicated on this sheet of the SWPPP during active construction and within 24-hours after a rainfall event greater than 0.5 inches in 24 hours. Following an inspection that occurs within 24-hours after a rainfall event, the next inspection must be conducted at the time interval indicated in the Receiving Waters Table found on the SITE PLAN AND INFORMATION SHEET of the SWPPP.

All inspections and maintenance conducted during construction must be recorded on the day it is completed and must be retained with the SWPPP. Inspection report forms are available in the Project Specifications. Inspection report forms other than those provided shall be approved by the engineer.

The Contractor may request a change in inspection schedule for the following conditions:

- a. Inspections of areas with permanent cover to be reduced to once per month,
- b. Inspections of areas that have permanent cover and have had no construction activity for 12 months to be suspended until construction resumes,
- c. Inspections of areas where construction is suspended due to frozen ground conditions, inspections to be suspended until the earlier of within 24 hours of runoff occurring, or upon resuming construction.

No change in inspection schedule shall occur until authorized by the Engineer.

Inspections must include:

- 1. All erosion prevention and sediment control BMPs and Pollution Prevention Management Measures to ensure integrity and effectiveness
- 2. Surface waters, including drainage ditches and conveyance systems for evidence of erosion and sediment deposition.
- 3. Construction site vehicle exit locations, streets and curb and gutter systems within and adjacent to the project for sedimentation from erosion or tracked sediment from vehicles.
- 4. Infiltration areas to ensure that no sediment from ongoing construction activity is reaching the infiltration area and that equipment is not being driven across the infiltration area.

All non-functioning BMPs and those BMPs where sediment reaches one-half (1/2) of the depth of the BMP, or in the case of sediment basins one-half (1/2) of the storage volume, must be repaired, replaced, or supplemented by the end of the next business day after discovery, or as soon as field conditions allow.

Permittees must repair, replace or supplement all nonfunctional BMPs with functional BMPs by the end of the next business day after discovery, or as soon as field conditions allow.

Any sediment that escapes the site must be removed and the area stabilized within 7 calendar days of discovery unless precluded by legal, regulatory, or physical access in which case the work shall be completed within 7 calendar days of authorization. Paved surfaces such as streets shall have any escaped or tracked sediment removed by the end of the day that it is discovered. Sediment release, other than paved surfaces that can be cleaned up with street sweeping shall be reported immediately upon discovery to the Engineer.

PUBLIC WATER RESTRICTIONS:

For public waters that have been promulgated "work in water restrictions" during fish spawning time frames, all exposed soil areas that are within 200 feet of the water's edge, and drain to these waters must complete stabilization within 24-hours during the time period. MN DNR permits are not valid for work in waters that are designated as infested waters unless accompanied by an Infested Waters Permit or written notification has been obtained from MN DNR stating that such permit is not required. There is no exception for pre-existing permits. If a MN DNR Permit has been issued for the project and the water is later designated as infested, the Contractor shall halt all work covered by the MN DNR Permit until an Infested Waters Permit is obtained or that written notification is obtained stating that such permit is not required.

FINAL STABILIZATION

Final Stabilization is not complete until all the following requirements have been met:

- 1. Substantial Completion has been reached and no ground disturbing activities are anticipated
- 2. Permanent cover has been installed with an established minimum uniform perennial vegetation density of 70 percent of its expected final growth. Vegetation is not required in areas where no vegetation is proposed by this project such as impervious surfaces or the base of a sand filter.

- 3. Accumulated sediment has been removed from all permanent stormwater treatment systems as necessary to ensure the system is operating as designed.
- 4. All sediment has been removed from conveyance systems
- 5. All temporary synthetic erosion prevention and sediment control BMPs have been removed. BMPs designated on the SWPPP to remain to decompose on-site may remain.
- 6. For residential construction only, permit coverage terminates on individual lots if the structures are finished and temporary erosion prevention and downgradient perimeter control is complete, the residence sells to the homeowner, and the permittee distributes the MPCA's "Homeowner Fact Sheet" to the homeowner.
- 7. For agricultural land only (e.g., pipelines across cropland), the disturbed land must be returned to its preconstruction agricultural use prior to submitting the NOT.

SITE STABILIZATION COMPLETION:

| Stabilization of exposed soils shall begin immediately and shall be | |
|---|----------|
| completed after the construction activity has temporarily or | 24 hours |
| permanently ceased no later than: | |

SITE INSPECTION INTERVAL

| A trained person shall routinely inspect the entire construction site during active construction at an interval of no more than: | 7 calendar days |
|--|-----------------|

SPECIAL ENVIRONMENTAL CONSIDERATIONS AND PERMITS:

| 1) | Was an environmental review required for this project or any part of a common plan of development or sale that includes all or any portion of this project? | NO |
|----|---|----|
| 2) | Does any portion of the site have the potential to affect threatened or endangered species or their critical habitat? | NO |
| 3) | Does any portion of this site discharge to a Calcareous fen. | NO |
| 4) | Will any portion of the site potentially affect properties listed on the National Register of Historic Places or a known or discovered archeological site? | NO |
| 5) | Have any Karst features have been identified in the project vicinity? | NO |
| 6) | Is compliance with temporary or permanent stormwater management design requirements infeasible for this project? | NO |
| 7) | Has the MN DNR promulgated "work in water restrictions" for any Public Water this site disharges to during fish spawning? | NO |
| | | |

| TYPE OF PERMIT | PERMITTING AGENCY | PERMIT STATUS AND CONDITIONS |
|-------------------------------|-------------------|------------------------------|
| Construction Stormwater NPDES | MPCA | In Progress |
| | | |
| | | |
| | | |


SWPPP DESIGNER TRAINING DOCUMENTATION:

University of Minnesota

Paul Strong

Design Construction of SWPPP (May 31 2026)

PRELIMINARY DRAFT - FOR AGENCY REVIEW ONLY







| DESIGNED | RWK | NO. | ISSUED FOR | DATE | NATIONAL SPORTS CENTER, MINNESOTA | SHEET |
|----------|------------------|-----|------------|------|-----------------------------------|-------|
| DRAWN | RWK | | | | MASC - COB FIELDS | C2 12 |
| CHECKED | JRP | | | | SWPPP - NARRATIVE | C3.13 |
| OV1. | л. NO. 131841 | | | | | |

NATIONAL SPORTS CENTER



NSC ENTRY PLAZA & FIELDS 50 & 51

BLAINE, MN

1700 105TH AVE, BLAINE, MN, 55449



DRAWING INDEX

TITLE SHEET

SITE DETAILS

NATIONAL SPORTS CENTER

EXISTING CONDITIONS AND REMOVALS PLAN

SITE LAYOUT AND FINISHING PLAN

GRADING AND UTILITY PLAN EROSION CONTROL PLAN

SWPPP - SOILS MAP

Treek Trail Johnsville 125th Avenue Northeast SPORTS CENTER 109th Avenue Northeast Lexington

GENERAL NOTES

THE CONTRACTOR WILL BE DECRONCIBLE FOR AND CHALL DAY FOR ALL CONSTRUCTION STAVING ALL CONSTRUCTION STAVING

2. THE CONTRACTOR WILL BE RESPONSIBLE FOR AND SHALL PAY FOR ALL CONSTRUCTION STAKING / LAYOUT.

. OBTAIN AND PAY FOR ALL RELATED CONSTRUCTION PERMITS, INCLUDING THE NPDES PERMIT FROM THE MPCA. SUBMIT A COPY OF ALL PERMITS TO THE CITY AND WATERSHED.

4 CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TRAFFIC CONTROL SIGNAGE (CONSTRUCTION ZONES) NECESSARY TO CONSTRUCT PROPOSED IMPROVEMENTS.

5. INSTALL CONTROL FENCING AND BARRICADING AS NECESSARY TO PROTECT THE PUBLIC

6. INSPECT SITE TO DETERMINE EXTENT OF WORK AND NATURE OF MATERIALS TO BE HANDLE

ALL CONSTRUCTION SHALL COMPLY WITH APPLICABLE STATE AND LOCAL ORDINANCES

7. CHECK ALL PLAN AND DETAIL DIMENSIONS AND VERIFY SAME BEFORE FIELD LAYOU

. REFER TO THE STORM WATER POLLUTION PREVENTION PLAN (SWPPP) NARRATIVE, SHEET C3.12, FOR EROSION CONTROL REQUIREMENTS. SECTION 31 00 00 SHALL BE RESPONSIBLE FOR FULL IMPLEMENTATION OF THE SWI

9. MAINTAIN ADJACENT PROPERTY AND PUBLIC STREETS CLEAN FROM CONSTRUCTION CAUSED DIRT AND DEBRIS ON A DAILY BASIS. PROTECT DRAINAGE SYSTEMS FROM SEDIMENTATION AS A RESULT OF CONSTRUCTION RELATED DIRT ANI DEBRIS.

10. MAINTAIN DUST CONTROL DURING GRADING OPERATIONS

11. ALL EROSION CONTROL METHODS SHALL COMPLY WITH MPCA AND LOCAL REGULATIONS.

12. MINIMIZE DISTURBANCE TO SITE AND PROTECT EXISTING SITE FEATURES (INCLUDING TURF AND VEGETATION) WHICH ARE TO REMAIN

13. PROPOSED CONTOURS AND SPOT ELEVATIONS ARE SHOWN TO FINISH GRADE UNLESS OTHERWISE NOTED.

14. PROPOSED ELEVATIONS SHOWN TYPICALLY AS 99.1 OR 99 SHALL BE UNDERSTOOD TO MEAN 899.1 OR 899.

15. SPOT ELEVATIONS SHOWN IN PARKING LOTS, DRIVES AND ROADS INDICATE GUTTER GRADES, UNLESS NOTED OTHERWISE

16. THE CONTRACTOR WILL BE SOLELY RESPONSIBLE FOR DETERMINING QUANTITIES OF CUT, FILL AND WASTE MATERIALS TO BE HANDLED, AND FOR AMOUNT OF GRADING TO BE DONE IN ORDER TO COMPLETELY PERFORM ALL WORK INDICATED ON THE DRAWINGS. IMPORT SUITABLE MATERIAL AND EXPORT UNSUITABLE / EXCESS / WASTE MATERIAL, AS REQUIRED, AT NO ADDITIONAL COST TO THE OWNER.

17. NO FINISHED SLOPES SHALL EXCEED 3' HORIZONTAL TO 1' VERTICAL (3:1), UNLESS OTHERWISE NOTED.

18. ALL DISTURBED AREAS WHICH ARE NOT DESIGNATED TO BE PAVED OR RECEIVE TURF, SHALL RECEIVE AT LEAST 6" OF TOPSOIL AND SHALL BE SEEDED. REFER TO FINISHING PLANS FOR SEED LOCATIONS. ALL AREAS NOT DESIGNATED FOR SOD OR A SPECIFIC SEED MIX, WHICH ARE DISTURBED BY CONSTRUCTION, SHALL BE SEEDED WITH SEED MIX #1.

19. FAILURE OF TURF DEVELOPMENT: IN THE EVENT THE CONTRACTOR FAILS TO PROVIDE AN ACCEPTABLE TURF, RE-SEED ALL APPLICABLE AREAS, AT NO ADDITIONAL COST TO THE OWNER, TO THE SATISFACTION OF THE ENGINEER OR LANDSCAPE ARCHITECT.

20. ALL STORM SEWER PIPE SHALL BE PVC PIPE (ASTM D3034, SDR 35) INSTALLED IN ACCORDANCE WITH ASTM D2321, UNLESS OTHERWISE NOTED.

21. ALL STORM SEWER PIPE CROSSING WATERMAIN, OUTSIDE OF THE PUBLIC RIGHT-OF-WAY, SHALL BE ASTM D2665, SCHEDULE 40 PVC WITH SOLVENT WELD JOINTS.

22. FLEXIBLE JOINTS AT STORM SEWER PIPE CONNECTIONS TO STRUCTURES:

a. IN ACCORDANCE WITH MINNESOTA PLUMBING CODE, PROVIDE FLEXIBLE JOINTS AT ALL PIPE CONNECTIONS TO ALL STORM SEWER STRUCTURES.

i. FERNCO, "CONCRETE MANHOLE ADAPTORS" OR "LARGE-DIAMETER WATERSTOPS"ii. PRESS-SEAL, WATERSTOP GROUTING RINGS"

iii. OR APPROVED EQUAL.

26. LOCATE ALL EXISTING UTILITIES. VERIFY LOCATION, SIZE AND INVERT ELEVATION OF ALL EXISTING UTILITIES. BEFORE BEGINNING CONSTRUCTION.


27. STAKE LIMITS OF WALKS AND CURBING PRIOR TO INSTALLATION OF GATE VALVES, CATCH BASINS, AND MANHOLES. ADJUST GATE VALVE AND MANHOLE LOCATIONS TO AVOID PLACEMENT OF THESE STRUCTURES IN WALKS AND CURB AND GUTTER. STAKE CURB AND GUTTER ALIGNMENTS TO ALLOW CURB INLET TYPE CATCH BASINS TO PROPERLY ALIGN WITH CURB AND GUTTER.

28. ALL DISTURBED AREAS INCLUDING SOIL STOCKPILE SHALL BE STABILIZED WITH VEGETATION WITHIN SEVEN (7) DAYS OF ROUGH GRADING OR 24 HOURS OF INACTIVITY.

DDELIMINARY DRAFT - FOR REVIEW ONLY



Nature Center











0V1.132864


PRELIMINARY DRAFT - FOR REVIEW ONLY












BIORETENTION POND 3 NOTES:

NOT TO SCALE


1. INSTALL APPROPRIATE TEMPORARY EROSION CONTROL DEVICES TO PREVENT SEDIMENT FROM LEAVING OR ENTERING THE FILTRATION AREA DURING CONSTRUCTION.

- 2. PERFORM WEEKLY INSPECTIONS, INCLUDING AFTER EACH RAINFALL EVENT.
- 3. ROUGH GRADE THE SITE.
- 4. COMPLETE, STABILIZE, AND VEGETATE ALL OTHER SITE IMPROVEMENTS.
- COMPLETE GRADING AND STABILIZATION OF FILTRATION AREA ONLY AFTER THE CONTRIBUTING DRAINAGE AREA'S VEGETATION HAS REACHED 70% GROWTH OF PERMANENT PERENNIAL VEGETATION, OR PLACEMENT OF SOIL STABILIZATION AND APPROVED BY ENGINEER, AND BEFORE CONSTRUCTION AND INSTALLING VEGETATION IN FILTRATION AREAS.
- REMOVE TEMPORARY EROSION CONTROL DEVICES AFTER THE CONTRIBUTING DRAINAGE AREA AFTER VEGETATION HAS REACHED 70% GROWTH OF PERMANENT PERENNIAL VEGETATION.
- 7. IN THE EVENT THAT SEDIMENT IS INTRODUCED INTO THE BMP DURING OR IMMEDIATELY FOLLOWING EXCAVATION, THIS MATERIAL SHALL BE REMOVED FROM THE PRACTICE PRIOR TO CONTINUING CONSTRUCTION.
- 8. SUBGRADE SHALL BE PREPARED SO THAT THE AREA BENEATH THE BASINS AND EMBANKMENTS IS STRIPPED OF ALL VEGETATION, TOPSOIL, AND ORGANIC MATTER.
- 9. INSTALLATION WITH DRY SOIL CONDITIONS IS CRITICAL TO PREVENT SMEARING AND COMPACTION. SCHEDULE WORK FOR PERIODS OF DRY WEATHER. DO NOT WORK IF SOIL CONDITIONS ARE WET. EXCAVATION, SOIL PLACEMENT AND RAPID STABILIZATION OF PERIMETER SLOPES WITH METHODS SHOWN ON PLAN MUST BE COMPLETED BEFORE THE NEXT PRECIPITATION EVENT.
- 10. REMOVAL OF ACCUMULATED SEDIMENT AND DEBRIS SHALL BE DONE BY HAND OR, IF SELF-PROPELLED EQUIPMENT IS REQUIRED, FROM OUTSIDE THE PERIMETER OF THE FILTRATION AREAS.




The valve shall be installed in the full open position. The SWCD will observe the temporary pool following a rain event and will adjust

the valve as needed to achieve the optimum drain down time of approximately 12 hours. Further valve adjustment should not be



needed unless plants show signs of stress.




PEDESTRIAN CURB RAMP

C2.12 NOT TO SCALE

I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION, OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED 05/31/2024






SHEET

0V1.132864

STORMWATER POLLUTION PREVENTION PLAN (SWPPP)

NATIONAL SPORTS CENTER - 2024

CITY OF BLAINE ANOKA COUNTY, MINNESOTA



RESPONSIBLE PARTIES:

The Contractor and Owner will be joint applicants under the MPCA's General Stormwater Permit for Construction Activity as required by the National Pollutant Discharge Elimination System (NPDES) Phase II program.

The Contractor shall provide one or more trained Construction SWPPP Manager(s) knowledgeable and experienced in the application of erosion prevention and sediment control BMPs that will oversee the implementation of the SWPPP, and the installation, inspection and maintenance of the erosion prevention and sediment control BMPs.

A Construction SWPPP Manager must be available for an on-site inspection within 72 hours upon request by the MPCA.

| | COMPANY | CONTACT PERSON | PHONE |
|--------------------------------------|------------------------|----------------|--------------|
| OWNER: | National Sports Center | Neil Ladd | 763-785-5600 |
| SWPPP DESIGNER: | Bolton & Menk, Inc. | Paul Strong | 651-247-8789 |
| CONTRACTOR: | Dimke Excavation | Tom Dimke | 612-225-7100 |
| CONSTRUCTION SWPPP MANAGER: | TBD | TBD | TBD |
| PARTY RESPONSIBLE FOR LONG TERM O&M: | National Sports Center | Neil Ladd | 763-785-5600 |

The SWPPP Designer, Construction SWPPP Manager, and BMP Installer must have appropriate training. Documentation showing training commensurate with the job duties and responsibilities is required to be included in the SWPPP prior to any work beginning on the site. Training documentation for the SWPPP Designer is included on the Narrative sheet. The Contractor shall attach training documentation to this SWPPP for the Construction SWPPP Manager and BMP Installer prior to the start of construction. This information shall be kept up to date until the project NOT is filed.

ADDITIONAL COMPENSATION

Payment for all work associated with Erosion and Sediment Control shall be as described in the Project Manual. Unless otherwise authorized by the Owner no additional payment shall be made for any work required to administer and maintain the site erosion and sediment control in compliance with the Minnesota Pollution Control Agency (MPCA) - General Stormwater Permit for Construction Activity (MN R100001) including but not limited to inspection, maintenance, and removal of BMPs or addition of BMPs to accommodate Contractor phasing.

DOCUMENT RETENTION

Permittees must make the SWPPP, including all inspection reports, maintenance records, training records and other information required by this permit, available to federal, state, and local officials within three (3) days upon request for the duration of the permit and for three (3) years following the NOT.

GENERAL STORMWATER DISCHARGE REQUIREMENTS

All requirements listed in Section 5.1 of the Permit for the design of the permanent stormwater management system and discharge have been included in the preparation of this SWPPP. These include but are not limited to:

- 1. The expected amount, frequency, intensity, and duration of precipitation.
- 2. The nature of stormwater runoff and run-on at the site
- 3. Peak flow rates and stormwater volumes to minimize erosion at outlets and downstream channel and stream bank erosion.
- 4. The range of soil particle sizes expected to be present on the site.

Permanent stormwater treatment systems for this project have been designed in accordance with the guidance in the MN Stormwater Manual in place at the time of bidding. Copies of the design information and calculations are part of this SWPPP and will be provided in digital format upon written request to the Engineer.

PROJECT AREAS:

| Total Project Size (disturbed area) = | 8.9700 | ACRES |
|--|--------|-------|
| Existing area of impervious surface = | 0.1830 | ACRES |
| Post construction area of impervious surface = | 0.6206 | ACRES |
| Total new impervious surface area created = | 0.4376 | ACRES |
| | | |

Planned Construction Start Date: Estimated Construction Completion Date:

7/29/2024 12/31/2024

PERMANENT STORMWATER MANAGEMENT SYSTEM:

Type of storm water management used if more than 1 acre of new impervious surface is created:

| | | Wet Sedimentation Basin | | |
|--|----|--|--|--|
| | X* | Infiltration/Filtration | | |
| | | Regional Pond | | |
| | | Permanent Stormwater Management Not Required | | |
| *- Less than 1 acre of impervious reconstruction | | | | |

PROJECT LOCATION:

| COUNTY | TOWNSHIP | RANGE | SECTION | LATITUDE | LONGITUDE |
|--------|----------|-------|---------|-----------|------------|
| ANOKA | T31N | R23W | 20 | 45.16014° | -93.22381° |
| | | | | | |

| BMP SUMMARY | QUANTITY | UNIT |
|-------------------------|----------|------|
| Construction Entrance | 2 | EACH |
| Silt Fence | 2300 | LF |
| Inlet Protection Device | 10 | EACH |
| Seed Mix 1 | TBD | ACRE |
| Seed Mix 2 | TBD | ACRE |
| Biolog | 1550 | LF |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

DESCRIPTION OF CONSTRUCTION ACTIVITIES AND STORMWATER MANAGEMENT:


Construction activities include: Site grading, field construction, parking lot improvements, temporary erosion and sediment control, and permanent stabilization.

Pavement improvements to the Super Rink parking area is proposed to improve traffic flow and safety. Activities will include realignment of drive lanes, parking areas, and the expansion of the existing wet sedimentation basin on site; however, it will not include full depth pavement reconstruction. While no impervious reconstruction will occur, the wet sedimentation basin will be expanded for aesthetic purposes and additional gravel pathways instaleld, resulting in a net increase of approximately 0.5 acres of impervious.

Additionally, Fields 50 and 51, directly north of the Super Rink, will be raised to improve drainage and reduce the flood frequency of those fields and to provide grass berms for spectator seating. Stormwater from the parking lot currently flows to the existing wet sedimentation, which outlets to county ditch 41. Stormwater from the field sheet flows into county ditch 41.

After construction is complete, stormwater will flow the same as pre-construction.

Stormwater BMPs proposed; wet sedimentation.



RECEIVING WATERS:

Receiving waters, including surface water, wetlands, Public Waters, and stormwater ponds, within 1-mile of the project boundary are identified on the USGS 7.5 min guad map above. Receiving waters that are impaired, the impairment, and WLA are listed as follows. All specific BMPs relative to construction activities listed in the permit for special, prohibited, restricted, or impaired have been incorporated into this plan. All specific BMPs listed in approved TMDLs and those BMPs listed for construction related waste load allocations have also been incorporated.

| NAME OF WATER BODY | TYPE (ditch, pond, wetland, lake, etc.) | Special, Prohibited, Restricted Water ¹ | Flows to Impaired Water Within 1-Mile ² | USEPA Approved Construction Related TMDL ³ |
|--------------------|---|---|---|---|
| County Ditch 41 | Ditch | No | No | - |
| | | | | |


¹ Special, prohibited, and restricted waters are listed in Section 23 of the MN Construction Stormwater General Permit (MNR100001). ² Identified as impaired under section 303 (d) of the federal Clean Water Act for phosphorus, turbidity, TSS, dissolved oxygen, and/or aquatic biota. ³ Construction Related TMDLs include those related to: phosphorus, turbidity, TSS, dissolved oxygen, and/or aquatic biota.

IMPLEMENTATION SCHEDULE AND PHASING: The Contractor is required to provide an updated schedule and site management plan meeting the minimum requirements of Section 1717 of the Minnesota Standard Specifications for Construction.


- 1) Submit SWPPP Updates to Engineer. Submittal shall include any requested changes to the SWPPP, including but not limited to: Trained Personnel, Locations for Stockpiles, Concrete Washout, Sanitation Facilities, Types and Locations of Erosion & Sediment Control. Failure to submit updates shall be considered acceptance of the SWPPP as designed with no changes.
- 2) Install perimeter sediment control, inlet protection, and construction exit. 3) Complete removals
- 4) Complete mass grading
- 5) Complete parking area improvements
- 6) Add additional temporary BMPs as necessary during construction based on inspection reports.
- Ensure final stabilization measures are complete.
- 8) Provide digital copy of all Field SWPPP Documentation including Inspection Reports and SWPPP Revisions to the Owner.
- 9) Submit Notice of Termination (NOT) to MPCA. NOTE: The NOT must be submitted to MPCA before Final Stabilization is considered complete.

PRELIMINARY DRAFT - FOR AGENCY REVIEW ONLY









| DESIGNED | RWK | NO. | ISSUED FOR | DATE | NATIONAL COORTS CENTED MAININESCOTA | CHEET | | |
|--------------|--------|----------|------------|------|-------------------------------------|-----------------|-----------------------------------|-------|
| | LAAL | | IVVVIX | | | | NATIONAL SPORTS CENTER, MINNESOTA | SHEET |
| DRAWN | RWK | | | | 1100 51/51/ 51 4 54 0 515/ 50 50 54 | - | | |
| | ITVVIX | | | | NSC ENTRY PLAZA & FIELDS 50 & 51 | C2 11 | | |
| CHECKED | JRP | | | | | 1 C 3.11 | | |
| | | <u> </u> | | | SWPPP - PROJECT DESCRIPTION | | | |
| CLIENT PROJ. | | | | | 1 SWITT TROJECT DESCRIPTION | | | |
| I 0V1.1 | 31841 | | | | | | | |

SWPPP AMENDMENTS AND SUBMITTALS

Contractor must prepare and submit to the Engineer a SWPPP amendment as necessary to include additional Best Management Practices (BMPs) to correct problems identified or address the following situations.

- 1. Contact information and training documentation for Construction SWPPP Manager and BMP Installer,
- 2. There is a change in construction method of phasing, operation, maintenance, weather or seasonal conditions not anticipated during the design of the SWPPP including but not limited to:
- a. Types and/or Locations of BMPs
- b. Material Storage and Spill Response
- c. Fueling Plans
- d. Locations for Stockpiles, Concrete Washout, and Sanitation Facilities and
- e. Project Phasing
- 3. It is determined that the SWPPP is not achieving objectives of minimizing pollutants in stormwater discharges associated with construction activity, or
- 4. The SWPPP is not consistent with the terms and conditions of the permit.

The Contractor may implement SWPPP amendments immediately and is not required to wait for Engineer review of the submittal. The responsibility for completeness of SWPPP amendments and compliance with the Permit lies with the Contractor. Review, comment, or lack of comment by the Engineer on a SWPPP amendment shall not absolve the responsibilities of the Contractor in any way.

If a change order is issued for a design change the SWPPP amendment will be prepared by the Engineer and included in the change order.

In addition to SWPPP amendments, the Contractor shall submit to the Engineer Weekly Erosion and Sediment Control Schedule meeting the requirements of MnDOT 1717.

The Contractor shall keep copies of all SWPPP amendments, Weekly Erosion and Sediment Control Schedules, inspection logs, and maintenance logs with the field copy of the SWPPP. A PDF copy of these documents will be provided along with a copy of the final Field Copy of the SWPPP to the Engineer along with the signed Notice of Termination when final stabilization is complete.

EROSION PREVENTION PRACTICES

Stormwater conveyance channels shall be routed around unstabilized areas. Erosion controls and velocity dissipation devices shall be used at outlets within and along the length of any constructed conveyance channel.

The normal wetted perimeter of all ditches or swales, including storm water management pond slopes, that drain waters from the site must be stabilized within 200' of any property edge or discharge point, including storm sewer inlets, within 24 hours of connection.

Temporary or permanent ditches or swales used as sediment containment during construction do not need to be stabilized during temporary period of use and shall be stabilized within 24 hours after no longer used as sediment containment.

Mulch, hydromulch, tackifier, or similar practice shall not be used in any portion of the wetted perimeter of a temporary or permanent drainage ditch or swale section with a continuous slope of greater than 2 percent.

Energy dissipation shall be installed at all temporary or permanent pipe outlets within 24 hours of connection to a surface water or permanent stormwater treatment system.

The Contractor shall phase construction and use construction methods to the extent practical to minimize exposed soils. The project phasing shall be documented in the Weekly Erosion and Sediment Control Schedule.

SEDIMENT CONTROL PRACTICES

Down gradient BMPs including perimeter BMPs must be in place before up gradient land- disturbing activities begin and shall remain in place until final stabilization.

All BMPs that have been adjusted or removed to accommodate short-term activities shall be re-installed or replaced the earlier of the end of the work day or before the next precipitation event even if the activity is not complete.

Inlet BMPs may be removed for specific safety concerns. The BMPs shall be replaced as soon as the safety concern is resolved. The removal shall be documented in the SWPPP as a SWPPP amendment.

Temporary stockpiles must have sediment control BMPs. The Contractor shall prepare and submit to the Engineer a SWPPP amendment showing the location of temporary stockpiles and the BMPs for each stockpile. The SWPPP amendment must meet the minimum requirements of Section 9 of the Permit.

Soil compaction shall be minimized and topsoil shall be preserved, unless infeasible or if construction activities dictate soil compaction or topsoil stripping.

The use of polymers, flocculants, or other sedimentation treatment chemicals are not proposed as part of this SWPPP as designed by the Engineer. If methods or phasing of construction require the use of any of these chemicals, the Contractor shall prepare and submit to the Engineer a SWPPP amendment that meets the minimum requirements of Section 9 of the Permit.

TEMPORARY SEDIMENTATION BASINS

A temporary sedimentation basin has not been included in this SWPPP as designed by the Engineer. If a basin is later determined to be desirable or necessary the Contractor shall prepare and submit to the Engineer a SWPPP amendment. Temporary sedimentation basins shall meet or exceed the minimum requirements of Section 14 of the Permit and shall include a basin draining plan meeting or exceeding the minimum requirements of Section 10 of the Permit. Where the site discharges to Special and/or Impaired Waters the SWPPP amendment shall also meet or exceed the minimum requirements of Section 23 of the permit.

DEWATERING

A dewatering plan has not been included in this SWPPP as designed by the Engineer. If dewatering is required for this project, the Contractor shall prepare and submit to the Engineer a SWPPP amendment. All dewatering shall meet or exceed the minimum requirements of Section 10 of the Permit.

POLLUTION PREVENTION

Products and materials that have the potential to leach pollutants that are stored on the site must be stored in a manner designed to minimize contact with stormwater. Materials that are not a source of potential contamination to stormwater or that are designed for exposure to stormwater are not required to be covered.

Hazardous materials including but not limited to pesticides, fertilizer, petroleum products, curing compounds and toxic waste must be properly stored and protected from stormwater exposure as recommended by the manufacturer in an access restricted area.

Solid waste must be stored, collected and disposed of in compliance with Minnesota Administrative Rules Chapter 7035.

Portable toilets must be positioned so that they are secure and will not be tipped or knocked over. Sanitary waste must be disposed of properly in accordance with Minn. R. CH 7041.

Exterior vehicle or equipment washing on the project site shall be limited to a defined area of the site. No engine degreasing is allowed on site. A sign must be installed adjacent to each washout facility that requires site personnel to utilize the proper facilities for disposal of concrete and other washout wastes.

The Contractor shall prepare and submit a SWPPP amendment detailing the location and BMPs proposed for storage of materials, solid waste, portable toilets, and exterior vehicle or equipment washing on the site. The SWPPP amendment shall include a spill prevention and response plan that is appropriate for the materials proposed to be on the site. The SWPPP amendment shall meet or exceed the minimum requirements of Section 12 of the Permit.

INSPECTION & MAINTENANCE

A trained person shall routinely inspect the entire construction site at the time interval indicated on this sheet of the SWPPP during active construction and within 24-hours after a rainfall event greater than 0.5 inches in 24 hours. Following an inspection that occurs within 24-hours after a rainfall event, the next inspection must be conducted at the time interval indicated in the Receiving Waters Table found on the SITE PLAN AND INFORMATION SHEET of the SWPPP.

All inspections and maintenance conducted during construction must be recorded on the day it is completed and must be retained with the SWPPP. Inspection report forms are available in the Project Specifications. Inspection report forms other than those provided shall be approved by the engineer.

The Contractor may request a change in inspection schedule for the following conditions:

- a. Inspections of areas with permanent cover to be reduced to once per month,
- b. Inspections of areas that have permanent cover and have had no construction activity for 12 months to be suspended until construction resumes,
- c. Inspections of areas where construction is suspended due to frozen ground conditions, inspections to be suspended until the earlier of within 24 hours of runoff occurring, or upon resuming construction.

No change in inspection schedule shall occur until authorized by the Engineer.

Inspections must include:

- 1. All erosion prevention and sediment control BMPs and Pollution Prevention Management Measures to ensure integrity and effectiveness.
- 2. Surface waters, including drainage ditches and conveyance systems for evidence of erosion and sediment deposition.
- 3. Construction site vehicle exit locations, streets and curb and gutter systems within and adjacent to the project for sedimentation from erosion or tracked sediment from vehicles.
- 4. Infiltration areas to ensure that no sediment from ongoing construction activity is reaching the infiltration area and that equipment is not being driven across the infiltration area.

All non-functioning BMPs and those BMPs where sediment reaches one-half (1/2) of the depth of the BMP, or in the case of sediment basins one-half (1/2) of the storage volume, must be repaired, replaced, or supplemented by the end of the next business day after discovery, or as soon as field conditions allow.

Permittees must repair, replace or supplement all nonfunctional BMPs with functional BMPs by the end of the next business day after discovery, or as soon as field conditions allow.

Any sediment that escapes the site must be removed and the area stabilized within 7 calendar days of discovery unless precluded by legal, regulatory, or physical access in which case the work shall be completed within 7 calendar days of authorization. Paved surfaces such as streets shall have any escaped or tracked sediment removed by the end of the day that it is discovered. Sediment release, other than paved surfaces that can be cleaned up with street sweeping shall be reported immediately upon discovery to the Engineer.

PUBLIC WATER RESTRICTIONS:

For public waters that have been promulgated "work in water restrictions" during fish spawning time frames, all exposed soil areas that are within 200 feet of the water's edge, and drain to these waters must complete stabilization within 24-hours during the time period. MN DNR permits are not valid for work in waters that are designated as infested waters unless accompanied by an Infested Waters Permit or written notification has been obtained from MN DNR stating that such permit is not required. There is no exception for pre-existing permits. If a MN DNR Permit has been issued for the project and the water is later designated as infested, the Contractor shall halt all work covered by the MN DNR Permit until an Infested Waters Permit is obtained or that written notification is obtained stating that such permit is not required.

FINAL STABILIZATION

Final Stabilization is not complete until all the following requirements have been met:

- 1. Substantial Completion has been reached and no ground disturbing activities are anticipated.
- 2. Permanent cover has been installed with an established minimum uniform perennial vegetation density of 70 percent of its expected final growth. Vegetation is not required in areas where no vegetation is proposed by this project such as impervious surfaces or the base of a sand filter.

- 3. Accumulated sediment has been removed from all permanent stormwater treatment systems as necessary to ensure the system is operating as designed.
- 4. All sediment has been removed from conveyance systems
- 5. All temporary synthetic erosion prevention and sediment control BMPs have been removed. BMPs designated on the SWPPP to remain to decompose on-site may remain.
- 6. For residential construction only, permit coverage terminates on individual lots if the structures are finished and temporary erosion prevention and downgradient perimeter control is complete, the residence sells to the homeowner, and the permittee distributes the MPCA's "Homeowner Fact Sheet" to the homeowner.
- 7. For agricultural land only (e.g., pipelines across cropland), the disturbed land must be returned to its preconstruction agricultural use prior to submitting the NOT.

SITE STABILIZATION COMPLETION:

| Stabilization of exposed soils shall begin immediately and shall be | |
|---|----------|
| completed after the construction activity has temporarily or | 24 hours |
| permanently ceased no later than: | |

SITE INSPECTION INTERVAL:

| A trained person shall routinely inspect the entire construction site during active construction at an interval of no more than: | 7 calendar days |
|--|-----------------|

SPECIAL ENVIRONMENTAL CONSIDERATIONS AND PERMITS:

| Was an environmental review required for this project or any part of a common plan of development or sale that includes all or any portion of this project? | NO |
|---|--|
| Does any portion of the site have the potential to affect threatened or endangered species or their critical habitat? | NO |
| Does any portion of this site discharge to a Calcareous fen. | NO |
| Will any portion of the site potentially affect properties listed on the National Register of Historic Places or a known or discovered archeological site? | NO |
| Have any Karst features have been identified in the project vicinity? | NO |
| Is compliance with temporary or permanent stormwater management design requirements infeasible for this project? | NO |
| Has the MN DNR promulgated "work in water restrictions" for any Public Water this site disharges to during fish spawning? | NO |
| | or sale that includes all or any portion of this project? Does any portion of the site have the potential to affect threatened or endangered species or their critical habitat? Does any portion of this site discharge to a Calcareous fen. Will any portion of the site potentially affect properties listed on the National Register of Historic Places or a known or discovered archeological site? Have any Karst features have been identified in the project vicinity? Is compliance with temporary or permanent stormwater management design requirements infeasible for this project? Has the MN DNR promulgated "work in water restrictions" for any Public Water this site disharges to |

| TYPE OF PERMIT | PERMITTING AGENCY | PERMIT STATUS AND CONDITIONS |
|-------------------------------|-------------------|------------------------------|
| Construction Stormwater NPDES | MPCA | In Progress |
| Watershed Permit | CCWD | In Progress |
| | | |
| | | |

SWPPP DESIGNER TRAINING DOCUMENTATION:


University of Minnesota

Paul Strong


Design Construction of SWPPP (May 31 2026)

PRELIMINARY DRAFT - FOR AGENCY REVIEW ONLY

C3.12









Permit Application Review Report Date: 8/7/2024

Board Meeting Date: 8/12/2024

Agenda Item: 15

Applicant/Landowner: National Sports Center Attn: Neil Ladd 1700 105th Ave NE Blaine, MN 55449

Project Name: Turf Field and Campus Improvements

Project PAN: P-24-004

Project Purpose: Conversion of natural turf fields to artificial turf and a 30-foot-wide roadway

Project Location: Numerous locations across National Sports Center Campus, 1700 105th Ave

NE, Blaine

Site Size: size of parcel - 300 acres; size of disturbed area - 34.29 acres; size of regulated

impervious surface - 0.67

Applicable District Rule(s): Rule 2, Rule 3, Rule 4, Rule 6

Recommendation: Approve with 2 Conditions and 4 Stipulations

Description: The National Sports Center is proposing several improvements to the campus including widening of an existing roadway, regrading of multiple soccer fields, roadway and sidewalk reconfiguring, and reconstruction of an existing pond. An interim grading permit was approved (3/11/24) and issued on March 13, 2024, which encompassed the proposed soccer field grading. This approval is for the remainder of the proposed work. The total disturbance is 34.29 acres. The project will create 0.67 acres of regulated impervious. The project area drains to County Ditch 41. The relevant water resource concerns are stormwater management, erosion and sediment control, and floodplain. These correlate to District Rules 3, 4, and 6. See attached Figure 1: Project Location and Figure 2: Site Plan.

Conditions to be Met Before Permit Issuance:

Rule 2.7 – Procedural Requirements

1. Submittal of a performance escrow in the amount of \$6,485.00 for increase in area of disturbance from previously approved application.

Rule 3.0 - Stormwater Management

2. Provide proof of recording of a fully executed Operations and Maintenance Agreement for the perpetual inspection and maintenance of all proposed stormwater management practices after review and approval by the District.

Stipulations: The permit will be issued with the following stipulations as conditions of the permit. By accepting the permit, the applicant agrees to these stipulations:

- 1. The applicant must apply for coverage under the Minnesota Pollution Control Agency's (MPCA's) Construction Stormwater Permit (Permit No: MNR100001)
- 2. If dewatering is required, provide DNR dewatering permit prior to construction. If a DNR permit is not required, provide well-field location, rates, discharge location, schedule and quantities prior to construction.
- 3. Submittal of grading as-builts for the project to confirm adequate floodplain compensatory storage has been provided.
- 4. Submittal of as-builts for the stormwater management practices and associated structures listed in Tables 2 and 3, including volume, critical elevations and proof of installation for hydrodynamic separators.

Exhibits:

| Exhibit Type | Exhibit Author | Signature Date | Received Date |
|--|----------------|----------------|---------------|
| MIDS | Bolton & Menk | | 06/03/2024 |
| Construction Plans | Bolton & Menk | 06/03/2024 | 06/03/2024 |
| HydroCAD Models (Existing&Proposed) | Bolton & Menk | | 07/17/2024 |
| Project Narrative & Stormwater Management Plan | Bolton & Menk | 07/17/2024 | 07/17/2024 |
| Construction Plans | Bolton & Menk | 05/31/2024 | 07/17/2024 |

Findings

Fees and Escrows (Rule 2.7): The applicant has submitted a \$4,800.00 application fee and deposit which corresponds with the nonrefundable application fee (\$10), base fee for a Commercial/Industrial Development project of 300 acres (\$4,500.00), and addition to base fee (\$300.00). The applicant will be required to submit a performance escrow in the amount of \$6,485.00. This corresponds to a base escrow of \$2,000, plus an additional \$500/acre of disturbance (8.97 acres of land disturbance proposed). The applicant has already paid escrow fees of \$14,660.00 for previously approved disturbance of 25.32 acres.

Stormwater Management (Rule 3.0):

Rule 3.0 applies to the proposed project because it includes land disturbing activities creating a cumulative total of 10,000 sf or more of new or fully reconstructed impervious surface.

The Hydrologic Soil Group (HSG) of soils on site are HSG A.

Rate Control: Peak stormwater flow rate at each point of site discharge increases from the predevelopment condition for the several precipitation events as shown in Table 1. The rate increase for the existing NSC pond discharge point results in a static bounce of less than 0.1 feet in the pond, which is entirely contained within the applicant's property. No surrounding structures would be impacted. The rate increase for the Super Rink pond was modeled in XPSWMMM and showed no adverse impacts and no increase in downstream high water levels. The project will not impact Drainage Sensitive Use areas. The rate control standard is considered met.

| Point of | 2-year (cfs) | | 10-year (cfs | 10-year (cfs) | | 100-year (cfs) | |
|------------|--------------|----------|--------------|---------------|----------|----------------|--|
| Discharge | Existing | Proposed | Existing | Proposed | Existing | Proposed | |
| Super Rink | 0.87 | 0.07 | 1.39 | 1.53 | 2.53 | 2.64 | |
| Pond | | | | | | | |
| CD 41 | 0.38 | 0.24 | 0.58 | 0.36 | 1.32 | 1.22 | |

| 2 |
|----|
| .5 |
| |

| Е | xisting NSC | 0 | 0.18 | 0.02 | 0.27 | 0.65 | 1.26 |
|---|-------------|---|------|------|------|------|------|
| P | ond | | | | | | |

Table 1.

Volume Control:

The application proposes redevelopment which does not disturb more than 50% of the site or reconstruct more than 50% of the existing impervious surface, therefore the volume reduction requirement is equal to 1.1 inches over the area of new and fully reconstructed impervious surface. The amount of proposed impervious required to be treated is 29,338 ft².

The applicant is proposing the Stormwater Management Practices (SMPs) described below:

| Drainage Area | Impervious required to be treated (ft²) | Proposed SMP | TP Removal Factor | Required Water Quality Volume (ft ³) | Water Quality Volume Provided (ft ³) |
|---------------------------------------|---|--------------------------|----------------------|---|--|
| Access Rd Basin 1 (1S) | 11,984 | Infiltration basin 1 | 1 | 1,098 | 2,618 |
| Access Rd Basin 2 (2S) | 6,357 | Infiltration Basin 2 | 1 | 582 | 1,623 |
| Access Rd - Existing NSC Pond | 2,253 | NSC Pond | 0.5 | 413 | 413 |
| NSC Entrance Basin 3 (5S) | 4,342 | Biofiltration Basin 3 | 0.65 | 612 | 1,483 |
| NSC Entrance- Super Rink Pnd | 4,402 | Super Rink Pond | 0.5 | 807 | 807 |
| Totals: | 29,338 | | | 3,514 | 6,944 |

Table 2.

The following pretreatment has been provided:

| SMP ID | Pretreatment Device/Method | Percent TSS Removal | |
|-----------------------|----------------------------|---------------------|--|
| Biofiltration Basin 3 | Vegetated Filter Strip | 80 | |
| Infiltration Basin 2 | Vegetated Filter Strip | 80 | |
| Infiltration Basin 1 | Vegetated Filter Strip | 80 | |

Table 3.

Pretreatment is required to be designed such that the device/method provides removal of 80% TSS entering an infiltration or filtration Stormwater Management Practice. The proposed project meets pretreatment requirements as shown in Table 3.

The volume control standard has been met as shown in Table 2.

<u>Water Quality</u>: The total Water Quality Volume has been provided in aggregate.

Stormwater treatment on site must remove at least 80% of the average annual post development TSS per discharge location. The following TSS removal has been provided:

| Discharge Point | TSS Removal Provided |
|-------------------|----------------------|
| Super Rink Pond | 93 |
| CD 41 | 100 |
| Existing NSC Pond | 100 |

Table 4.

The TSS removal standard is met at each discharge point as shown in Table 4.

Discharges to Wetlands: Stormwater from the proposed project is not being discharged into any wetlands, therefore this section does not apply.

Landlocked Basins: The proposed drainage system does not outlet to a landlocked basin, therefore this section does not apply.

Low Floor Freeboard: The proposed project is not considered new development with buildings and habitable structures; therefore, this section does not apply.

Maintenance:

Access: Sufficient maintenance access has been provided on the plans for all stormwater management practices.

Maintenance Agreements: The proposed stormwater management practices will not be maintained as part of standard municipal public work activities. Therefore, a maintenance agreement that meets District standards will be required.

Soils and Erosion Control (Rule 4.0)

Rule 4.0 applies to the proposed project because it is a land disturbing activity that requires a permit under another District rule.

The proposed project drains to Ditch 41. The soils affected by the project include Rifle and Lino and have a soil erodibility factor of 0.15 or greater. Disturbed areas are proposed to be stabilized within 24 hours, as required. The proposed erosion and sediment control plan includes perimeter control, rock construction entrance, inlet protection. The erosion control plan meets District Requirements. See attached Figure 3: Erosion and Sediment Control Plan.

Wetlands (Rule 5.0)

The proposed project does not include activities which result in the filling, draining, excavating, or otherwise altering the hydrology of a wetland. Rule 5.0 does not apply.

Floodplain (Rule 6.0)

Rule 6.0 applies to the proposed project because it includes land disturbing activities within or adjacent to the boundary of the 100-year flood elevation as mapped and modeled by the District.

The regulatory floodplain elevation ranges from 895.5 to 898.4 ft MSL. The application proposes the placement of fill within the floodplain. Compensatory storage is required. The proposed project is providing compensatory storage that exceeds the required 1:1 ratio and is within the relevant reach.

Drainage, Bridges, Culverts, and Utility Crossings (Rule 7.0)

The proposed project does not include land disturbing activities which construct, improve, repair, or alter the hydraulic characteristics of a bridge profile control or culvert structure on a creek, public ditch, or major watercourse. The proposed project does not include land disturbing activities which involve a pipeline or utility crossing of a creek, public ditch, or major watercourse.

The proposed project does not include land disturbing activities which construct, improve, repair or alter the hydraulic characteristics of a conveyance system that extends across two or more parcels of record not under common ownership and has a drainage area of 200 acres or greater. Rule 7.0 does not apply.

Buffers (Rule 8.0)

The proposed project does not include a land disturbing activity on land adjacent or directly contributing to a Public Water, Additional Waters, High or Outstanding Ecological Value Waters, a Public Ditch, or Impaired Waters/waters exceeding state water quality standards. Rule 8.0 does not apply.

Variances (Rule 10.2)

The proposed project is not requesting a variance from the District's rules, regulations, and policies. Rule 10.2 does not apply.

Figure 1: Project Location





Figure 2: Site Plan









Figure 3: Erosion and Sediment Control Plan








Figure 4: Floodplain Impact

NATIONAL SPORTS CENTER




MASC - COB FIELDS

BLAINE, MN

1700 105TH AVE, BLAINE, MN, 55449



VICINITY MAP



ALL CONSTRUCTION SHALL COMPLY WITH APPLICABLE STATE AND LOCAL ORDINANCES.

GENERAL NOTES

iii. OR APPROVED EQUAL.

12. ALL EROSION CONTROL METHODS SHALL COMPLY WITH MPCA AND LOCAL REGULATIONS.

 $oxed{13}$. MINIMIZE DISTURBANCE TO SITE AND PROTECT EXISTING SITE FEATURES (INCLUDING TURF AND VEGETATION) WHICH ARE TO REMAIN.

14. PROPOSED CONTOURS AND SPOT ELEVATIONS ARE SHOWN TO FINISH GRADE UNLESS OTHERWISE NOTED.

15. PROPOSED ELEVATIONS SHOWN TYPICALLY AS 99.1 OR 99 SHALL BE UNDERSTOOD TO MEAN 899.1 OR 899.

16. SPOT ELEVATIONS SHOWN IN PARKING LOTS, DRIVES AND ROADS INDICATE GUTTER GRADES, UNLESS NOTED OTHERWISE.

17. THE CONTRACTOR WILL BE SOLELY RESPONSIBLE FOR DETERMINING QUANTITIES OF CUT, FILL AND WASTE MATERIALS TO BE HANDLED, AND FOR AMOUNT OF GRADING TO BE DONE IN ORDER TO COMPLETELY PERFORM ALL WORK INDICATED ON THE DRAWINGS. IMPORT SUITABLE MATERIAL AND EXPORT UNSUITABLE / EXCESS / WASTE MATERIAL, AS REQUIRED, AT NO ADDITIONAL COST TO THE OWNER.

18. NO FINISHED SLOPES SHALL EXCEED 3' HORIZONTAL TO 1' VERTICAL (3:1), UNLESS OTHERWISE NOTED.

19. ALL DISTURBED AREAS WHICH ARE NOT DESIGNATED TO BE PAVED OR RECEIVE TURF, SHALL RECEIVE AT LEAST 6" OF TOPSOIL AND SHALL BE SEEDED. REFER TO FINISHING PLANS FOR SEED LOCATIONS. ALL AREAS NOT DESIGNATED FOR SOD OR A SPECIFIC SEED MIX, WHICH ARE DISTURBED BY CONSTRUCTION, SHALL BE SEEDED WITH SEED MIX #1.

20. FAILURE OF TURF DEVELOPMENT: IN THE EVENT THE CONTRACTOR FAILS TO PROVIDE AN ACCEPTABLE TURF, RE-SEED ALL APPLICABLE AREAS, AT NO ADDITIONAL COST TO THE OWNER, TO THE SATISFACTION OF THE ENGINEER OR LANDSCAPE

21. ALL STORM SEWER PIPE SHALL BE PVC PIPE (ASTM D3034, SDR 35) INSTALLED IN ACCORDANCE WITH ASTM D2321, UNLESS OTHERWISE NOTED.

22. ALL STORM SEWER PIPE CROSSING WATERMAIN, OUTSIDE OF THE PUBLIC RIGHT-OF-WAY, SHALL BE ASTM D2665, SCHEDULE 40 PVC WITH SOLVENT WELD JOINTS.

23. FLEXIBLE JOINTS AT STORM SEWER PIPE CONNECTIONS TO STRUCTURES: a. IN ACCORDANCE WITH MINNESOTA PLUMBING CODE, PROVIDE FLEXIBLE JOINTS AT ALL PIPE CONNECTIONS TO ALL STORM SEWER STRUCTURES.

b. ACCEPTABLE MANUFACTURERS / PRODUCTS:

i. FERNCO, "CONCRETE MANHOLE ADAPTORS" OR "LARGE-DIAMETER WATERSTOPS" ii. PRESS-SEAL, WATERSTOP GROUTING RINGS"

26. LOCATE ALL EXISTING UTILITIES. VERIFY LOCATION, SIZE AND INVERT ELEVATION OF ALL EXISTING UTILITIES. BEFORE BEGINNING CONSTRUCTION.

27. STAKE LIMITS OF WALKS AND CURBING PRIOR TO INSTALLATION OF GATE VALVES, CATCH BASINS, AND MANHOLES. ADJUST GATE VALVE AND MANHOLE LOCATIONS TO AVOID PLACEMENT OF THESE STRUCTURES IN WALKS AND CURB AND GUTTER. STAKE CURB AND GUTTER ALIGNMENTS TO ALLOW CURB INLET TYPE CATCH BASINS TO PROPERLY ALIGN WITH CURB AND GUTTER.

28. ALL DISTURBED AREAS INCLUDING SOIL STOCKPILE SHALL BE STABILIZED WITH VEGETATION WITHIN SEVEN (7) DAYS OF ROUGH GRADING OR 24 HOURS OF INACTIVITY.

DRAWING INDEX

NATIONAL SPORTS CENTER

EXISTING CONDITIONS AND REMOVALS PLAN SITE LAYOUT AND FINISHING PLAN

GRADING AND EROSION CONTROL PLAN

DRAIN TILE AND STORM SEWER PLAN

C1.21 **EXISTING CONDITIONS AND REMOVALS PLAN**

SITE LAYOUT AND FINISHING PLAN

GRADING AND EROSION CONTROL PLAN DRAIN TILE AND STORM SEWER PLAN

EXISTING CONDITIONS AND REMOVALS PLAN SITE LAYOUT AND FINISHING PLAN

GRADING AND EROSION CONTROL PLAN

DRAIN TILE AND STORM SEWER PLAN

SITE DETAILS

SITE DETAILS C2.12

SITE DETAILS

STORMWATER POLLUTION PREVENTION PLAN


SWPPP - PROJECT DESCRIPTION

SWPPP - SOILS MAP

SWPPP - NARRATIVE

PRELIMINARY DRAFT - FOR AGENCY REVIEW ONLY











| IED DVA/ | 1/ | NO. | ISSUED FOR | DATE | NATIONAL CROPES OF METER AMAINIFICATA |
|-----------|-----|-----|------------|------|---------------------------------------|
| RW | K | | | | NATIONAL SPORTS CENTER, MINNESOTA |
| NI. | | | | | |
| ` RW | K L | | | | MASC CORFIEIDS |
| | | | | | MASC - COB FIELDS |
| ED IDD | . + | - | | | |
| JRP | | | | | TITLE CLIEFT |
| PROJ. NO. | | | | | TITLE SHEET |
| | | - | | | 1 |
| | | | | | |






- 1. REFER TO SHEET C0.01 TITLE SHEET, FOR GENERAL NOTES.
- 2. CHECK ALL PLAN AND DETAIL DIMENSIONS AND VERIFY SAME BEFORE FIELD LAYOUT.
- 4. ALL DISTURBED AREAS WHICH ARE NOT DESIGNATED TO BE PAVED OR RECEIVE SYNTHETIC TURF SHALL RECEIVE AT LEAST 6" OF TOPSOIL AND SHALL BE
- 5. FAILURE OF TURF DEVELOPMENT: IN THE EVENT THE CONTRACTOR FAILS TO PROVIDE AN ACCEPTABLE TURF, THE CONTRACTOR SHALL RE-SEED ALL APPLICABLE AREAS, AT NO ADDITIONAL COST TO THE OWNER, TO THE SATISFACTION OF THE ENGINEER.






PRELIMINARY DRAFT - FOR AGENCY REVIEW ONLY










| [| DESIGNED | RWK | NO. | ISSUED FOR | DATE | NATIONAL CROPES OFFITED AMAINIFICATA | |
|------------|--------------|-----|-----|------------|------|--------------------------------------|------|
| | | | | | | NATIONAL SPORTS CENTER, MINNESOTA | SHE |
| F | DRAWN | | | | | | _ |
| - | 5101111 | RWK | | | | MASC - COB FIELDS | |
| H | | | - | | | IVIASC - COD I ILLUS | |
| CHECKE | CHECKED | JRP | | | | | TCO. |
| | | | | | | SITE REFERENCE PLAN | |
| (| CLIENT PROJ. | NO. | | | | SHE KEI EKENCE I EAN | |
| 0V1.131841 | | | | | | | |











LEGEND

TREE REMOVALS



REMOVALS KEY NOTE

PROTECTION KEY NOTE

NOTES

- 1. REFER TO SHEET C1.0, TITLE SHEET, FOR GENERAL NOTES.
- 2. MINIMIZE DISTURBANCE TO SITE AND PROTECT EXISTING VEGETATION AND SITE FEATURES (CURBS, WALKS, PAVEMENTS, OVERHEAD AND UNDERGROUND UTILITIES, SIGNAGE, ROADWAYS, ETC.) WHICH ARE TO REMAIN.
- 3. REPAIR OR REPLACE EXISTING PROPERTY AND SITE FEATURES, INCLUDING GRASS AND VEGETATION, WHICH IS TO REMAIN THAT IS DAMAGED BY THE WORK, TO THE OWNER'S SATISFACTION AND AT NO ADDITIONAL COST TO THE OWNER.
- 4. HIRE THE SERVICES OF A UTILITY LOCATOR COMPANY TO LOCATE ALL PRIVATELY OWNED UTILITIES THAT MAY BE DISTURBED BY CONSTRUCTION OPERATIONS.

KEY NOTE LEGEND

REMOVE TREE, INCLUDING STUMP

REMOVE AND SALVAGE IRRIGATION

PROTECT TREE & LANDSCAPING


PROTECT EXISTING PAVEMENT

PROTECT STORM SEWER STRUCTURE

PROTECT STRUCTURE (MOVE IF NECESSARY)


PROTECT SIGN

PROTECT IRRIGATION CONTROLS ON POST



PRELIMINARY DRAFT - FOR AGENCY REVIEW ONLY








7575 GOLDEN VALLEY ROAD, SUITE 200 MINNEAPOLIS, MN, 55427

| | DESIGNED | RWK | NO. | ISSUED FOR | DATE | NATIONAL CROPTS OFNITTED AMAINIFOOTA |
|--|--------------|-----------------------------|----------|---------------------------------------|------|--|
| | | | | | | NATIONAL SPORTS CENTER, MINNESOTA |
| | DRAWN | | | | | |
| | Diotevit | RWK | \vdash | | | FIELDS 29-32 |
| | | JRP | - | | | 116603 23-32 |
| | CHECKED | | | | | |
| | | EXISTING CONDITIONS AND REA | | EXISTING CONDITIONS AND REMOVALS PLAN | | |
| | CLIENT PROJ. | NO. | | | | EXISTING CONDITIONS AND REMOVALS I LAN |
| | NV1 131841 | | | | | |



- 1. REFER TO SHEET C1.0 TITLE SHEET FOR GENERAL NOTES.
- 2. CHECK ALL PLAN AND DETAIL DIMENSIONS AND VERIFY SAME BEFORE FIELD LAYOUT.
- 3. ALL DISTURBED AREAS WHICH ARE NOT WITHIN THE FIELDS SHALL RECEIVE AT LEAST 6" OF TOPSOIL AND SHALL BE SEEDED.
- 4. FAILURE OF TURF DEVELOPMENT: IN THE EVENT THE CONTRACTOR FAILS TO PROVIDE AN ACCEPTABLE TURF, THE CONTRACTOR SHALL RE-SEED ALL APPLICABLE AREAS, AT NO ADDITIONAL COST TO THE OWNER, TO THE SATISFACTION OF THE ENGINEER.

LEGEND



REFERENCE KEY TO SITE DETAILS DETAIL I.D NUMBER (TOP) DETAIL SHEET NUMBER (BOTTOM)



SYNTHETIC TURF FIELD (1) (C2.12)






FENCING KEY NOTE




FENCING KEY NOTES

5' HIGH CHAIN LINK FENCE WITH TOP AND BOTTOM RAIL

4' WIDE, 5' HIGH SINGLE SWING GATE WITH LOCKING DEVICE










PRELIMINARY DRAFT - FOR AGENCY REVIEW ONLY







7575 GOLDEN VALLEY ROAD, SUITE 200 MINNEAPOLIS, MN, 55427

| DESIG | NED | RWK | NO. | ISSUED FOR | DATE | NATIONAL SPORTS CENTER, MINNESOTA |
|------------|---------|-----|-----|------------|------|--|
| DDAVA | /h! | | | | | 147 (11314) (E.S. OKTS CENTER, WINGINGSOT) |
| DRAW | / N | RWK | | | | FIELDS 29-32 |
| | | | | | | FIELDS 29-32 |
| CHEC | KED | JRP | | | | |
| CLIEN | T PROJ. | NO | | | | SITE LAYOUT AND FINISHING PLAN |
| 0V1.131841 | | | | | | |

C1.22




REFERENCE KEY TO SITE DETAILS DETAIL I.D. NUMBER (TOP) DETAIL SHEET NUMBER (BOTTOM) **EXISTING CONTOUR** EXISTING SPOT ELEVATION PROPOSED CONTOUR PROPOSED SPOT ELEVATION

ME = MATCH EXISTING

EOF = EMERGENCY OVERFLOW PROPOSED GRADING LIMITS PROPOSED MANHOLE (MH) PROPOSED CATCH BASIN (CB) PROPOSED FLARED END SECTION (FES)


PRELIMINARY DRAFT - FOR AGENCY REVIEW ONLY

C1.23






| - (| | \ | | | |
|-----------|--------|-----|------------|------|--|
| SIGNED | DVAZZ | NO. | ISSUED FOR | DATE | 114 TIONIAL CROPTS OF LITER AND LICOTA |
| | RWK | | | | NATIONAL SPORTS CENTER, MINNESOTA |
| AWN | | | | | |
| AVVIN | RWK | | | | FIELDS 29-32 |
| | | | , , | ! | FIELDS 29-32 |
| CKED | JRP | | | | |
| | JUL | | | | |
| ENT PROJ. | NO | 1 | , | ! | GRADING AND EROSION CONTROL PLAN |
| | 121011 | | | | |




NOTES

- 1. REFER TO SHEET CO.01, TITLE SHEET, FOR GENERAL NOTES.
- 2. ALL STORM SEWER PIPE SHALL BE PVC PIPE (ASTM D3034, SDR 35) INSTALLED IN ACCORDANCE WITH ASTM D2321, UNLESS
- 3. ALL STORM SEWER PIPE CROSSING WATERMAIN, OUTSIDE OF THE PUBLIC RIGHT-OF-WAY, SHALL BE ASTM D2665, SCHEDULE 40 PVC WITH SOLVENT WELD JOINTS.
- 4. FLEXIBLE JOINTS AT STORM SEWER PIPE CONNECTIONS TO STRUCTURES:
- a. IN ACCORDANCE WITH MINNESOTA PLUMBING CODE, PROVIDE FLEXIBLE JOINTS AT ALL PIPE CONNECTIONS TO ALL STORM SEWER STRUCTURES.
- b. ACCEPTABLE MANUFACTURERS / PRODUCTS:
- i. FERNCO, "CONCRETE MANHOLE ADAPTORS" OR "LARGE-DIAMETER WATERSTOPS"
- ii. PRESS-SEAL, WATERSTOP GROUTING RINGS"
- iii. OR APPROVED EQUAL.
- 5. INSTALL MANOLES, CATCH BASINS, STORM SEWER, SANITARY SEWER, DRAIN TILE, AND OTHER POTENTIAL SOURCES OF CONTAMINATION AT LEAST 10 FEET HORIZONTALLY FROM ANY WATERMAIN PER MN PLUMBING CODE. THIS ISOLATION DISTANCE IS MEASURED FROM THE OUTER EDGE OF THE PIPE TO THE OUTER EDGE OF THE CONTAMINATION SOURCE (OUTER EDGE OF STRUCTURES OR SIMILAR).
- 6. LOCATE ALL EXISTING UTILITIES. VERIFY LOCATION, SIZE AND INVERT ELEVATION OF ALL EXISTING UTILITIES BEFORE BEGINNING
- 7. STAKE LIMITS OF WALKS AND CURBING PRIOR TO INSTALLATION OF GATE VALVES, CATCH BASINS, AND MANHOLES. ADJUST GATE VALVE AND MANHOLE LOCATIONS TO AVOID PLACEMENT OF THESE STRUCTURES IN WALKS AND CURB AND GUTTER. STAKE CURB AND GUTTER ALIGNMENTS TO ALLOW CURB INLET TYPE CATCH BASINS TO PROPERLY ALIGN WITH CURB AND GUTTER


LEGEND





PRELIMINARY DRAFT - FOR AGENCY REVIEW ONLY







7575 GOLDEN VALLEY ROAD, SUITE 200 MINNEAPOLIS, MN, 55427

| F | RWK | RWK | RWK | NO. | ISSUED FOR | DAIL | NATIONAL SPORTS CENTER, MINNESOTA |
|-------------|-----|-----|-----|-----|---------------------------------|------|-----------------------------------|
| wn F | RWK | | | | FIELDS 29-32 | | |
| CKED | JRP | | | | | | |
| NT PROJ. NO | | | | | DRAIN TILE AND STORM SEWER PLAN | | |

MINNESOTA C1.24



LEGEND

TREE REMOVALS

REMOVALS KEY NOTE

PROTECTION KEY NOTE

NOTES

- 1. REFER TO SHEET CO.01, TITLE SHEET, FOR GENERAL NOTES.
- 2. MINIMIZE DISTURBANCE TO SITE AND PROTECT EXISTING VEGETATION AND SITE FEATURES (CURBS, WALKS, PAVEMENTS, OVERHEAD AND UNDERGROUND UTILITIES, SIGNAGE, ROADWAYS, ETC.) WHICH ARE TO REMAIN.
- 3. REPAIR OR REPLACE EXISTING PROPERTY AND SITE FEATURES, INCLUDING GRASS AND VEGETATION, WHICH IS TO REMAIN THAT IS DAMAGED BY THE WORK, TO THE OWNER'S SATISFACTION AND AT NO ADDITIONAL COST TO THE OWNER.
- 4. HIRE THE SERVICES OF A UTILITY LOCATOR COMPANY TO LOCATE ALL PRIVATELY OWNED UTILITIES THAT MAY BE DISTURBED BY CONSTRUCTION OPERATIONS.

KEY NOTE LEGEND

REMOVE TREE, INCLUDING STUMP

REMOVE AND SALVAGE IRRIGATION

PROTECT TREE & LANDSCAPING


PROTECT EXISTING PAVEMENT

PROTECT STORM SEWER STRUCTURE

PROTECT STRUCTURE (MOVE IF NECESSARY)

PROTECT SIGN


PROTECT IRRIGATION CONTROLS ON POST



C1.31

PRELIMINARY DRAFT - FOR AGENCY REVIEW ONLY







7575 GOLDEN VALLEY ROAD, SUITE 200 MINNEAPOLIS, MN, 55427

| | | | V | | |
|------------------|--------|-----|------------|------|--|
| DESIGNED | DVA/I/ | NO. | ISSUED FOR | DATE | NATIONAL CROPES CENTER AMAINIFICATA |
| | RWK | | | | NATIONAL SPORTS CENTER, MINNESOTA |
| DRAWN | | | | | |
| DRAWIN | RWK | | | | |
| | | | | | FIELDS 55 & 56 |
| CHECKED | JRP | | | | |
| | JKP | | | | EVICTIALS CONDITION AND DENAOVALS DIAM |
| CLIENT DDO | I NO | - | | | EXISTING CONDITION AND REMOVALS PLAN |
| CLIENT PROJ. NO. | | | | | |




NOTES:

- REFER TO SHEET C1.0 TITLE SHEET FOR GENERAL NOTES.
- 2. CHECK ALL PLAN AND DETAIL DIMENSIONS AND VERIFY SAME BEFORE FIELD LAYOUT.
- ALL DISTURBED AREAS WHICH ARE NOT WITHIN THE FIELDS SHALL RECEIVE AT LEAST 6" OF TOPSOIL AND SHALL BE SEEDED.
- 4. FAILURE OF TURF DEVELOPMENT: IN THE EVENT THE CONTRACTOR FAILS TO PROVIDE AN ACCEPTABLE TURF, THE CONTRACTOR SHALL RE-SEED ALL APPLICABLE AREAS, AT NO ADDITIONAL COST TO THE OWNER, TO THE SATISFACTION OF THE ENGINEER.

LEGEND




REFERENCE KEY TO SITE DETAILS DETAIL I.D NUMBER (TOP)
DETAIL SHEET NUMBER (BOTTOM)




PROPOSED CONCRETE WALK $\begin{pmatrix} 10 \\ (2.11) \end{pmatrix}$





PROPOSED CHAIN LINK FENCING WITH MAINTENANCE STRIP






FENCING KEY NOTE



FENCING KEY NOTES

5' HIGH CHAIN LINK FENCE WITH TOP AND BOTTOM RAIL 4' WIDE, 5' HIGH SINGLE SWING GATE WITH LOCKING DEVICE $\begin{pmatrix} 1 \\ C2.12 \end{pmatrix}$




14' WIDE, 5' HIGH DOUBLE SWING GATE WITH LOCKING DEVICE AND PLUNGER ROD $\begin{pmatrix} 1 \\ C2.12 \end{pmatrix}$

20' WIDE, 5' HIGH DOUBLE SWING GATE WITH LOCKING DEVICE AND PLUNGER ROD








PRELIMINARY DRAFT - FOR AGENCY REVIEW ONLY








7575 GOLDEN VALLEY ROAD, SUITE 200 MINNEAPOLIS, MN, 55427

| | RWK | | |
|--------|-------|--|--|
| | RWK | | |
| | | | |
|) | JRP | | |
| ROJ. I | NO. | | |
| 1 1 | 21011 | | |

NATIONAL SPORTS CENTER, MINNESOTA FIELDS 55 & 56 SITE LAYOUT AND FINISHING PLAN

C1.32






NOTES

- 1. REFER TO SHEET CO.01, TITLE SHEET, FOR GENERAL NOTES.
- 2. ALL STORM SEWER PIPE SHALL BE PVC PIPE (ASTM D3034, SDR 35) INSTALLED IN ACCORDANCE WITH ASTM D2321, UNLESS
- 3. ALL STORM SEWER PIPE CROSSING WATERMAIN, OUTSIDE OF THE PUBLIC RIGHT-OF-WAY, SHALL BE ASTM D2665, SCHEDULE 40 PVC WITH SOLVENT WELD JOINTS.
- 4. FLEXIBLE JOINTS AT STORM SEWER PIPE CONNECTIONS TO STRUCTURES:
- a. IN ACCORDANCE WITH MINNESOTA PLUMBING CODE, PROVIDE FLEXIBLE JOINTS AT ALL PIPE CONNECTIONS TO ALL STORM SEWER STRUCTURES.
- b. ACCEPTABLE MANUFACTURERS / PRODUCTS:
- i. FERNCO, "CONCRETE MANHOLE ADAPTORS" OR "LARGE-DIAMETER WATERSTOPS"
- ii. PRESS-SEAL, WATERSTOP GROUTING RINGS"
- iii. OR APPROVED EQUAL.
- 5. INSTALL MANOLES, CATCH BASINS, STORM SEWER, SANITARY SEWER, DRAIN TILE, AND OTHER POTENTIAL SOURCES OF CONTAMINATION AT LEAST 10 FEET HORIZONTALLY FROM ANY WATERMAIN PER MN PLUMBING CODE. THIS ISOLATION DISTANCE IS MEASURED FROM THE OUTER EDGE OF THE PIPE TO THE OUTER EDGE OF THE CONTAMINATION SOURCE (OUTER EDGE OF STRUCTURES OR SIMILAR).
- 6. LOCATE ALL EXISTING UTILITIES. VERIFY LOCATION, SIZE AND INVERT ELEVATION OF ALL EXISTING UTILITIES BEFORE BEGINNING
- 7. STAKE LIMITS OF WALKS AND CURBING PRIOR TO INSTALLATION OF GATE VALVES, CATCH BASINS, AND MANHOLES. ADJUST GATE VALVE AND MANHOLE LOCATIONS TO AVOID PLACEMENT OF THESE STRUCTURES IN WALKS AND CURB AND GUTTER. STAKE CURB AND GUTTER ALIGNMENTS TO ALLOW CURB INLET TYPE CATCH BASINS TO PROPERLY ALIGN WITH CURB AND GUTTER.

LEGEND






C1.34

PRELIMINARY DRAFT - FOR AGENCY REVIEW ONLY









7575 GOLDEN VALLEY ROAD, SUITE 200 MINNEAPOLIS, MN, 55427

| RWK | NO. | ISSUED FOR | DATE | NATIONAL SPORTS CENTER, MINNESOTA |
|------------------|-----|------------|------|-----------------------------------|
| RWK | | | | FIELDS 55 & 56 |
| JRP | | | | |
| J. NO. 131841 | | | | DRAIN TILE AND STORM SEWER PLAN |





TURF FIELD CROSS SECTION

C2.12


NOT TO SCALE

MNDOT SEED MIX 25-121 \ AND BLANKET CAT 25 MINIMUM 6" NATIVE TOPSOIL'-DEPTH = 1.5' ¬ 4H:1V EXISTING-OR SHALLOWER GROUND UNDISTURBED, UNCOMPACTED **INSITU SOIL** ~ ~ ~ ~ ~ ~ ~ ~ ` ***** ~ \ ~ ~ SCARIFY NATIVE SAND TO MINIMUM DEPTH OF 12"

> STORMWATER INFILTRATION BASIN C2.12 **BASINS 1 & 2** NOT TO SCALE


STORMWATER INFILTRATION BASIN NOTES:

- 1. INSTALL APPROPRIATE TEMPORARY EROSION CONTROL DEVICES TO PREVENT SEDIMENT FROM LEAVING OR ENTERING THE INFILTRATION AREA DURING CONSTRUCTION.
- 2. PERFORM WEEKLY INSPECTIONS, INCLUDING AFTER EACH RAINFALL EVENT.
- 3. ROUGH GRADE THE SITE.
- COMPLETE, STABILIZE, AND VEGETATE ALL OTHER SITE IMPROVEMENTS.
- COMPLETE GRADING AND STABILIZATION OF INFILTRATION AREA ONLY AFTER THE CONTRIBUTING DRAINAGE AREA'S VEGETATION HAS REACHED 70% GROWTH OF PERMANENT PERENNIAL VEGETATION, OR PLACEMENT OF SOIL STABILIZATION AND APPROVED BY ENGINEER, AND BEFORE CONSTRUCTION AND INSTALLING VEGETATION IN INFILTRATION AREAS.
- 6. REMOVE TEMPORARY EROSION CONTROL DEVICES AFTER THE CONTRIBUTING DRAINAGE AREA AFTER VEGETATION HAS REACHED 70% GROWTH OF PERMANENT PERENNIAL VEGETATION.
- 7. IN THE EVENT THAT SEDIMENT IS INTRODUCED INTO THE BMP DURING OR IMMEDIATELY FOLLOWING EXCAVATION, THIS MATERIAL SHALL BE REMOVED FROM THE PRACTICE PRIOR TO CONTINUING CONSTRUCTION.
- 8. SUBGRADE SHALL BE PREPARED SO THAT THE AREA BENEATH THE BASINS AND EMBANKMENTS IS STRIPPED OF ALL VEGETATION, TOPSOIL, AND ORGANIC MATTER.
- 9. INSTALLATION WITH DRY SOIL CONDITIONS IS CRITICAL TO PREVENT SMEARING AND COMPACTION. SCHEDULE WORK FOR PERIODS OF DRY WEATHER. DO NOT WORK IF SOIL CONDITIONS ARE WET. EXCAVATION, SOIL PLACEMENT AND RAPID STABILIZATION OF PERIMETER SLOPES WITH METHODS SHOWN ON PLAN MUST BE COMPLETED BEFORE THE NEXT PRECIPITATION EVENT.
- 10. REMOVAL OF ACCUMULATED SEDIMENT AND DEBRIS SHALL BE DONE BY HAND OR, IF SELF-PROPELLED EQUIPMENT IS REQUIRED, FROM OUTSIDE THE PERIMETER OF THE INFILTRATION AREAS.




PRELIMINARY DRAFT - FOR AGENCY REVIEW ONLY










| SNED | RWK | NO. | ISSUED FOR | DATE | NATIONAL CROPTS OF STEP AMAINIFECTA |
|----------|-------|-----|------------|------|-------------------------------------|
| | KVVK | | | | NATIONAL SPORTS CENTER, MINNESOTA |
| VN | RWK | | | | MASC - COB FIELDS |
| | | . | | | IVIASC - COB FIELDS |
| KED | JRP | | | | CITE DETAIL C |
| IT PROJ. | NO. | | | | SITE DETAILS |
|)V1.1 | 31841 | | | | |

STORMWATER POLLUTION PREVENTION PLAN (SWPPP)

NATIONAL SPORTS CENTER - 2024

CITY OF BLAINE ANOKA COUNTY, MINNESOTA



RESPONSIBLE PARTIES:

The Contractor and Owner will be joint applicants under the MPCA's General Stormwater Permit for Construction Activity as required by the National Pollutant Discharge Elimination System (NPDES) Phase II program.

The Contractor shall provide one or more trained Construction SWPPP Manager(s) knowledgeable and experienced in the application of erosion prevention and sediment control BMPs that will oversee the implementation of the SWPPP, and the installation, inspection and maintenance of the erosion prevention and sediment control BMPs.

A Construction SWPPP Manager must be available for an on-site inspection within 72 hours upon request by the MPCA.

| | COMPANY | CONTACT PERSON | PHONE |
|--------------------------------------|------------------------|----------------|--------------|
| OWNER: | National Sports Center | Neil Ladd | 763-785-5600 |
| SWPPP DESIGNER: | Bolton & Menk, Inc. | Paul Strong | 651-247-8789 |
| CONTRACTOR: | Dimke Excavating | Tom Dimke | 612-225-7100 |
| CONSTRUCTION SWPPP MANAGER: | TBD | TBD | TBD |
| PARTY RESPONSIBLE FOR LONG TERM O&M: | National Sports Center | Neil Ladd | 763-785-5600 |

The SWPPP Designer, Construction SWPPP Manager, and BMP Installer must have appropriate training. Documentation showing training commensurate with the job duties and responsibilities is required to be included in the SWPPP prior to any work beginning on the site. Training documentation for the SWPPP Designer is included on the Narrative sheet. The Contractor shall attach training documentation to this SWPPP for the Construction SWPPP Manager and BMP Installer prior to the start of construction. This information shall be kept up to date until the project NOT is filed.

ADDITIONAL COMPENSATION

Payment for all work associated with Erosion and Sediment Control shall be as described in the Project Manual. Unless otherwise authorized by the Owner no additional payment shall be made for any work required to administer and maintain the site erosion and sediment control in compliance with the Minnesota Pollution Control Agency (MPCA) - General Stormwater Permit for Construction Activity (MN R100001) including but not limited to inspection, maintenance, and removal of BMPs or addition of BMPs to accommodate Contractor phasing.

DOCUMENT RETENTION

Permittees must make the SWPPP, including all inspection reports, maintenance records, training records and other information required by this permit, available to federal, state, and local officials within three (3) days upon request for the duration of the permit and for three (3) years following the NOT.

GENERAL STORMWATER DISCHARGE REQUIREMENTS

All requirements listed in Section 5.1 of the Permit for the design of the permanent stormwater management system and discharge have been included in the preparation of this SWPPP. These include but are not limited to:

- 1. The expected amount, frequency, intensity, and duration of precipitation.
- 2. The nature of stormwater runoff and run-on at the site
- 3. Peak flow rates and stormwater volumes to minimize erosion at outlets and downstream channel and stream bank erosion.
- 4. The range of soil particle sizes expected to be present on the site.

Permanent stormwater treatment systems for this project have been designed in accordance with the guidance in the MN Stormwater Manual in place at the time of bidding. Copies of the design information and calculations are part of this SWPPP and will be provided in digital format upon written request to the Engineer.

PROJECT AREAS:

| Total Project Size (disturbed area) = | 25.1 | ACRES |
|--|------|-------|
| Existing area of impervious surface = | 0.13 | ACRES |
| Post construction area of impervious surface = | 0.60 | ACRES |
| Total new impervious surface area created = | 0.47 | ACRES |
| · | | |

Planned Construction Start Date: Estimated Construction Completion Date:

03/18/2024 11/30/2024

PERMANENT STORMWATER MANAGEMENT SYSTEM:

Type of storm water management used if more than 1 acre of new impervious surface is created:

| | Wet Sedimentation Basin |
|----|--|
| | Infiltration/Filtration |
| | Regional Pond |
| X* | Permanent Stormwater Management Not Required |

*Less than 1 acre of land disturbed

PROJECT LOCATION:

| COUNTY | COUNTY TOWNSHIP | | SECTION | LATITUDE | LONGITUDE | |
|--------|-----------------|------|---------|-----------|------------|--|
| ANOKA | T31N | R23W | 20,21 | 45.16155° | -93.22559° | |
| | | | | | | |

| BMP SUMMARY | QUANTITY | UNIT |
|-------------------------|----------|------|
| Construction Entrance | 1 | EACH |
| Silt Fence | 6771 | LF |
| Inlet Protection Device | 2 | EACH |
| Turf Seed Mix | 4.5000 | AC |
| Native Seed Mix | 0.9000 | AC |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |


DESCRIPTION OF CONSTRUCTION ACTIVITIES AND STORMWATER MANAGEMENT:

Construction activities include: Site grading, turf field construction, road construction, temporary erosion and sediment control, and permanent stabilization.

Numerous fields are proposed to be converted from natural turf to artificial turf. Natural turf will be excavated and the fields will be graded to prepare for artificial turf installation. A new 30' wide connecting roadway and adjacent walking path will be constructed. Shallow depressions for infiltration and rate control were designed to treat the additional impervious. Another depression was designed to treat runofff from an additional parking resulting in 0.12 acres of new impervious.

Stormwater currently sheet flows west, primarily into county ditch 41. In addition, stormwater also flows to several onsite stormwater management facilities.

After construction is complete, stormwater will flow the same as pre-construction.



RECEIVING WATERS:

Receiving waters, including surface water, wetlands, Public Waters, and stormwater ponds, within 1-mile of the project boundary are identified on the USGS 7.5 min quad map above. Receiving waters that are impaired, the impairment, and WLA are listed as follows. All specific BMPs relative to construction activities listed in the permit for special, prohibited, restricted, or impaired have been incorporated into this plan. All specific BMPs listed in approved TMDLs and those BMPs listed for construction related waste load allocations have also been incorporated.

| NAME OF WATER BODY | TYPE (ditch, pond, wetland, lake, etc.) | Special, Prohibited, Restricted Water ¹ | Flows to Impaired Water Within 1-Mile ² | USEPA Approved Construction Related TMDL ³ |
|--------------------|---|---|---|---|
| County Ditch 41 | Ditch | No | No | - |
| | | | | |


¹ Special, prohibited, and restricted waters are listed in Section 23 of the MN Construction Stormwater General Permit (MNR100001). ² Identified as impaired under section 303 (d) of the federal Clean Water Act for phosphorus, turbidity, TSS, dissolved oxygen, and/or aquatic biota. ³ Construction Related TMDLs include those related to: phosphorus, turbidity, TSS, dissolved oxygen, and/or aquatic biota.

IMPLEMENTATION SCHEDULE AND PHASING: The Contractor is required to provide an updated schedule and site management plan meeting the minimum requirements of Section 1717 of the Minnesota Standard Specifications for Construction.


- 1) Submit SWPPP Updates to Engineer. Submittal shall include any requested changes to the SWPPP, including but not limited to: Trained Personnel, Locations for Stockpiles, Concrete Washout, Sanitation Facilities, Types and Locations of Erosion & Sediment Control. Failure to submit updates shall be considered acceptance of the SWPPP as designed with no changes.
- 2) Install perimeter sediment control, inlet protection, and construction exit.
- 3) Grade site,
- 4) Construct turf fields, walking paths, and depressions
- 5) Pave roadway and parking area
- 6) Add additional temporary BMPs as necessary during construction based on inspection reports.
- Ensure final stabilization measures are complete.
- 8) Provide digital copy of all Field SWPPP Documentation including Inspection Reports and SWPPP Revisions to the Owner.
- Submit Notice of Termination (NOT) to MPCA. NOTE: The NOT must be submitted to MPCA before Final Stabilization is considered complete.

PRELIMINARY DRAFT - FOR AGENCY REVIEW ONLY










| DESIGNED | RWK | NO. | . ISSUED FOR DATE | NATIONAL SPORTS CENTER, MINNESOTA | SHEET |
|------------|---------|-----|-------------------|-----------------------------------|--------------------|
| DRAWN | RWK | | | MASC - COB FIELDS | $\frac{1}{1}$ |
| CHECKED | JRP | | | SWPPP - PROJECT DESCRIPTION | ¹ C3.11 |
| CLIENT PRO | .131841 | | | | |



LEGEND

PROJECT BOUNDARY




SOIL TYPE



IMPAIRED, SPECIAL OR PROTECTED WATERS

NATIONAL WETLANDS INVENTORY






SOIL TYPE SUMMARY

| 3012 111 2 301411411 (1(1 | | | | | | |
|---------------------------|---|--------------------|--|--|--|--|
| Map Unit Symbol | Soil Name | Hyd. Soil Group | | | | |
| lw | Isanti fine sandy loam | A/D | | | | |
| Rf | Rifle mucky peat | A/D | | | | |
| LnA | Lino loamy fine sand, 0 to 4 percent slopes | A/D | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

PRELIMINARY DRAFT - FOR AGENCY REVIEW ONLY





| IGINED | | 1 | .00022 . 0.1 | 1 |
|----------|-------|---|--------------|-------|
| | RWK | | | |
| WN | RWK | | | |
| | | 4 | | |
| CKED | JRP | | | |
| NT PROJ. | NO. | 1 | | |
| | 210/1 | | | |

NATIONAL SPORTS CENTER, MINNESOTA MASC - COB FIELDS C3.12 SWPPP - SOILS MAP

SWPPP AMENDMENTS AND SUBMITTALS

Contractor must prepare and submit to the Engineer a SWPPP amendment as necessary to include additional Best Management Practices (BMPs) to correct problems identified or address the following situations.

- 1. Contact information and training documentation for Construction SWPPP Manager and BMP Installer,
- 2. There is a change in construction method of phasing, operation, maintenance, weather or seasonal conditions not anticipated during the design of the SWPPP including but not limited to:
- a. Types and/or Locations of BMPs
- b. Material Storage and Spill Response
- c. Fueling Plans
- d. Locations for Stockpiles, Concrete Washout, and Sanitation Facilities and
- e. Project Phasing
- 3. It is determined that the SWPPP is not achieving objectives of minimizing pollutants in stormwater discharges associated with construction activity, or
- 4. The SWPPP is not consistent with the terms and conditions of the permit.

The Contractor may implement SWPPP amendments immediately and is not required to wait for Engineer review of the submittal. The responsibility for completeness of SWPPP amendments and compliance with the Permit lies with the Contractor. Review, comment, or lack of comment by the Engineer on a SWPPP amendment shall not absolve the responsibilities of the Contractor in any way.

If a change order is issued for a design change the SWPPP amendment will be prepared by the Engineer and included in the change order.

In addition to SWPPP amendments, the Contractor shall submit to the Engineer Weekly Erosion and Sediment Control Schedule meeting the requirements of MnDOT 1717.

The Contractor shall keep copies of all SWPPP amendments, Weekly Erosion and Sediment Control Schedules, inspection logs, and maintenance logs with the field copy of the SWPPP. A PDF copy of these documents will be provided along with a copy of the final Field Copy of the SWPPP to the Engineer along with the signed Notice of Termination when final stabilization is complete.

EROSION PREVENTION PRACTICES

Stormwater conveyance channels shall be routed around unstabilized areas. Erosion controls and velocity dissipation devices shall be used at outlets within and along the length of any constructed conveyance channel.

The normal wetted perimeter of all ditches or swales, including storm water management pond slopes, that drain waters from the site must be stabilized within 200' of any property edge or discharge point, including storm sewer inlets, within 24 hours of connection.

Temporary or permanent ditches or swales used as sediment containment during construction do not need to be stabilized during temporary period of use and shall be stabilized within 24 hours after no longer used as sediment containment.

Mulch, hydromulch, tackifier, or similar practice shall not be used in any portion of the wetted perimeter of a temporary or permanent drainage ditch or swale section with a continuous slope of greater than 2 percent.

Energy dissipation shall be installed at all temporary or permanent pipe outlets within 24 hours of connection to a surface water or permanent stormwater treatment system.

The Contractor shall phase construction and use construction methods to the extent practical to minimize exposed soils. The project phasing shall be documented in the Weekly Erosion and Sediment Control Schedule.

SEDIMENT CONTROL PRACTICES

Down gradient BMPs including perimeter BMPs must be in place before up gradient land- disturbing activities begin and shall remain in place until final stabilization.

All BMPs that have been adjusted or removed to accommodate short-term activities shall be re-installed or replaced the earlier of the end of the work day or before the next precipitation event even if the activity is not complete.

Inlet BMPs may be removed for specific safety concerns. The BMPs shall be replaced as soon as the safety concern is resolved. The removal shall be documented in the SWPPP as a SWPPP amendment.

Temporary stockpiles must have sediment control BMPs. The Contractor shall prepare and submit to the Engineer a SWPPP amendment showing the location of temporary stockpiles and the BMPs for each stockpile. The SWPPP amendment must meet the minimum requirements of Section 9 of the Permit.

Soil compaction shall be minimized and topsoil shall be preserved, unless infeasible or if construction activities dictate soil compaction or topsoil stripping.

The use of polymers, flocculants, or other sedimentation treatment chemicals are not proposed as part of this SWPPP as designed by the Engineer. If methods or phasing of construction require the use of any of these chemicals, the Contractor shall prepare and submit to the Engineer a SWPPP amendment that meets the minimum requirements of Section 9 of the Permit.

TEMPORARY SEDIMENTATION BASINS

A temporary sedimentation basin has not been included in this SWPPP as designed by the Engineer. If a basin is later determined to be desirable or necessary the Contractor shall prepare and submit to the Engineer a SWPPP amendment. Temporary sedimentation basins shall meet or exceed the minimum requirements of Section 14 of the Permit and shall include a basin draining plan meeting or exceeding the minimum requirements of Section 10 of the Permit. Where the site discharges to Special and/or Impaired Waters the SWPPP amendment shall also meet or exceed the minimum requirements of Section 23 of the permit.

DEWATERING

A dewatering plan has not been included in this SWPPP as designed by the Engineer. If dewatering is required for this project, the Contractor shall prepare and submit to the Engineer a SWPPP amendment. All dewatering shall meet or exceed the minimum requirements of Section 10 of the Permit.

POLLUTION PREVENTION

Products and materials that have the potential to leach pollutants that are stored on the site must be stored in a manner designed to minimize contact with stormwater. Materials that are not a source of potential contamination to stormwater or that are designed for exposure to stormwater are not required to be covered.

Hazardous materials including but not limited to pesticides, fertilizer, petroleum products, curing compounds and toxic waste must be properly stored and protected from stormwater exposure as recommended by the manufacturer in an access restricted area.

Solid waste must be stored, collected and disposed of in compliance with Minnesota Administrative Rules Chapter 7035.

Portable toilets must be positioned so that they are secure and will not be tipped or knocked over. Sanitary waste must be disposed of properly in accordance with Minn. R. CH 7041.

Exterior vehicle or equipment washing on the project site shall be limited to a defined area of the site. No engine degreasing is allowed on site. A sign must be installed adjacent to each washout facility that requires site personnel to utilize the proper facilities for disposal of concrete and other washout wastes.

The Contractor shall prepare and submit a SWPPP amendment detailing the location and BMPs proposed for storage of materials, solid waste, portable toilets, and exterior vehicle or equipment washing on the site. The SWPPP amendment shall include a spill prevention and response plan that is appropriate for the materials proposed to be on the site. The SWPPP amendment shall meet or exceed the minimum requirements of Section 12 of the Permit.

INSPECTION & MAINTENANCE

A trained person shall routinely inspect the entire construction site at the time interval indicated on this sheet of the SWPPP during active construction and within 24-hours after a rainfall event greater than 0.5 inches in 24 hours. Following an inspection that occurs within 24-hours after a rainfall event, the next inspection must be conducted at the time interval indicated in the Receiving Waters Table found on the SITE PLAN AND INFORMATION SHEET of the SWPPP.

All inspections and maintenance conducted during construction must be recorded on the day it is completed and must be retained with the SWPPP. Inspection report forms are available in the Project Specifications. Inspection report forms other than those provided shall be approved by the engineer.

The Contractor may request a change in inspection schedule for the following conditions:

- a. Inspections of areas with permanent cover to be reduced to once per month,
- b. Inspections of areas that have permanent cover and have had no construction activity for 12 months to be suspended until construction resumes,
- c. Inspections of areas where construction is suspended due to frozen ground conditions, inspections to be suspended until the earlier of within 24 hours of runoff occurring, or upon resuming construction.

No change in inspection schedule shall occur until authorized by the Engineer.

Inspections must include:

- 1. All erosion prevention and sediment control BMPs and Pollution Prevention Management Measures to ensure integrity and effectiveness.
- 2. Surface waters, including drainage ditches and conveyance systems for evidence of erosion and sediment deposition.
- 3. Construction site vehicle exit locations, streets and curb and gutter systems within and adjacent to the project for sedimentation from erosion or tracked sediment from vehicles.
- 4. Infiltration areas to ensure that no sediment from ongoing construction activity is reaching the infiltration area and that equipment is not being driven across the infiltration area.

All non-functioning BMPs and those BMPs where sediment reaches one-half (1/2) of the depth of the BMP, or in the case of sediment basins one-half (1/2) of the storage volume, must be repaired, replaced, or supplemented by the end of the next business day after discovery, or as soon as field conditions allow.

Permittees must repair, replace or supplement all nonfunctional BMPs with functional BMPs by the end of the next business day after discovery, or as soon as field conditions allow.

Any sediment that escapes the site must be removed and the area stabilized within 7 calendar days of discovery unless precluded by legal, regulatory, or physical access in which case the work shall be completed within 7 calendar days of authorization. Paved surfaces such as streets shall have any escaped or tracked sediment removed by the end of the day that it is discovered. Sediment release, other than paved surfaces that can be cleaned up with street sweeping shall be reported immediately upon discovery to the Engineer.

PUBLIC WATER RESTRICTIONS:

For public waters that have been promulgated "work in water restrictions" during fish spawning time frames, all exposed soil areas that are within 200 feet of the water's edge, and drain to these waters must complete stabilization within 24-hours during the time period. MN DNR permits are not valid for work in waters that are designated as infested waters unless accompanied by an Infested Waters Permit or written notification has been obtained from MN DNR stating that such permit is not required. There is no exception for pre-existing permits. If a MN DNR Permit has been issued for the project and the water is later designated as infested, the Contractor shall halt all work covered by the MN DNR Permit until an Infested Waters Permit is obtained or that written notification is obtained stating that such permit is not required.

FINAL STABILIZATION

Final Stabilization is not complete until all the following requirements have been met:

- 1. Substantial Completion has been reached and no ground disturbing activities are anticipated.
- 2. Permanent cover has been installed with an established minimum uniform perennial vegetation density of 70 percent of its expected final growth. Vegetation is not required in areas where no vegetation is proposed by this project such as impervious surfaces or the base of a sand filter.

- 3. Accumulated sediment has been removed from all permanent stormwater treatment systems as necessary to ensure the system is operating as designed.
- 4. All sediment has been removed from conveyance systems
- 5. All temporary synthetic erosion prevention and sediment control BMPs have been removed. BMPs designated on the SWPPP to remain to decompose on-site may remain.
- 6. For residential construction only, permit coverage terminates on individual lots if the structures are finished and temporary erosion prevention and downgradient perimeter control is complete, the residence sells to the homeowner, and the permittee distributes the MPCA's "Homeowner Fact Sheet" to the homeowner.
- 7. For agricultural land only (e.g., pipelines across cropland), the disturbed land must be returned to its preconstruction agricultural use prior to submitting the NOT.

SITE STABILIZATION COMPLETION:

| Stabilization of exposed soils shall begin immediately and shall be | |
|---|----------|
| completed after the construction activity has temporarily or | 24 hours |
| permanently ceased no later than: | |

SITE INSPECTION INTERVAL:

| A trained person shall routinely inspect the entire construction site during active construction at an interval of no more than: | 7 calendar days |
|--|-----------------|
| • | |

SPECIAL ENVIRONMENTAL CONSIDERATIONS AND PERMITS:

| 1) | Was an environmental review required for this project or any part of a common plan of development or sale that includes all or any portion of this project? | NO |
|----|---|----|
| 2) | Does any portion of the site have the potential to affect threatened or endangered species or their critical habitat? | NO |
| 3) | Does any portion of this site discharge to a Calcareous fen. | NO |
| 4) | Will any portion of the site potentially affect properties listed on the National Register of Historic Places or a known or discovered archeological site? | NO |
| 5) | Have any Karst features have been identified in the project vicinity? | NO |
| 6) | Is compliance with temporary or permanent stormwater management design requirements infeasible for this project? | NO |
| 7) | Has the MN DNR promulgated "work in water restrictions" for any Public Water this site disharges to during fish spawning? | NO |

| TYPE OF PERMIT | PERMITTING AGENCY | PERMIT STATUS AND CONDITIONS |
|-------------------------------|-------------------|------------------------------|
| Construction Stormwater NPDES | MPCA | In Progress |
| | | |
| | | |
| | | |

SWPPP DESIGNER TRAINING DOCUMENTATION:

University of Minnesota

Paul Strong

Design Construction of SWPPP (May 31 2026)

PRELIMINARY DRAFT - FOR AGENCY REVIEW ONLY



NATIONAL SPORTS CENTER



NSC ENTRY PLAZA & FIELDS 50 & 51

BLAINE, MN

1700 105TH AVE, BLAINE, MN, 55449



DRAWING INDEX

TITLE SHEET

SITE DETAILS

NATIONAL SPORTS CENTER

EXISTING CONDITIONS AND REMOVALS PLAN

SITE LAYOUT AND FINISHING PLAN

GRADING AND UTILITY PLAN EROSION CONTROL PLAN

SWPPP - SOILS MAP

Treek Trail Johnsville 125th Avenue Northeast SPORTS CENTER 109th Avenue Northeast Lexington

GENERAL NOTES

THE CONTRACTOR WILL BE DECRONCIBLE FOR AND CHALL DAY FOR ALL CONSTRUCTION STAVING ALL CONSTRUCTION STAVING

2. THE CONTRACTOR WILL BE RESPONSIBLE FOR AND SHALL PAY FOR ALL CONSTRUCTION STAKING / LAYOUT.

. OBTAIN AND PAY FOR ALL RELATED CONSTRUCTION PERMITS, INCLUDING THE NPDES PERMIT FROM THE MPCA. SUBMIT A COPY OF ALL PERMITS TO THE CITY AND WATERSHED.

4 CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TRAFFIC CONTROL SIGNAGE (CONSTRUCTION ZONES) NECESSARY TO CONSTRUCT PROPOSED IMPROVEMENTS.

5. INSTALL CONTROL FENCING AND BARRICADING AS NECESSARY TO PROTECT THE PUBLIC

6. INSPECT SITE TO DETERMINE EXTENT OF WORK AND NATURE OF MATERIALS TO BE HANDLE

ALL CONSTRUCTION SHALL COMPLY WITH APPLICABLE STATE AND LOCAL ORDINANCES

7. CHECK ALL PLAN AND DETAIL DIMENSIONS AND VERIFY SAME BEFORE FIELD LAYOU

. REFER TO THE STORM WATER POLLUTION PREVENTION PLAN (SWPPP) NARRATIVE, SHEET C3.12, FOR EROSION CONTROL REQUIREMENTS. SECTION 31 00 00 SHALL BE RESPONSIBLE FOR FULL IMPLEMENTATION OF THE SWI

9. MAINTAIN ADJACENT PROPERTY AND PUBLIC STREETS CLEAN FROM CONSTRUCTION CAUSED DIRT AND DEBRIS ON A DAILY BASIS. PROTECT DRAINAGE SYSTEMS FROM SEDIMENTATION AS A RESULT OF CONSTRUCTION RELATED DIRT ANI DEBRIS.

10. MAINTAIN DUST CONTROL DURING GRADING OPERATIONS

11. ALL EROSION CONTROL METHODS SHALL COMPLY WITH MPCA AND LOCAL REGULATIONS.

12. MINIMIZE DISTURBANCE TO SITE AND PROTECT EXISTING SITE FEATURES (INCLUDING TURF AND VEGETATION) WHICH ARE TO REMAIN

13. PROPOSED CONTOURS AND SPOT ELEVATIONS ARE SHOWN TO FINISH GRADE UNLESS OTHERWISE NOTED.

14. PROPOSED ELEVATIONS SHOWN TYPICALLY AS 99.1 OR 99 SHALL BE UNDERSTOOD TO MEAN 899.1 OR 899.

15. SPOT ELEVATIONS SHOWN IN PARKING LOTS, DRIVES AND ROADS INDICATE GUTTER GRADES, UNLESS NOTED OTHERWISE

16. THE CONTRACTOR WILL BE SOLELY RESPONSIBLE FOR DETERMINING QUANTITIES OF CUT, FILL AND WASTE MATERIALS TO BE HANDLED, AND FOR AMOUNT OF GRADING TO BE DONE IN ORDER TO COMPLETELY PERFORM ALL WORK INDICATED ON THE DRAWINGS. IMPORT SUITABLE MATERIAL AND EXPORT UNSUITABLE / EXCESS / WASTE MATERIAL, AS REQUIRED, AT NO ADDITIONAL COST TO THE OWNER.

17. NO FINISHED SLOPES SHALL EXCEED 3' HORIZONTAL TO 1' VERTICAL (3:1), UNLESS OTHERWISE NOTED.

18. ALL DISTURBED AREAS WHICH ARE NOT DESIGNATED TO BE PAVED OR RECEIVE TURF, SHALL RECEIVE AT LEAST 6" OF TOPSOIL AND SHALL BE SEEDED. REFER TO FINISHING PLANS FOR SEED LOCATIONS. ALL AREAS NOT DESIGNATED FOR SOD OR A SPECIFIC SEED MIX, WHICH ARE DISTURBED BY CONSTRUCTION, SHALL BE SEEDED WITH SEED MIX #1.

19. FAILURE OF TURF DEVELOPMENT: IN THE EVENT THE CONTRACTOR FAILS TO PROVIDE AN ACCEPTABLE TURF, RE-SEED ALL APPLICABLE AREAS, AT NO ADDITIONAL COST TO THE OWNER, TO THE SATISFACTION OF THE ENGINEER OR LANDSCAPE ARCHITECT.

20. ALL STORM SEWER PIPE SHALL BE PVC PIPE (ASTM D3034, SDR 35) INSTALLED IN ACCORDANCE WITH ASTM D2321, UNLESS OTHERWISE NOTED.

21. ALL STORM SEWER PIPE CROSSING WATERMAIN, OUTSIDE OF THE PUBLIC RIGHT-OF-WAY, SHALL BE ASTM D2665, SCHEDULE 40 PVC WITH SOLVENT WELD JOINTS.

22. FLEXIBLE JOINTS AT STORM SEWER PIPE CONNECTIONS TO STRUCTURES:

a. IN ACCORDANCE WITH MINNESOTA PLUMBING CODE, PROVIDE FLEXIBLE JOINTS AT ALL PIPE CONNECTIONS TO ALL STORM SEWER STRUCTURES.

i. FERNCO, "CONCRETE MANHOLE ADAPTORS" OR "LARGE-DIAMETER WATERSTOPS"ii. PRESS-SEAL, WATERSTOP GROUTING RINGS"

iii. OR APPROVED EQUAL.

26. LOCATE ALL EXISTING UTILITIES. VERIFY LOCATION, SIZE AND INVERT ELEVATION OF ALL EXISTING UTILITIES. BEFORE BEGINNING CONSTRUCTION.


27. STAKE LIMITS OF WALKS AND CURBING PRIOR TO INSTALLATION OF GATE VALVES, CATCH BASINS, AND MANHOLES. ADJUST GATE VALVE AND MANHOLE LOCATIONS TO AVOID PLACEMENT OF THESE STRUCTURES IN WALKS AND CURB AND GUTTER. STAKE CURB AND GUTTER ALIGNMENTS TO ALLOW CURB INLET TYPE CATCH BASINS TO PROPERLY ALIGN WITH CURB AND GUTTER.

28. ALL DISTURBED AREAS INCLUDING SOIL STOCKPILE SHALL BE STABILIZED WITH VEGETATION WITHIN SEVEN (7) DAYS OF ROUGH GRADING OR 24 HOURS OF INACTIVITY.

DDELIMINARY DRAFT - FOR REVIEW ONLY



Nature Center











0V1.132864


PRELIMINARY DRAFT - FOR REVIEW ONLY












BIORETENTION POND 3 NOTES:

NOT TO SCALE


1. INSTALL APPROPRIATE TEMPORARY EROSION CONTROL DEVICES TO PREVENT SEDIMENT FROM LEAVING OR ENTERING THE FILTRATION AREA DURING CONSTRUCTION.

- 2. PERFORM WEEKLY INSPECTIONS, INCLUDING AFTER EACH RAINFALL EVENT.
- 3. ROUGH GRADE THE SITE.
- 4. COMPLETE, STABILIZE, AND VEGETATE ALL OTHER SITE IMPROVEMENTS.
- COMPLETE GRADING AND STABILIZATION OF FILTRATION AREA ONLY AFTER THE CONTRIBUTING DRAINAGE AREA'S VEGETATION HAS REACHED 70% GROWTH OF PERMANENT PERENNIAL VEGETATION, OR PLACEMENT OF SOIL STABILIZATION AND APPROVED BY ENGINEER, AND BEFORE CONSTRUCTION AND INSTALLING VEGETATION IN FILTRATION AREAS.
- REMOVE TEMPORARY EROSION CONTROL DEVICES AFTER THE CONTRIBUTING DRAINAGE AREA AFTER VEGETATION HAS REACHED 70% GROWTH OF PERMANENT PERENNIAL VEGETATION.
- 7. IN THE EVENT THAT SEDIMENT IS INTRODUCED INTO THE BMP DURING OR IMMEDIATELY FOLLOWING EXCAVATION, THIS MATERIAL SHALL BE REMOVED FROM THE PRACTICE PRIOR TO CONTINUING CONSTRUCTION.
- 8. SUBGRADE SHALL BE PREPARED SO THAT THE AREA BENEATH THE BASINS AND EMBANKMENTS IS STRIPPED OF ALL VEGETATION, TOPSOIL, AND ORGANIC MATTER.
- 9. INSTALLATION WITH DRY SOIL CONDITIONS IS CRITICAL TO PREVENT SMEARING AND COMPACTION. SCHEDULE WORK FOR PERIODS OF DRY WEATHER. DO NOT WORK IF SOIL CONDITIONS ARE WET. EXCAVATION, SOIL PLACEMENT AND RAPID STABILIZATION OF PERIMETER SLOPES WITH METHODS SHOWN ON PLAN MUST BE COMPLETED BEFORE THE NEXT PRECIPITATION EVENT.
- 10. REMOVAL OF ACCUMULATED SEDIMENT AND DEBRIS SHALL BE DONE BY HAND OR, IF SELF-PROPELLED EQUIPMENT IS REQUIRED, FROM OUTSIDE THE PERIMETER OF THE FILTRATION AREAS.




The valve shall be installed in the full open position. The SWCD will observe the temporary pool following a rain event and will adjust

the valve as needed to achieve the optimum drain down time of approximately 12 hours. Further valve adjustment should not be



needed unless plants show signs of stress.




PEDESTRIAN CURB RAMP

C2.12 NOT TO SCALE

I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION, OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED 05/31/2024






SHEET

0V1.132864

STORMWATER POLLUTION PREVENTION PLAN (SWPPP)

NATIONAL SPORTS CENTER - 2024

CITY OF BLAINE ANOKA COUNTY, MINNESOTA



RESPONSIBLE PARTIES:

The Contractor and Owner will be joint applicants under the MPCA's General Stormwater Permit for Construction Activity as required by the National Pollutant Discharge Elimination System (NPDES) Phase II program.

The Contractor shall provide one or more trained Construction SWPPP Manager(s) knowledgeable and experienced in the application of erosion prevention and sediment control BMPs that will oversee the implementation of the SWPPP, and the installation, inspection and maintenance of the erosion prevention and sediment control BMPs.

A Construction SWPPP Manager must be available for an on-site inspection within 72 hours upon request by the MPCA.

| | COMPANY | CONTACT PERSON | PHONE |
|--------------------------------------|------------------------|----------------|--------------|
| OWNER: | National Sports Center | Neil Ladd | 763-785-5600 |
| SWPPP DESIGNER: | Bolton & Menk, Inc. | Paul Strong | 651-247-8789 |
| CONTRACTOR: | Dimke Excavation | Tom Dimke | 612-225-7100 |
| CONSTRUCTION SWPPP MANAGER: | TBD | TBD | TBD |
| PARTY RESPONSIBLE FOR LONG TERM O&M: | National Sports Center | Neil Ladd | 763-785-5600 |

The SWPPP Designer, Construction SWPPP Manager, and BMP Installer must have appropriate training. Documentation showing training commensurate with the job duties and responsibilities is required to be included in the SWPPP prior to any work beginning on the site. Training documentation for the SWPPP Designer is included on the Narrative sheet. The Contractor shall attach training documentation to this SWPPP for the Construction SWPPP Manager and BMP Installer prior to the start of construction. This information shall be kept up to date until the project NOT is filed.

ADDITIONAL COMPENSATION

Payment for all work associated with Erosion and Sediment Control shall be as described in the Project Manual. Unless otherwise authorized by the Owner no additional payment shall be made for any work required to administer and maintain the site erosion and sediment control in compliance with the Minnesota Pollution Control Agency (MPCA) - General Stormwater Permit for Construction Activity (MN R100001) including but not limited to inspection, maintenance, and removal of BMPs or addition of BMPs to accommodate Contractor phasing.

DOCUMENT RETENTION

Permittees must make the SWPPP, including all inspection reports, maintenance records, training records and other information required by this permit, available to federal, state, and local officials within three (3) days upon request for the duration of the permit and for three (3) years following the NOT.

GENERAL STORMWATER DISCHARGE REQUIREMENTS

All requirements listed in Section 5.1 of the Permit for the design of the permanent stormwater management system and discharge have been included in the preparation of this SWPPP. These include but are not limited to:

- 1. The expected amount, frequency, intensity, and duration of precipitation.
- 2. The nature of stormwater runoff and run-on at the site
- 3. Peak flow rates and stormwater volumes to minimize erosion at outlets and downstream channel and stream bank erosion.
- 4. The range of soil particle sizes expected to be present on the site.

Permanent stormwater treatment systems for this project have been designed in accordance with the guidance in the MN Stormwater Manual in place at the time of bidding. Copies of the design information and calculations are part of this SWPPP and will be provided in digital format upon written request to the Engineer.

PROJECT AREAS:

| Total Project Size (disturbed area) = | 8.9700 | ACRES |
|--|--------|-------|
| Existing area of impervious surface = | 0.1830 | ACRES |
| Post construction area of impervious surface = | 0.6206 | ACRES |
| Total new impervious surface area created = | 0.4376 | ACRES |
| | | |

Planned Construction Start Date: Estimated Construction Completion Date:

7/29/2024 12/31/2024

PERMANENT STORMWATER MANAGEMENT SYSTEM:

Type of storm water management used if more than 1 acre of new impervious surface is created:

| | | Wet Sedimentation Basin | |
|--|----|--|--|
| | X* | Infiltration/Filtration | |
| | | Regional Pond | |
| | | Permanent Stormwater Management Not Required | |
| *- Less than 1 acre of impervious reconstruction | | | |

PROJECT LOCATION:

| COUNTY | TOWNSHIP | RANGE | SECTION | LATITUDE | LONGITUDE |
|--------|----------|-------|---------|-----------|------------|
| ANOKA | T31N | R23W | 20 | 45.16014° | -93.22381° |
| | | | | | |

| BMP SUMMARY | QUANTITY | UNIT |
|-------------------------|----------|------|
| Construction Entrance | 2 | EACH |
| Silt Fence | 2300 | LF |
| Inlet Protection Device | 10 | EACH |
| Seed Mix 1 | TBD | ACRE |
| Seed Mix 2 | TBD | ACRE |
| Biolog | 1550 | LF |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

DESCRIPTION OF CONSTRUCTION ACTIVITIES AND STORMWATER MANAGEMENT:


Construction activities include: Site grading, field construction, parking lot improvements, temporary erosion and sediment control, and permanent stabilization.

Pavement improvements to the Super Rink parking area is proposed to improve traffic flow and safety. Activities will include realignment of drive lanes, parking areas, and the expansion of the existing wet sedimentation basin on site; however, it will not include full depth pavement reconstruction. While no impervious reconstruction will occur, the wet sedimentation basin will be expanded for aesthetic purposes and additional gravel pathways instaleld, resulting in a net increase of approximately 0.5 acres of impervious.

Additionally, Fields 50 and 51, directly north of the Super Rink, will be raised to improve drainage and reduce the flood frequency of those fields and to provide grass berms for spectator seating. Stormwater from the parking lot currently flows to the existing wet sedimentation, which outlets to county ditch 41. Stormwater from the field sheet flows into county ditch 41.

After construction is complete, stormwater will flow the same as pre-construction.

Stormwater BMPs proposed; wet sedimentation.



RECEIVING WATERS:

Receiving waters, including surface water, wetlands, Public Waters, and stormwater ponds, within 1-mile of the project boundary are identified on the USGS 7.5 min guad map above. Receiving waters that are impaired, the impairment, and WLA are listed as follows. All specific BMPs relative to construction activities listed in the permit for special, prohibited, restricted, or impaired have been incorporated into this plan. All specific BMPs listed in approved TMDLs and those BMPs listed for construction related waste load allocations have also been incorporated.

| NAME OF WATER BODY | TYPE (ditch, pond, wetland, lake, etc.) | Special, Prohibited, Restricted Water ¹ | Flows to Impaired Water Within 1-Mile ² | USEPA Approved Construction Related TMDL ³ |
|--------------------|---|---|---|---|
| County Ditch 41 | Ditch | No | No | - |
| | | | | |


¹ Special, prohibited, and restricted waters are listed in Section 23 of the MN Construction Stormwater General Permit (MNR100001). ² Identified as impaired under section 303 (d) of the federal Clean Water Act for phosphorus, turbidity, TSS, dissolved oxygen, and/or aquatic biota. ³ Construction Related TMDLs include those related to: phosphorus, turbidity, TSS, dissolved oxygen, and/or aquatic biota.

IMPLEMENTATION SCHEDULE AND PHASING: The Contractor is required to provide an updated schedule and site management plan meeting the minimum requirements of Section 1717 of the Minnesota Standard Specifications for Construction.


- 1) Submit SWPPP Updates to Engineer. Submittal shall include any requested changes to the SWPPP, including but not limited to: Trained Personnel, Locations for Stockpiles, Concrete Washout, Sanitation Facilities, Types and Locations of Erosion & Sediment Control. Failure to submit updates shall be considered acceptance of the SWPPP as designed with no changes.
- 2) Install perimeter sediment control, inlet protection, and construction exit. 3) Complete removals
- 4) Complete mass grading
- 5) Complete parking area improvements
- 6) Add additional temporary BMPs as necessary during construction based on inspection reports.
- Ensure final stabilization measures are complete.
- 8) Provide digital copy of all Field SWPPP Documentation including Inspection Reports and SWPPP Revisions to the Owner.
- 9) Submit Notice of Termination (NOT) to MPCA. NOTE: The NOT must be submitted to MPCA before Final Stabilization is considered complete.

PRELIMINARY DRAFT - FOR AGENCY REVIEW ONLY









| DESIGNED | RWK | NO. | ISSUED FOR | DATE | NATIONAL COORTS CENTED MAININESCOTA | CHEET |
|--------------|--------|----------|------------|------|-------------------------------------|-----------------|
| | IVVVIV | | | | NATIONAL SPORTS CENTER, MINNESOTA | SHEET |
| DRAWN | RWK | | | | 1100 51/51/ 51 4 54 0 515/ 50 50 54 | - |
| | IVVIX | | | | NSC ENTRY PLAZA & FIELDS 50 & 51 | C2 11 |
| CHECKED | JRP | | | | | 1 C 3.11 |
| | | <u> </u> | | | SWPPP - PROJECT DESCRIPTION | |
| CLIENT PROJ. | | | | | 1 SWITT TROJECT DESCRIPTION | |
| I 0V1.1 | 31841 | | | | | |

SWPPP AMENDMENTS AND SUBMITTALS

Contractor must prepare and submit to the Engineer a SWPPP amendment as necessary to include additional Best Management Practices (BMPs) to correct problems identified or address the following situations.

- 1. Contact information and training documentation for Construction SWPPP Manager and BMP Installer,
- 2. There is a change in construction method of phasing, operation, maintenance, weather or seasonal conditions not anticipated during the design of the SWPPP including but not limited to:
- a. Types and/or Locations of BMPs
- b. Material Storage and Spill Response
- c. Fueling Plans
- d. Locations for Stockpiles, Concrete Washout, and Sanitation Facilities and
- e. Project Phasing
- 3. It is determined that the SWPPP is not achieving objectives of minimizing pollutants in stormwater discharges associated with construction activity, or
- 4. The SWPPP is not consistent with the terms and conditions of the permit.

The Contractor may implement SWPPP amendments immediately and is not required to wait for Engineer review of the submittal. The responsibility for completeness of SWPPP amendments and compliance with the Permit lies with the Contractor. Review, comment, or lack of comment by the Engineer on a SWPPP amendment shall not absolve the responsibilities of the Contractor in any way.

If a change order is issued for a design change the SWPPP amendment will be prepared by the Engineer and included in the change order.

In addition to SWPPP amendments, the Contractor shall submit to the Engineer Weekly Erosion and Sediment Control Schedule meeting the requirements of MnDOT 1717.

The Contractor shall keep copies of all SWPPP amendments, Weekly Erosion and Sediment Control Schedules, inspection logs, and maintenance logs with the field copy of the SWPPP. A PDF copy of these documents will be provided along with a copy of the final Field Copy of the SWPPP to the Engineer along with the signed Notice of Termination when final stabilization is complete.

EROSION PREVENTION PRACTICES

Stormwater conveyance channels shall be routed around unstabilized areas. Erosion controls and velocity dissipation devices shall be used at outlets within and along the length of any constructed conveyance channel.

The normal wetted perimeter of all ditches or swales, including storm water management pond slopes, that drain waters from the site must be stabilized within 200' of any property edge or discharge point, including storm sewer inlets, within 24 hours of connection.

Temporary or permanent ditches or swales used as sediment containment during construction do not need to be stabilized during temporary period of use and shall be stabilized within 24 hours after no longer used as sediment containment.

Mulch, hydromulch, tackifier, or similar practice shall not be used in any portion of the wetted perimeter of a temporary or permanent drainage ditch or swale section with a continuous slope of greater than 2 percent.

Energy dissipation shall be installed at all temporary or permanent pipe outlets within 24 hours of connection to a surface water or permanent stormwater treatment system.

The Contractor shall phase construction and use construction methods to the extent practical to minimize exposed soils. The project phasing shall be documented in the Weekly Erosion and Sediment Control Schedule.

SEDIMENT CONTROL PRACTICES

Down gradient BMPs including perimeter BMPs must be in place before up gradient land- disturbing activities begin and shall remain in place until final stabilization.

All BMPs that have been adjusted or removed to accommodate short-term activities shall be re-installed or replaced the earlier of the end of the work day or before the next precipitation event even if the activity is not complete.

Inlet BMPs may be removed for specific safety concerns. The BMPs shall be replaced as soon as the safety concern is resolved. The removal shall be documented in the SWPPP as a SWPPP amendment.

Temporary stockpiles must have sediment control BMPs. The Contractor shall prepare and submit to the Engineer a SWPPP amendment showing the location of temporary stockpiles and the BMPs for each stockpile. The SWPPP amendment must meet the minimum requirements of Section 9 of the Permit.

Soil compaction shall be minimized and topsoil shall be preserved, unless infeasible or if construction activities dictate soil compaction or topsoil stripping.

The use of polymers, flocculants, or other sedimentation treatment chemicals are not proposed as part of this SWPPP as designed by the Engineer. If methods or phasing of construction require the use of any of these chemicals, the Contractor shall prepare and submit to the Engineer a SWPPP amendment that meets the minimum requirements of Section 9 of the Permit.

TEMPORARY SEDIMENTATION BASINS

A temporary sedimentation basin has not been included in this SWPPP as designed by the Engineer. If a basin is later determined to be desirable or necessary the Contractor shall prepare and submit to the Engineer a SWPPP amendment. Temporary sedimentation basins shall meet or exceed the minimum requirements of Section 14 of the Permit and shall include a basin draining plan meeting or exceeding the minimum requirements of Section 10 of the Permit. Where the site discharges to Special and/or Impaired Waters the SWPPP amendment shall also meet or exceed the minimum requirements of Section 23 of the permit.

DEWATERING

A dewatering plan has not been included in this SWPPP as designed by the Engineer. If dewatering is required for this project, the Contractor shall prepare and submit to the Engineer a SWPPP amendment. All dewatering shall meet or exceed the minimum requirements of Section 10 of the Permit.

POLLUTION PREVENTION

Products and materials that have the potential to leach pollutants that are stored on the site must be stored in a manner designed to minimize contact with stormwater. Materials that are not a source of potential contamination to stormwater or that are designed for exposure to stormwater are not required to be covered.

Hazardous materials including but not limited to pesticides, fertilizer, petroleum products, curing compounds and toxic waste must be properly stored and protected from stormwater exposure as recommended by the manufacturer in an access restricted

Solid waste must be stored, collected and disposed of in compliance with Minnesota Administrative Rules Chapter 7035.

Portable toilets must be positioned so that they are secure and will not be tipped or knocked over. Sanitary waste must be disposed of properly in accordance with Minn. R. CH 7041.

Exterior vehicle or equipment washing on the project site shall be limited to a defined area of the site. No engine degreasing is allowed on site. A sign must be installed adjacent to each washout facility that requires site personnel to utilize the proper facilities for disposal of concrete and other washout wastes.

The Contractor shall prepare and submit a SWPPP amendment detailing the location and BMPs proposed for storage of materials, solid waste, portable toilets, and exterior vehicle or equipment washing on the site. The SWPPP amendment shall include a spill prevention and response plan that is appropriate for the materials proposed to be on the site. The SWPPP amendment shall meet or exceed the minimum requirements of Section 12 of the Permit.

INSPECTION & MAINTENANCE

A trained person shall routinely inspect the entire construction site at the time interval indicated on this sheet of the SWPPP during active construction and within 24-hours after a rainfall event greater than 0.5 inches in 24 hours. Following an inspection that occurs within 24-hours after a rainfall event, the next inspection must be conducted at the time interval indicated in the Receiving Waters Table found on the SITE PLAN AND INFORMATION SHEET of the SWPPP.

All inspections and maintenance conducted during construction must be recorded on the day it is completed and must be retained with the SWPPP. Inspection report forms are available in the Project Specifications. Inspection report forms other than those provided shall be approved by the engineer.

The Contractor may request a change in inspection schedule for the following conditions:

- a. Inspections of areas with permanent cover to be reduced to once per month,
- b. Inspections of areas that have permanent cover and have had no construction activity for 12 months to be suspended until construction resumes,
- c. Inspections of areas where construction is suspended due to frozen ground conditions, inspections to be suspended until the earlier of within 24 hours of runoff occurring, or upon resuming construction.

No change in inspection schedule shall occur until authorized by the Engineer.

Inspections must include:

- 1. All erosion prevention and sediment control BMPs and Pollution Prevention Management Measures to ensure integrity and effectiveness.
- 2. Surface waters, including drainage ditches and conveyance systems for evidence of erosion and sediment deposition.
- 3. Construction site vehicle exit locations, streets and curb and gutter systems within and adjacent to the project for sedimentation from erosion or tracked sediment from vehicles.
- 4. Infiltration areas to ensure that no sediment from ongoing construction activity is reaching the infiltration area and that equipment is not being driven across the infiltration area.

All non-functioning BMPs and those BMPs where sediment reaches one-half (1/2) of the depth of the BMP, or in the case of sediment basins one-half (1/2) of the storage volume, must be repaired, replaced, or supplemented by the end of the next business day after discovery, or as soon as field conditions allow.

Permittees must repair, replace or supplement all nonfunctional BMPs with functional BMPs by the end of the next business day after discovery, or as soon as field conditions allow.

Any sediment that escapes the site must be removed and the area stabilized within 7 calendar days of discovery unless precluded by legal, regulatory, or physical access in which case the work shall be completed within 7 calendar days of authorization. Paved surfaces such as streets shall have any escaped or tracked sediment removed by the end of the day that it is discovered. Sediment release, other than paved surfaces that can be cleaned up with street sweeping shall be reported immediately upon discovery to the Engineer.

PUBLIC WATER RESTRICTIONS:

For public waters that have been promulgated "work in water restrictions" during fish spawning time frames, all exposed soil areas that are within 200 feet of the water's edge, and drain to these waters must complete stabilization within 24-hours during the time period. MN DNR permits are not valid for work in waters that are designated as infested waters unless accompanied by an Infested Waters Permit or written notification has been obtained from MN DNR stating that such permit is not required. There is no exception for pre-existing permits. If a MN DNR Permit has been issued for the project and the water is later designated as infested, the Contractor shall halt all work covered by the MN DNR Permit until an Infested Waters Permit is obtained or that written notification is obtained stating that such permit is not required.

FINAL STABILIZATION

Final Stabilization is not complete until all the following requirements have been met:

- 1. Substantial Completion has been reached and no ground disturbing activities are anticipated.
- 2. Permanent cover has been installed with an established minimum uniform perennial vegetation density of 70 percent of its expected final growth. Vegetation is not required in areas where no vegetation is proposed by this project such as impervious surfaces or the base of a sand filter.

- 3. Accumulated sediment has been removed from all permanent stormwater treatment systems as necessary to ensure the system is operating as designed.
- 4. All sediment has been removed from conveyance systems
- 5. All temporary synthetic erosion prevention and sediment control BMPs have been removed. BMPs designated on the SWPPP to remain to decompose on-site may remain.
- 6. For residential construction only, permit coverage terminates on individual lots if the structures are finished and temporary erosion prevention and downgradient perimeter control is complete, the residence sells to the homeowner, and the permittee distributes the MPCA's "Homeowner Fact Sheet" to the homeowner.
- 7. For agricultural land only (e.g., pipelines across cropland), the disturbed land must be returned to its preconstruction agricultural use prior to submitting the NOT.

SITE STABILIZATION COMPLETION:

| Stabilization of exposed soils shall begin immediately and shall be | |
|---|----------|
| completed after the construction activity has temporarily or | 24 hours |
| permanently ceased no later than: | |

SITE INSPECTION INTERVAL:

| A trained person shall routinely inspect the entire construction site during active construction at an interval of no more than: | 7 calendar days |
|--|-----------------|

SPECIAL ENVIRONMENTAL CONSIDERATIONS AND PERMITS:

| 1) | Was an environmental review required for this project or any part of a common plan of development or sale that includes all or any portion of this project? | NO |
|----|---|----|
| 2) | Does any portion of the site have the potential to affect threatened or endangered species or their critical habitat? | NO |
| 3) | Does any portion of this site discharge to a Calcareous fen. | NO |
| 4) | Will any portion of the site potentially affect properties listed on the National Register of Historic Places or a known or discovered archeological site? | NO |
| 5) | Have any Karst features have been identified in the project vicinity? | NO |
| 6) | Is compliance with temporary or permanent stormwater management design requirements infeasible for this project? | NO |
| 7) | Has the MN DNR promulgated "work in water restrictions" for any Public Water this site disharges to during fish spawning? | NO |

| TYPE OF PERMIT | PERMITTING AGENCY | PERMIT STATUS AND CONDITIONS |
|-------------------------------|-------------------|------------------------------|
| Construction Stormwater NPDES | MPCA | In Progress |
| Watershed Permit | CCWD | In Progress |
| | | |
| | | |

SWPPP DESIGNER TRAINING DOCUMENTATION:


University of Minnesota

Paul Strong


Design Construction of SWPPP (May 31 2026)

PRELIMINARY DRAFT - FOR AGENCY REVIEW ONLY

C3.12









Permit Application Review Report Date: 8/7/2024

Board Meeting Date: 8/12/2024

Agenda Item: 16

Applicant/Landowner:

Lakeshore Management LLC Attn: Lakeshore Management 8800 Bronx Avenue Suite 200 Skokie, IL 60077

Project Name: Park of Four Seasons

Project PAN: P-23-068

Project Purpose: Construct 8 new mobile home pads with paved private parking, concrete patio, and utility connections, along with associated stormwater management practices.

Project Location: Area A: on vacant land north of community center. Area B: southeast corner of property., Park of Four Seasons 50 113th Avenue, Blaine

Site Size: size of parcel - 107.0 acres; size of disturbed area - 1.13 acres; size of regulated impervious surface - 0.31

Applicable District Rule(s): Rule 2, Rule 3, Rule 4, Rule 6

Recommendation: Approve with 3 Conditions and 4 Stipulations

Description: The applicant proposes the construction of 6 new mobile home pads and associated infiltration basins in 2 locations at the Park of Four Seasons mobile home park. This project will disturb 1.13 acres and create 0.31 of new impervious. The area drains to County Ditch 39. The relevant water resource concerns are stormwater management, erosion and sediment control and floodplain, which corresponds to District Rules 3, 4, and 6. See attached Figure 1: Project Location and Figure 2: Site Plan.

Conditions to be Met Before Permit Issuance:

Rule 2.7 – Procedural Requirements

1. Submittal of a performance escrow in the amount of \$2,565.00.

Rule 3.0 – Stormwater Management

2. Provide proof of recording of a fully executed Operations and Maintenance Agreement for the perpetual inspection and maintenance of all proposed stormwater management practices after review and approval by the District.

Rule 4.0 – Soils and Erosion Control

3. Update the erosion and sediment control plan to include the following:

- a. After initial grading, surround the proposed infiltration basin with erosion control measures to prevent the basin from clogging.
- b. A note that soils and soil stockpiles will be stabilized within 7 days of inactivity.

Stipulations: The permit will be issued with the following stipulations as conditions of the permit. By accepting the permit, the applicant agrees to these stipulations:

- 1. If dewatering is required, provide DNR dewatering permit prior to construction. If a DNR permit is not required, provide well-field location, rates, discharge location, schedule and quantities prior to construction.
- 2. Completion of post construction infiltration tests on Bioretention #1 and Bioretention #2 by filling the basin to a minimum depth of 6 inches with water and monitoring the time necessary to drain, or multiple double ring infiltration tests to ASTM standards. The Coon Creek Watershed District shall be notified prior to the test to witness the results.
- 3. Submittal of as-builts for the stormwater management practices and associated structures listed in Tables 2 and 3, including volume, critical elevations and proof of installation for hydrodynamic separators.
- 4. The applicant must apply for coverage under the Minnesota Pollution Control Agency's (MPCA's) Construction Stormwater Permit (Permit No: MNR100001).

Exhibits:

| Exhibit Type | Exhibit Author | Signature Date | Received Date |
|---|---------------------------------|----------------|---------------|
| Addendum | Element | 05/30/2024 | 07/09/2024 |
| Geotechnical Report | Element | 08/03/2023 | 10/23/2023 |
| Stormwater Management Design & Calculations | Independence Engineering LLC | | 07/09/2024 |
| Construction Plans | Independence Engineering LLC | 07/08/2024 | 07/09/2024 |

Findings

Fees and Escrows (Rule 2.7):

The applicant has submitted a \$7,010.00 application fee and deposit which corresponds with the nonrefundable application fee (\$10), base fee for a Single Family/Multifamily Residential Development project of 107.0 acres (\$7,000.00). The applicant will be required to submit a performance escrow in the amount of \$2,565.00. This corresponds to a base escrow of \$2,000, plus an additional \$500/acre of disturbance (1.13 acres of land disturbance proposed).

Stormwater Management (Rule 3.0):

Rule 3.0 applies to the proposed project because it includes land disturbing activities creating a cumulative total of 10,000 sf or more of new or fully reconstructed impervious surface.

The Hydrologic Soil Group (HSG) of soils on site are HSG B. Curve Numbers have been shifted down one classification to account for the impacts of grading on soil structure.

Rate Control: Peak stormwater flow rate at point 2 of site discharge increases from the predevelopment condition for the 24-hour precipitation event with a return frequency of 2 and 10 years as shown in Table 1. This increase is due to uncaptured front yard/driveway drainage that is infeasible to direct towards the infiltration basins. The project will not impact Drainage Sensitive Use areas. The rate control standard is met to the maximum extent practicable.

| Point of | 2-year (cfs) | | 10-year (cfs) | | 100-year (cfs | 5) |
|-----------|--------------|----------|---------------|----------|---------------|----------|
| Discharge | Existing | Proposed | Existing | Proposed | Existing | Proposed |

| | 1 | 2.06 | 1.48 | 4.07 | 2.58 | 8.59 | 6.67 |
|---|---|------|------|------|------|------|-------|
| I | 2 | 0 | 0.2 | 0.01 | 0.33 | 0.8 | 0.382 |

Table 1.

Volume Control: The proposed project is new development; therefore, the volume reduction requirement is equal to 1.1 inches over the area of all impervious surface. The amount of proposed impervious required to be treated is 13,411 ft².

The applicant is proposing the Stormwater Management Practices (SMPs) described below:

| Drainage Area | Impervious required to be treated (ft²) | Proposed SMP | TP Removal Factor | Required Water Quality Volume (ft ³) | Water Quality Volume Provided (ft ³) |
|------------------|---|-------------------------|----------------------|---|---|
| untreated | 9,331 | none | 0 | 855 | 0 |
| Basin 2 | 1,200 | bioretention basin 2 | 1 | 110 | 2,445 |
| Basin 1 | 2,880 | bioretention basin 1 | 1 | 264 | 3,358 |
| Totals: | 13,411 | | | 1,229 | 5,803 |

Table 2.

The following pretreatment has been provided:

| SMP ID | Pretreatment Device/Method | Percent TSS Removal | |
|----------------------|----------------------------|---------------------|--|
| bioretention basin 2 | vegetated filter strip | 80 | |
| bioretention basin 1 | vegetated filter strip | 80 | |

Table 3.

Pretreatment is required to be designed such that the device/method provides removal of 80% TSS entering an infiltration or filtration Stormwater Management Practice. The proposed project meets pretreatment requirements as shown in Table 3.

Due to the infeasibility of routing front yard/driveway drainage, the volume control standard has been met to the maximum extent practicable.

Water Quality: The total Water Quality Volume has been provided in aggregate.

Stormwater treatment on site must remove at least 80% of the average annual post development TSS per discharge location. The following TSS removal has been provided:

| Discharge Point | TSS Removal Provided | |
|-----------------|----------------------|--|
| 2 | 100 | |
| 1 | 100 | |

Table 4.

The TSS removal standard is met at each discharge point as shown in Table 4.

Discharges to Wetlands: Stormwater from the proposed project is not being discharged into any wetlands, therefore this section does not apply.

Landlocked Basins: The proposed drainage system does not outlet to a landlocked basin, therefore this section does not apply.

Low Floor Freeboard: The proposed project is new development which includes buildings and habitable structures. Therefore, SMPs must be designed such that the lowest basement floor elevations are at least 2 feet above the 100-yr high water level and 1 foot above the emergency overflow. The lowest basement floor elevations proposed are 895.8 and 909.6 ft MSL. The applicable 100-year high water levels are 894.6 and 906.2 ft MSL and the applicable emergency overflows are

at 894.5 and 906.5 ft MSL. The freeboard requirement is met.

Maintenance:

Access: Sufficient maintenance access has been provided on the plans for all stormwater management practices.

Maintenance Agreements: The proposed stormwater management practices will not be maintained as part of standard municipal public work activities. Therefore, a maintenance agreement that meets District standards will be required.

Soils and Erosion Control (Rule 4.0)

Rule 4.0 applies to the proposed project because it is a land disturbing activity that requires a permit under another District rule.

The proposed project drains to County Ditch 39. The soils affected by the project include Rifle, Markey and Sartell which do not have a soil erodibility factor of 0.15 or greater. Disturbed areas are not proposed to be stabilized within 7 days, as required. The proposed erosion and sediment control plan includes perimeter control, rock construction entrance, inlet protection and street sweeping. The erosion control plan does not meet District requirements because soils and soil stockpiles are not proposed to be stabilized within 7 days of inactivity and infiltration basins do not have perimeter control. See attached Figure 3: Erosion and Sediment Control Plan.

Wetlands (Rule 5.0)

The proposed project does not include activities which result in the filling, draining, excavating, or otherwise altering the hydrology of a wetland. Rule 5.0 does not apply.

Floodplain (Rule 6.0)

Rule 6.0 applies to the proposed project because it includes land disturbing activities within or adjacent to the boundary of the 100-year flood elevation as mapped and modeled by the District.

The regulatory floodplain elevation is 893.1 ft MSL. The application proposes the placement of 6.8 cubic yards of fill within the floodplain. This is a one-time deposition of less than 50 cubic yards, therefore compensatory storage is not required. See attached Figure 5: Floodplain Impacts.

Drainage, Bridges, Culverts, and Utility Crossings (Rule 7.0)

The proposed project does not include land disturbing activities which construct, improve, repair, or alter the hydraulic characteristics of a bridge profile control or culvert structure on a creek, public ditch, or major watercourse. The proposed project does not include land disturbing activities which involve a pipeline or utility crossing of a creek, public ditch, or major watercourse.

The proposed project does not include land disturbing activities which construct, improve, repair or alter the hydraulic characteristics of a conveyance system that extends across two or more parcels of record not under common ownership and has a drainage area of 200 acres or greater. Rule 7.0 does not apply.

Buffers (Rule 8.0)

The proposed project does not include a land disturbing activity on land adjacent or directly contributing to a Public Water, Additional Waters, High or Outstanding Ecological Value Waters, a Public Ditch, or Impaired Waters/waters exceeding state water quality standards. Rule 8.0 does not apply.

Variances (Rule 10.2)

The proposed project is not requesting a variance from the District's rules, regulations, and policies. Rule 10.2 does not apply.



Figure 1: Project Location





Figure 2: Site Plan






Figure 3: Erosion and Sediment Control Plan




Figure 4: Floodplain Impact

PRELIMINARY PLAT

FOR

LAKESHORE MANAGEMENT - PARK OF FOUR SEASONS 50 113TH AVENUE NORTHEAST, CITY OF BLAINE ANOKA COUNTY, MINNESOTA 55434

PROPERTY:
50 113TH AVENUE NE
CITY OF BLAINE
ANOKA COUNTY, MINNESOTA 55434

ARCEL ID: 18-31-23-22-0001 18-31-23-23-0001 18-31-23-32-0001 18-31-23-32-0002

AREA: 4,660,920 SF (107 AC.)
ZONING USE: R-4 (MANUFACTURED HOMES)

OWNER / APPLICANT:

LAKESHORE MANAGEMENT, INC. 8800 BRONX AVENUE, SUITE 200 SKOKIE II I INOIS 60077

ENGINEER:

INDEPENDENCE ENGINEERING LLC 1777 SENTRY PARKWAY WEST BUILDING 12, SUITE 103 BLUE BELL, PENNSYLVANIA 19422 PHONE: (215) 798-4450

SURVEYOR:

NORTHSTAR SURVEYING 310 EAST DEPOT STREET LITCHFIELD, MINNESOTA 55355 PHONE: (320) 693-3710

DEVELOPMENT DESCRIPTION:


THIS DEVELOPMENT PROPOSES THE CONSTRUCTION OF EIGHT NEW MOBILE HOME PAD SITES, EACH COMPLETE WITH A PAVED DRIVEWAY AND PARKING AREA, CONCRETE PATIO, AND UTILITY CONNECTIONS.

MANUFACTURED HOMES STANDARDS PER § 29.125:

| REQUIRED | EXISTING | PROVIDED |
|----------|---|--|
| 20 | 107 | 107 |
| N/A | 45.6 | 0.31 |
| N/A | 42.6% | 42.9% |
| 4,500 SF | N/A | 4,500 SF |
| 60 FT | N/A | 60 FT |
| 10 FT | N/A | 10 FT |
| 5 FT | N/A | 5 FT |
| 5 FT | N/A | 5 FT |
| 20 FT | N/A | 20 FT |
| 5 FT | N/A | 5 FT |
| 100 FT | N/A | 100 FT |
| | 20 N/A N/A 4,500 SF 60 FT 10 FT 5 FT 5 FT 20 FT 5 FT | 20 107 N/A 45.6 N/A 42.6% 4,500 SF N/A 60 FT N/A 10 FT N/A 5 FT N/A 20 FT N/A 5 FT N/A |

PARKING REQUIREMENTS:

| OFF-STREET PARKING: | ONE 440 SF AREA / MOBILE HOME LOT |
|---------------------|-----------------------------------|



SCALE: 1" = 2,000'





SHEET INDEX

| SHEET INDEX | | | | | |
|-------------|-----------|---|--|--|--|
| SHEET NO. | REFERENCE | SHEET TITLE | | | |
| 1 | C000 | COVER SHEET | | | |
| 2 | C300 | EXISTING CONDITIONS PLAN | | | |
| 3 | C310 | DEMOLITION PLAN | | | |
| 4 | C400 | SITE PLAN | | | |
| 5 | C500 | GRADING & LANDSCAPING PLAN | | | |
| 6 | C600 | UTILITY PLAN | | | |
| 7 | C800 | DETAIL SHEET | | | |
| 8 | C2000 | SOIL EROSION & SEDIMENT CONTROL PLAN | | | |
| 9 | C2010 | SOIL EROSION & SEDIMENT CONTROL DETAILS | | | |

REV DATE DESCRIPTION

1 01/11/2024 REVISED PER MULTIPLE REVIEW COMMENTS

2 07/08/2024 REVISED PER CCWD REVIEW COMMENTS

ENGINEERING LLC

1777 SENTRY PARKWAY WEST
BUILDING 12, SUITE 103
BLUE BELL, PENNSYLVANIA 19422
(215) 798-4450
NDEPENDENCE@INDEPENDENCE.ENGINEERING
IJERSEY PENNSYLVANIA MASSACHUSET

3 - PARK OF FOUR SEASON E, CITY OF BLAINE

KESHORE MANAGEMEN'
50 113TH AVENUE N



PROJECT
029-014


DATE
09/27/23

SCALE DRAWN
AS NOTED JEH

AS NOTED JEH


DESIGNED CHECKE

KAL JWJ



C000
SHEET OF





OVERALL PLAN

PROPERTY:
50 113TH AVENUE NE
CITY OF BLAINE
ANOKA COUNTY, MN 55434

PARCEL ID: 18-31-23-22-0001 18-31-23-23-0001 18-31-23-32-0001 18-31-23-32-0002

AREA: 4,660,920 SF (107 AC.) ZONING USE: R-4 (MANUFACTURED HOMES)

UNIT COUNT:

24' x 40': 8
EX. TO REMAIN: 572

TOTAL NEW: 8

TOTAL: 8
TOTAL: 580

STORM SHELTER SCHEDULE:

13' x 42': 13' x 82':

TOTAL: 4
TOTAL COMBINED AREA: 2,704

STORM SHELTER CALCULATIONS:
MINNESOTA RULES 1370 SPACE REQUIREMENTS:
MINIMUM 4 SQUARE FEET PER PARK RESIDENT.

PARK RESIDENTS: 1600 PERSONS STORM SHELTER SPACE REQ: 1600 x 4 SF / PERSON = 6,400 SF ENGINEERING LLC

1777 SENTRY PARKWAY WEST
BUILDING 12, SUITE 103
BLUE BELL, PENNSYLVANIA 19422
(215) 798-4450
INDEPENDENCE@INDEPENDENCE.ENGINEERIN

EXISTING CONDITIONS PLAN
FOR
LAKESHORE MANAGEMENT - PARK OF FOUR SE

0 100 200

GRAPHIC SCALE: 1" = 200'

PROJECT

GRAPHIC SCALE: 1" = 200'

PROJECT
029-014

DATE
09/27/23


SCALE DRAWN
1" = 200' ESC

SCALE DRAWN

1" = 200' ESC

DESIGNED CHECKED

KAL JWJ



C300

SHEET OF

GENERAL DEMOLITION NOTES:

CONTRACTOR AND 811 PRIOR TO DIGGING.

- . ALL CONDITIONS SHALL BE VERIFIED BY THE CONTRACTOR PRIOR TO SUBMITTING A BID, AND SHALL BE ADJUSTED IF NECESSARY. BASE MAP AND BOUNDARY INFORMATION SHOWN HEREON TAKEN FROM A PLAN ENTITLED "PARK OF FOUR SEASON" PREPARED BY NORTHSTAR SURVEYING, 310 EAST DEPOT STREET, MN 55355, DATED JULY 28TH, 2023, REVISED
- NOVEMBER 28TH, 2023. UTILITIES SHOWN HEREON ARE REFERENCED FROM A PRIVATE UTILITY LOCATE SURVEY PERFORMED AND PREPARED BY GPRS, 11299 UNIVERSITY AVE NE, MINNEAPOLIS, MN, DATED NOVEMBER 3RD, 2023, AND SHOWN ON THEIR PLAN ENTITLED "GPRS FINDINGS MAP." SURVEYED UTILITIES CANNOT BE GUARANTEED, AND MUST BE VERIFIED BY THE
- 3. ADDITIONAL SIDEWALK INFORMATION TAKEN FROM GIS DATA, FLOOD PLAIN LINES TAKEN FROM COON CREEK WATERSHED DISTRICT.
- 4. CONTRACTOR IS RESPONSIBLE TO CALL DIG SAFE 811 FOR UTILITY MARK OUT PRIOR TO ANY EXCAVATION.
- 5. CONTRACTOR IS RESPONSIBLE FOR FIELD VERIFYING ANY EXISTING SITE IMPROVEMENTS AND UTILITIES. ALL DISCREPANCIES SHALL BE IDENTIFIED TO THE ENGINEER IN WRITING PRIOR TO COMMENCEMENT OF CONSTRUCTION.
- 6. ALL DEMOLITION SHALL BE PERFORMED IN STRICT ACCORDANCE WITH ALL FEDERAL, STATE, AND LOCAL REGULATIONS.
- 7. DEMOLITION SHALL PROCEED FROM THE TOP OF THE STRUCTURE TO THE GROUND. 8. ALL DEMOLITION WORK SHALL BE COMPLETED ON A GIVEN FLOOR OF A BUILDING BEFORE ANY STRUCTURAL ELEMENTS
- OF THE LOWER FLOORS ARE DISTURBED. 9. CONCRETE AND MASONRY SHALL BE DEMOLISHED IN SMALL SECTIONS.
- 10. STRUCTURAL MEMBERS SHALL BE REMOVED AND LOWERED TO THE GROUND USING HOISTS, DERRICKS, AND/OR OTHER INDUSTRY-ACCEPTED METHODS.
- 11. CONCRETE SLABS-ON-GRADE SHALL BE BROKEN UP UNLESS OTHERWISE DIRECTED. 12. DEMOLITION EQUIPMENT SHALL BE LOCATED SPARSELY THROUGHOUT THE STRUCTURE AND MATERIALS REMOVED IN A
- MANNER TO AVOID THE IMPOSITION OF EXCESSIVE LOADS ON REMAINING STRUCTURAL ELEMENTS. 13. INTERIOR AND EXTERIOR SHORING, BRACING, AND/OR SUPPORTS SHALL BE PROVIDED TO PREVENT MOVEMENT,
- SETTLEMENT, AND COLLAPSE OF STRUCTURES TO BE DEMOLISHED AND ADJACENT FACILITIES. 14. ALL FOUNDATION WALLS, FOOTINGS, AND OTHER MATERIALS WITHIN THE FOOTPRINT OF THE FUTURE STRUCTURE SHALL BE DEMOLISHED. ALL OTHER FOUNDATION SYSTEMS SHALL BE DEMOLISHED TO A DEPTH OF NO LESS THAN TWELVE (12) INCHES BELOW THE GRADE OF PROPOSED PAVEMENT. BASEMENT FLOOR SLABS SHALL BE BROKEN. ALL OPEN UTILITY LINES SHALL BE SEALED WITH CONCRETE.
- 15. COVERED PASSAGEWAYS SHALL BE ERECTED ADJACENT TO AREAS OF DEMOLITION TO PROVIDE SAFE PASSAGE TO PEDESTRIANS. ALL DEMOLITION OPERATIONS SHALL BE PERFORMED TO PREVENT DAMAGE TO STRUCTURES AND ADJACENT BUILDINGS, AND INJURY TO PERSONS.
- 16. EXPLOSIVES SHALL NOT BE USED WITHOUT PRIOR WRITTEN CONSENT OF OWNER AND AUTHORITIES HAVING JURISDICTION.
- 17. DEMOLITION SHALL BE PERFORMED TO MINIMIZE INTERFERENCE WITH ROADS, STREETS, WALKS, AND OTHER WAYS. ROADS, STREETS, WALKS, AND OTHER WAYS SHALL NOT BE CLOSED WITHOUT PRIOR WRITTEN CONSENT OF OWNER AND AUTHORITIES HAVING JURISDICTION. ALTERNATE TRAVEL ROUTES SHALL BE PROVIDED AROUND CLOSED OR OBSTRUCTED WAYS IF REQUIRED BY AUTHORITIES HAVING JURISDICTION.
- 18. WATERING, TEMPORARY ENCLOSURES, AND/OR OTHER APPROPRIATE METHODS SHALL BE EMPLOYED AS NECESSARY TO MINIMIZE THE AMOUNT OF DUST LEAVING THE DEMOLITION SITE. ADJACENT IMPROVEMENTS SHALL BE CLEANED OF ALL DUST AND DEBRIS CAUSED BY DEMOLITION OPERATIONS. ALL ADJACENT AREAS SHALL BE RETURNED TO THE CONDITIONS IN EXISTENCE AT THE COMMENCEMENT OF WORK.
- 19. DEMOLITION SHALL BE PERFORMED TO PREVENT UNAUTHORIZED ENTRY OF ANY PERSONS TO THE SITE AT ANY TIME.
- 20. BELOW GRADE AREAS AND VOIDS RESULTING FROM DEMOLITION OF STRUCTURES AND FOUNDATIONS SHALL BE FILLED WITH SOIL MATERIALS CONSISTING OF STONE, GRAVEL, AND SAND, FREE FROM DEBRIS, TRASH, FROZEN MATERIALS, ROOTS, AND OTHER ORGANIC MATTER. STONES LARGER THAN SIX (6) INCHES IN DIMENSION SHALL NOT BE USED. DEMOLITION MATERIALS MAY NOT BE USED AS FILL. AREAS TO BE FILLED SHALL BE FREE STANDING WATER, FROST, FROZEN MATERIAL, TRASH, AND DEBRIS PRIOR TO FILLING. FILL MATERIALS SHALL BE PLACED IN HORIZONTAL LAYERS NOT EXCEEDING SIX (6) INCHES IN LOOSE DEPTH, AND EACH COMPACTED TO 95% OPTIMUM DRY DENSITY. THE SURFACE SHALL BE GRADED TO MEET ADJACENT CONTOURS AND TO PROVIDE ADEQUATE SURFACE DRAINAGE AWAY
- 21. ALL DEBRIS, RUBBISH, SALVAGEABLE ITEMS, AND HAZARDOUS AND COMBUSTIBLE MATERIALS SHALL BE REMOVED FROM THE SITE AT THE EARLIEST POSSIBLE TIME. MATERIALS TO BE REMOVED MAY NOT BE STORED, SOLD, OR BURNED ON SITE. HAZARDOUS AND COMBUSTIBLE MATERIALS SHALL BE REMOVED IN CONFORMANCE WITH ALL FEDERAL, STATE, AND LOCAL REGULATIONS, AND PROCEDURES ENFORCED BY THE FIRE DEPARTMENT AND OTHER AUTHORITIES HAVING
- 22. ALL UTILITIES SERVICING STRUCTURES TO BE DEMOLISHED SHALL BE DISCONNECTED, SHUT OFF, AND SEALED IN CONCRETE PRIOR TO THE COMMENCEMENT OF DEMOLITION. ALL UTILITY, DRAINAGE, AND SANITARY LINES SHALL BE MARKED FOR POSITION PRIOR TO DISCONNECTION, AND ALL ACTIVE LINES SHALL BE PROTECTED CONSISTENT WITH ACCEPTED INDUSTRY STANDARDS. ALL UTILITY SERVICES TO BE INTERRUPTED SHALL BE CLEARLY MARKED PRIOR TO
- 23. ALL EXISTING UTILITIES SHALL BE REMOVED, AS NECESSARY, IN ACCORDANCE WITH LOCAL UTILITY AGENCY
- 24. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL SAFETY PRECAUTIONS NECESSARY.


DEMOLITION, AND ALL LOCAL UTILITY AGENCIES SHALL BE NOTIFIED TO ENSURE THE CONTINUATION OF SERVICE.

REQUIREMENTS.

25. TEMPORARY SEEDING TO BE IN ACCORDANCE WITH LOCAL AND STATE EROSION AND SEDIMENT CONTROL STANDARDS.

/NV.(N)=890.50± SEWER MANHOLE APPEARS TO BE BACKING UP WATER AND MISC. DEBRIS IN BOTTOM MOBILE HOME MOBILE HOME 111111111111111111 COON CREEK -WATERSHED DISTRICT APPROX. LOCATION FLOODPLAIN COULD NOT LOCATE MANHOLE 113TH LANE NE BITUMINOUS BITUMINOUS MOBILE HOME REPLACE -COMBINATION CURB INLET WITH DECK INLET GRATE BITUMINOUS TO BF RELOCATED BITUMINOUS APPROX WATER LINE PER PARK MAP COMMUNITY CENTER NE BITUMINOUS

AREA 'A'



AREA 'A' 112th SQUARE NE KEY MAP SCALE: NTS

PROPERTY:

UNIT COUNT:

EX. TO REMAIN:

TOTAL NEW:

24' x 40':

TOTAL:

13' x 42':

13' x 82':

50 113TH AVENUE NE CITY OF BLAINE

ANOKA COUNTY, MN 55434

PARCEL ID: 18-31-23-22-0001

AREA: 4,660,920 SF (107 AC.)

18-31-23-23-0001 18-31-23-32-0001

18-31-23-32-0002

STORM SHELTER SCHEDULE

STORM SHELTER CALCULATIONS:

MINIMUM 4 SQUARE FEET PER PARK RESIDENT.

MINNESOTA RULES 1370 SPACE REQUIREMENTS:

STORM SHELTER SPACE REQ: 1600 x 4 SF / PERSON

1600 PERSONS

= 6,400 SF

TOTAL COMBINED AREA:

PARK RESIDENTS:

ZONING USE: R-4 (MANUFACTURED HOMES)

572

580

15 30

GRAPHIC SCALE: 1" = 30' PROJECT 029-014 DATE 09/27/23 SCALE DRAWN

1'' = 30'DESIGNED CHECKED KAL

LEGEND

— X — X — EXISTING FENCE SAN SAN SAN SAN EXISTING SANITARY PIPE

TH FH

EXISTING RIGHT-OF-WAY EXISTING PROPERTY LINE - EXISTING CONTOUR LINE - MAJOR EXISTING CONTOUR LINE - MINOR LIMIT OF DISTURBANCE

EXISTING UNDERGROUND ELECTRIC EXISTING CABLE / COMMS WIRE EXISTING DOMESTIC WATER SERVICE EXISTING GAS SERVICE

EXISTING FLOOD PLAIN BOUNDARY EXISTING STORM PIPE EXISTING TELECOMMUNICATIONS VAULT EXISTING SANITARY MANHOLE

EXISTING STORM MANHOLE EXISTING ELECTRIC TRANSFORMER EXISTING GAS METER EXISTING ELECTRIC METER

EXISTING GAS VALVE EXISTING FIRE HYDRANT EXISTING LIGHT POLE

EXISTING FEATURE TO BE REMOVED

AREA 'B'

SITE PLAN NOTES:

. PROPERTY:

50 113TH AVENUE NE

CITY OF BLAINE ANOKA COUNTY, MINNESOTA 55434

PARCEL ID: 18-31-23-22-0001 18-31-23-23-0001 18-31-23-32-0001

AREA: 4,660,920 SF (107 AC.)

18-31-23-32-0002

ZONE USE: R-4 (MANUFACTURED HOMES)

2. OWNER / APPLICANT: LAKESHORE MANAGEMENT, INC. 8800 BRONX AVENUE, SUITE 200 SKOKIE, ILLINOIS 60077

ENGINEER:

INDEPENDENCE ENGINEERING LLC 1777 SENTRY PARKWAY WEST BUILDING 12, SUITE 103 BLUE BELL, PENNSYLVANIA 19422 PHONE: (215) 798-4450

4. SURVEYOR:


NORTHSTAR SURVEYING 310 EAST DEPOT STREET LITCHFIELD, MINNESOTA 55355 PHONE: (320) 693-3710

- . ALL CONDITIONS SHALL BE VERIFIED BY THE CONTRACTOR PRIOR TO SUBMITTING A BID, AND SHALL BE ADJUSTED IF NECESSARY. NO ADDITIONAL COMPENSATION WILL BE GRANTED AFTER A BID AWARD FOR ANY EQUIPMENT, MATERIAL, OR LABOR REQUIRED TO MODIFY THE DESIGN TO MATCH FIELD CONDITIONS.
- : BASE MAP AND BOUNDARY INFORMATION SHOWN HERON TAKEN FROM A PLAN ENTITLED ENTITLED "PARK OF FOUR SEASON" PREPARED BY NORTHSTAR SURVEYING, 310 EAST DEPOT STREET, MN 55355, DATED JULY 28TH, 2023 REVISED
- ADDITIONAL SIDEWALK INFORMATION TAKEN FROM GIS DATA, FLOOD PLAIN LINES TAKEN FROM COON CREEK WATERSHED DISTRICT.
- 8. TWO REPORTS OF GEOTECHNICAL ENGINEERING WERE PREPARED BY DDG CONSULTING LLC, DATED AUGUST 3, 2023 AND MAY 30, 2024.
- PRIOR TO STARTING CONSTRUCTION, THE CONTRACTOR SHALL BE RESPONSIBLE TO MAKE SURE THAT ALL REQUESTED PERMITS AND APPROVALS HAVE BEEN OBTAINED. NO CONSTRUCTION OR FABRICATION SHALL BEGIN UNTIL THE CONTRACTOR HAS RECEIVED AND THOROUGHLY REVIEWED ALL PLANS AND OTHER DOCUMENTS PROVIDED BY ALL APPLICABLE PERMITTING AUTHORITIES.
- 10. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THESE PLANS AND SPECIFICATIONS AND THE REQUIREMENTS AND STANDARDS OF THE LOCAL GOVERNING AUTHORITY.
- 11. SITE CLEARING SHALL INCLUDE THE LOCATION AND REMOVAL OF ALL UNDERGROUND TANKS, PIPES, VALVES, ETC. CONTRACTOR SHALL REPAIR ANY DISTURBED AREAS TO EXISTING CONDITION, INCLUDING PAVED AREAS AND LANDSCAPED AREAS.
- 12. SOLID WASTE SHALL BE DISPOSED OF BY CONTRACTOR IN ACCORDANCE WITH ALL LOCAL, STATE, AND FEDERAL REGULATIONS.
- 13. ALL UNSUITABLE EXCAVATED MATERIAL SHALL BE TRANSPORTED TO AN APPROVED DISPOSAL LOCATION.
- 14. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL SHORING REQUIRED DURING CONSTRUCTION. SHORING SHALL BE CONSTRUCTED AND MAINTAINED IN ACCORDANCE WITH CURRENT OSHA STANDARDS. CONTRACTOR SHALL MAKE SUFFICIENT ADDITIONAL PROVISIONS TO ENSURE STABILITY OF ALL CONTIGUOUS AND ADJACENT STRUCTURES, AS FIELD CONDITIONS MAY DICTATE.
- 15. CONTRACTOR AND ANY SUBCONTRACTORS SHALL CARRY STATUTORY WORKERS' COMPENSATION INSURANCE, EMPLOYERS' LIABILITY INSURANCE, AND COMMERCIAL GENERAL LIABILITY INSURANCE AT REQUIRED LIMITS OF COVERAGE. ALL CONTRACTORS SHALL HAVE CGL POLICIES ISSUED TO INCLUDE INDEPENDENCE ENGINEERING LLC, WITH ITS SUBCONSULTANTS LISTED AS ADDITIONAL INSURED. ALL CONTRACTORS MUST FURNISH INDEPENDENCE ENGINEERING LLC WITH CERTIFICATES OF INSURANCE PRIOR TO THE COMMENCEMENT OF WORK, AND UPON RENEWAL OF EACH POLICY DURING THE TERM OF CONSTRUCTION CONTRACTOR SHALL INDEMNIFY AND HOLD HARMLESS INDEPENDENCE ENGINEERING LLC AND ITS SUBCONSULTANTS AGAINST ANY DAMAGES, LIABILITIES, OR COSTS, INCLUDING REASONABLE ATTORNEYS' FEES AND DEFENSE COSTS CONNECTED WITH THE PROJECT, INCLUDING ALL CLAIMS BY CONTRACTOR'S EMPLOYEES, TO THE FULLEST EXTENT PERMITTED BY LAW.
- 16. NEITHER THE PROFESSIONAL ACTIVITIES OF INDEPENDENCE ENGINEERING LLC NOR THE PRESENCE OF ITS EMPLOYEES AT THE PROJECT SITE SHALL RELIEVE THE CONTRACTOR OF ITS DUTIES, OBLIGATIONS, AND/OR RESPONSIBILITIES, INCLUDING BUT NOT LIMITED TO CONSTRUCTION MEANS, METHODS, SEQUENCING AND/OR PROTOCOLS NECESSARY FOR PERFORMING, COORDINATING, AND/OR SUPERINTENDING THE WORK IN ACCORDANCE WITH THE PROJECT DOCUMENTS AND APPLICABLE HEALTH AND SAFETY REGULATIONS. THE CONTRACTOR SHALL BEAR SOLE RESPONSIBILITY FOR SITE SAFETY PLANNING, PROVISIONING, IMPLEMENTATION, AND MAINTENANCE. INDEPENDENCE ENGINEERING LLC BEARS NO AUTHORITY TO EXERCISE CONTROL OVER CONTRACTOR OR ITS EMPLOYEES IN CONNECTION WITH CONSTRUCTION.
- 17. INDEPENDENCE ENGINEERING LLC SHALL REVIEW AND TAKE APPROPRIATE ACTION ON SUBMITTALS TO BE SUBMITTED BY CONTRACTOR PRIOR TO THE COMMENCEMENT OF CONSTRUCTION, INCLUDING BUT NOT LIMITED TO SHOP DRAWINGS, PRODUCT, DATA, AND MATERIAL SAMPLES. INDEPENDENCE ENGINEERING LLC SHALL REVIEW SUBMITTALS ONLY FOR CONSISTENCY WITH THE DESIGN DRAWINGS. SUBMITTALS SHALL NOT BE REVIEWED FOR CONSTRUCTION MEANS AND METHODS, COORDINATION OF TRADES, OR SITE SAFETY, WHICH ARE THE SOLE RESPONSIBILITY OF THE CONTRACTOR. INDEPENDENCE ENGINEERING LLC SHALL NOT BE LIABLE FOR DEVIATIONS OR THE RESULTS THEREFROM FROM THE APPROVED CONSTRUCTION DRAWINGS, UNLESS SAID DEVIATIONS ARE PROVIDED IN WRITING BY THE CONTRACTOR PRIOR TO IMPLEMENTATION, AND APPROVED IN WRITING BY INDEPENDENCE ENGINEERING LLC.
- 18. THE CONTRACTOR SHALL NOT DEVIATE FROM THE PLANS AND SPECIFICATIONS. INCLUDING THE NOTES THEREON. WITHOUT PRIOR WRITTEN AUTHORIZATION FROM INDEPENDENCE ENGINEERING LLC AND THE PROJECT OWNER. SHOULD THE CONTRACTOR DEVIATE FROM THE APPROVED PROJECT DOCUMENTS, HE SHALL BEAR SOLE RESPONSIBILITY FOR FINES, PENALTIES, AND ALL COMPENSATORY AND PUNITIVE DAMAGES RESULTING THEREFROM. IN SUCH CASE, THE CONTRACTOR SHALL INDEMNIFY AND HOLD INDEPENDENCE ENGINEERING LLC HARMLESS AGAINST ANY DAMAGES, LIABILITIES, OR COSTS, INCLUDING REASONABLE ATTORNEYS' FEES AND DEFENSE COSTS CONNECTED WITH THE PROJECT, INCLUDING ALL CLAIMS BY CONTRACTOR'S EMPLOYEES, TO THE FULLEST EXTENT PERMITTED BY
- 19. DISPUTES BETWEEN INDEPENDENCE ENGINEERING LLC AND THE CONTRACTOR SHALL BE SUBMITTED TO NONBINDING MEDIATION UNLESS THE PARTIES MUTUALLY AGREE OTHERWISE.
- 20. THE CONTRACTOR AND ITS SUBCONTRACTORS SHALL INCLUDE A PROVISION IN THEIR CONTRACTS WITH THEIR SUBCONTRACTORS, SUBCONSULTANTS, AND SUPPLIERS, PROVIDING FOR MEDIATION AS THE PRIMARY METHOD OF DISPUTE RESOLUTION BETWEEN THOSE PARTIES.
- 21. ALL TRAFFIC SIGNS AND STRIPING SHALL FOLLOW THE REQUIREMENTS SPECIFIED IN THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS," PUBLISHED BY THE FEDERAL HIGHWAY ADMINISTRATION, INCLUDING LOCALLY ADOPTED REVISIONS THERETO.
- 22. BUILDING SETBACKS SHOWN HEREON ARE MEASURED FROM THE EXTERIOR FACE OF BUILDING WALLS. SETBACKS DO NOT ACCOUNT FOR ROOF OVERHANGS, ORNAMENTAL ARCHITECTURAL ELEMENTS, SIGNAGE, OR OTHER EXTERIOR EXTENSION UNLESS OTHERWISE NOTED.
- 23. LOCATION OF ALL EXISTING AND PROPOSED SERVICES AND CONNECTION POINTS ARE APPROXIMATE AND MUST BE CONFIRMED INDEPENDENTLY IN THE FIELD AND WITH LOCAL UTILITY COMPANIES PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION OR EXCAVATION. ALL DISCREPANCIES SHALL BE REPORTED IMMEDIATELY IN WRITING TO THE
- 24. THE CONTRACTOR SHALL BE RESPONSIBLE TO NOTIFY "DIG SAFE 811" 72 HOURS PRIOR TO ANY EXCAVATION ON SITE. CONTRACTOR SHALL ALSO NOTIFY LOCAL WATER AND SEWER AUTHORITIES TO MARK OUT THEIR SYSTEMS.
- 25. THE CONTRACTOR SHALL COMPLETELY FILL BELOW-GRADE AREAS AND VOIDS RESULTING FROM THE DEMOLITION OF STRUCTURES AND FOUNDATIONS WITH SOIL MATERIALS CONSISTING OF STONE, GRAVEL, AND SAND, FREE FROM DEBRIS, TRASH, FROZEN MATERIALS, ROOTS, AND OTHER ORGANIC MATTER. STONES SHALL NOT BE LARGER THAN 6 INCHES IN ANY DIMENSION. DEMOLITION MATERIALS MAY NOT BE USED AS FILL. FILL MATERIALS SHALL BE PLACED IN HORIZONTAL LAYERS NOT EXCEEDING 6 INCHES IN LOOSE DEPTH CONTOURS AND TO PROVIDE SURFACE DRAINAGE.
- 26. ALL DEBRIS, RUBBISH, SALVAGE, HAZARDOUS AND COMBUSTIBLE MATERIALS SHALL BE REMOVED AT THE EARLIEST POSSIBLE TIME. REMOVED MATERIALS MAY NOT BE STORED, SOLD, OR BURNED ON SITE. HAZARDOUS AND COMBUSTIBLE MATERIALS SHALL BE REMOVED IN ACCORDANCE WITH PROCEDURES ADOPTED BY THE LOCAL FIRE DEPARTMENT AND OTHER JURISDICTIONAL AGENCIES.
- 27. NO PLANTINGS OR PRIVATE SIGNS ARE PERMITTED WITHIN THE COUNTY RIGHT OF WAY. CARE MUST BE TAKEN WHEN LOCATING PRIVATE SIGNS, BUILDINGS, STRUCTURES, PLANTINGS, BERMS, ETC. ALONGSIDE THE COUNTY RIGHT OF WAY SO AS TO NOT CREATE ANY NEW SIGHT OBSTRUCTIONS FOR THE COUNTY HIGHWAY (CSAH 51).


VAULT


LECEND

| LEGEND | | | |
|--------|----------------|----|---|
| | | | - EXISTING RIGHT-OF-WAY |
| | | | EXISTING PROPERTY LINE |
| X | x — x — | X | EXISTING FENCE |
| | VZ T | | EXISTING TELECOMMUNICATIONS |
| | © | | EXISTING SANITARY MANHOLE |
| | 0 | | EXISTING STORM MANHOLE |
| | 7 | | EXISTING ELECTRIC TRANSFORME |
| | \overline{G} | | EXISTING GAS METER |
| | E | | EXISTING ELECTRIC METER |
| | ₩ GV | | EXISTING GAS VALVE |
| | TH FH | | EXISTING FIRE HYDRANT |
| | . | | EXISTING LIGHT POLE |
| FP | FP | FP | EXISTING FLOOD PLAIN BOUNDARY |
| | ⋈ W∨ | | PROPOSED WATER VALVE |



AREA 'A'





PROPERTY:

CITY OF BLAINE

UNIT COUNT:

EX. TO REMAIN:

TOTAL NEW:

24' x 40':

TOTAL:

13' x 42':

13' x 82':

50 113TH AVENUE NE

ANOKA COUNTY, MN 55434

PARCEL ID: 18-31-23-22-0001

AREA: 4,660,920 SF (107 AC.)

18-31-23-23-0001

18-31-23-32-0001

18-31-23-32-0002

STORM SHELTER SCHEDULE

STORM SHELTER CALCULATIONS: MINNESOTA RULES 1370 SPACE REQUIREMENTS:

MINIMUM 4 SQUARE FEET PER PARK RESIDENT.

STORM SHELTER SPACE REQ: 1600 x 4 SF / PERSON

1600 PERSONS

= 6,400 SF

TOTAL COMBINED AREA:

PARK RESIDENTS:

ZONING USE: R-4 (MANUFACTURED HOMES)

572

580

15 30

GRAPHIC SCALE: 1" = 30' PROJECT 029-014 DATE 09/27/23 SCALE DRAWN

DESIGNED CHECKED KAL

1'' = 30'


AREA 'B'

GRADING NOTES:

- . SITE GRADING SHALL BE PERFORMED IN ACCORDANCE WITH THESE PLANS AND SPECIFICATIONS AND THE RECOMMENDATIONS SET FORTH IN THE SOILS REPORT REFERENCED IN THIS PLAN SET (IF ONE HAS BEEN PREPARED). THE CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING AND REPLACING ALL SOFT, YIELDING, OR UNSUITABLE MATERIALS AND REPLACING WITH SUITABLE MATERIALS AS SPECIFIED IN THE SOILS REPORT (IF ONE HAS BEEN PREPARED). ALL EXCAVATED OR FILLED AREAS SHALL BE COMPACTED TO 95% OF MODIFIED PROCTOR MAXIMUM DENSITY PER ASTM TEST D-1557. MOISTURE CONTENT AT THE TIME OF PLACEMENT SHALL NOT EXCEED 2% ABOVE NOR 3% BELOW OPTIMUM. CONTRACTOR SHALL SUBMIT A COMPACTION REPORT PREPARED BY A QUALIFIED SOILS ENGINEER, REGISTERED IN THE STATE IN WHICH THE WORK IS PERFORMED, VERIFYING THAT ALL FILLED AREAS AND SUBGRADE AREAS WITHIN THE BUILDING PAD AREA AND AREAS TO BE PAVED HAVE BEEN COMPACTED IN ACCORDANCE WITH THESE PLANS AND SPECS AND THE RECOMMENDATIONS SET FORTH IN THE SOILS REPORT.
- INTERNAL SITE GRADING SHALL NOT COMMENCE UNTIL ACHD ENGINEERING PLAN APPROVALS HAVE BEEN RECEIVED, AND ALL APPLICABLE PERMITS HAVE BEEN ISSUED BY ANOKA COUNTY AND ANY OTHER JURISDICTION HAVING
- CONTRACTOR IS RESPONSIBLE FOR VERIFICATION OF EXISTING TOPOGRAPHIC INFORMATION AND UTILITY INVERT ELEVATIONS PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION. CONTRACTOR TO ENSURE 0.75% MINIMUM SLOPE AGAINST ALL ISLANDS, GUTTERS, CURBS, AND MINIMUM 0.7% SLOPE ON ALL CONCRETE AND ASPHALT SURFACES TO PREVENT PONDING. ANY DISCREPANCIES THAT MAY AFFECT THE PUBLIC SAFETY OF PROJECT COST MUST BE IDENTIFIED TO THE ENGINEER IN WRITING IMMEDIATELY. PROCEEDING WITH CONSTRUCTION WITH KNOWN DESIGN TOLERANCE DISCREPANCIES SHALL BE AT THE CONTRACTOR'S RISK.
- . SUBBASE MATERIAL FOR SIDEWALKS, CURB, OR ASPHALT SHALL BE FREE OF ORGANICS AND OTHER UNSUITABLE MATERIALS. SHOULD SUBBASE BE DEEMED UNSUITABLE, SUBBASE IS TO BE REMOVED AND FILLED WITH APPROVED FILL MATERIAL COMPACTED TO 95% OPTIMUM DENSITY, AS DETERMINED BY MODIFIED PROCTOR METHOD.
- 5. IN CASE OF DISCREPANCIES BETWEEN THE PLANS, THE SITE PLAN SHALL SUPERSEDE. CONTRACTOR SHALL NOTIFY ENGINEER OF ANY CONFLICT IMMEDIATELY.
- . MAXIMUM CROSS-SLOPE OF 2.0% ON ALL SIDEWALKS, ACCESSIBLE PARKING SPACES, ACCESSIBLE ROUTES, AND ACCESSIBLE STRIPING AREAS.
- COUNTY DITCH #39 RUNS THROUGH THE MIDDLE OF THE PARK OF FOUR SEASONS PROPERTY AND MAY NOT BE ALTERED WITHOUT SUBMITTING PLANS AND OBTAINING NECESSARY APPROVALS.
- 8. OWNER SHALL RETAIN A QUALIFIED GEOTECHNICAL ENGINEER TO TEST PERMEABILITY AND PROVIDE CONSTRUCTION PHASE INSPECTIONS OF BASIN BOTTOM MATERIALS, INCLUDING INFILTRATION AND RETENTION BASINS. CONTRACTOR SHALL REMOVE UNSUITABLE OR OVERLY COMPACT SOIL OR ROCK MATERIAL AS NEEDED TO ACHIEVE REQUIRED PERMEABILITY AS DIRECTED BY THE OWNER'S GEOTECHNICAL ENGINEER, AND PLACED FILL SHALL HAVE A PERMEABILITY GREATER THAN OR EQUAL TO DESIGN CRITERIA.
- 9. CONTRACTOR SHALL BE RESPONSIBLE FOR CONTACTING THE OWNER'S GEOTECHNICAL ENGINEER PRIOR TO CONSTRUCTION TO CONFIRM MEANS, METHODS, AND MATERIALS, AND TO SCHEDULE REQUIRED INSPECTIONS.
- 10. CONTRACTOR IS RESPONSIBLE FOR AS-BUILT PLANS AND GRADE CONTROL UNLESS OTHERWISE SPECIFIED IN THE CONTRACT DOCUMENTS.
- 11. PERMANENT SEEDING TO BE IN ACCORDANCE WITH LOCAL AND STATE EROSION AND SEDIMENT CONTROL STANDARDS.
- 12. REFER TO SITE PLAN NOTES FOR ADDITIONAL NOTES.

LANDSCAPING NOTES:

- 1. ONE (1) OVERSTORY (SHADE) TREE IS PROPOSED PER PROPOSED MOBILE HOME LOT. 8 TOTAL TREES ARE PROPOSED.
- 2. ALL DISTURBED AREAS, EXCEPT FOR THE AREAS USED FOR THE MOBILE HOME, PATIOS, SIDEWALKS, AND OFF-STREET PARKING AREAS SHALL BE SODDED AND MAINTAINED WITH GRASS.




EVERGREEN/DECIDUOUS PLANTING DETAIL

FLOODPLAIN VOLUME SUMMARY:


| IMPACT AREA (SQ. FT.) | CUT (CU. YD.) | FILL (CU. YD.) | NET (CU. YD.) |
|--------------------------|---------------|----------------|--------------------|
| 1,000 | 0.00 | 6.80 | 6.80 <fill></fill> |


LECEND

| LEGEND | | | |
|--------|------------------------------------|----|---|
| | | | EXISTING RIGHT-OF-WAY |
| | | | EXISTING PROPERTY LINE |
| x | - x x - | x | EXISTING FENCE |
| | 100 | | EXISTING CONTOUR LINE - MAJOR |
| | — — <i>122</i> — — | | EXISTING CONTOUR LINE - MINOR |
| FP | FP | FP | EXISTING FLOOD PLAIN BOUNDARY |
| | VZ T | | EXISTING TELECOMMUNICATIONS VAULT |
| | © | | EXISTING SANITARY MANHOLE |
| | Ø | | EXISTING STORM MANHOLE |
| | \mathcal{T} | | EXISTING ELECTRIC TRANSFORMER |
| | G E | | EXISTING GAS METER |
| | E | | EXISTING ELECTRIC METER |
| | $\bowtie GV$ | | EXISTING GAS VALVE |
| | TH FH | | EXISTING FIRE HYDRANT |
| | \(\frac{\dagger}{\dagger}\) | | EXISTING LIGHT POLE |
| | + 100.25 | | EXISTING SPOT ELEVATION |
| | ₩WV | | PROPOSED WATER VALVE |
| | • 373.62 | | PROPOSED SPOT ELEVATION |
| | 120 | | PROP. CONTOUR - MAJOR |
| | 111 | | PROP. CONTOUR - MINOR |



AREA 'A'





SUGGESTED CONSTRUCTION SEQUENCING (note to designer: edit as needed to meet project requirements)

1. Install appropriate temporary erosion control devices to prevent sediment from leaving or entering the practice during construction.

2. All down-gradient perimeter sediment control bmp's must be in place before any up gradient land disturbing activity begins.

3. Perform continuous inspections of erosion control practices, especially after each rainfall event.


4. Install all utilities (water, sanitary sewer, electric, natural gas, phone, fiber optic, etc) prior to setting final grade of bioretention device.

5. Rough grade the site. If bioretention areas are being used as temporary sediment basins during construction, leave a minimum of 1 feet of cover over the practice to protect the underlying soils

- 6. Complete, stabilize, and vegetate all other site improvements.
 7. Construct and vegetate bioretention device following stabilization of contributing drainage area. Ensure that critical elevations, such as underdrain invert, top of media, top of mulch, and invert of overflow structure (if present) are correct.
 8. Remove temporary erosion control devices after the contributing drainage area is adequately vegetated.
- GENERAL NOTES (note to designer: edit as needed to meet project requirements)

 1. In the event that sediment is introduced into the bmp during or immediately following excavation, this material shall be removed from the practice prior to continuing construction.

 2. See Minnesota Stormwater Manual for subgrade preparation.
- MATERIAL SPECIFICATIONS
 1. See Minnesota Stormwater Manual for material specifications recommendations for bioretention soil, mulch, underdrains, etc.




SUGGESTED CONSTRUCTION SEQUENCING (note to designer: edit as needed to meet project requirements,

Install all utilities (water, sanitary sewer, electric, natural gas, phone, fiber optic, etc) prior to setting 5. Rough grade the site. If bioretention areas are being used as temporary sediment basins during construction, leave a minimum of 1 feet of cover over the practice to protect the underlying s

GENERAL NOTES (note to designer: edit as needed to meet project requirements)
1. In the event that sediment is introduced into the bmp during or immediately following excavation, this material shall be removed from the practice prior to continuing construction.
2. See Minnesota Stormwater Manual for subgrade preparation.

MATERIAL SPECIFICATIONS

1. See Minnesota Stormwater Manual for material specifications recommendations for bioretention soil, mulch, underdrains, etc.



√ Bioinfiltration Not To Scale

| | | LOT LANDSCAPE PLANT | SCHEDULE | | |
|--------|--------|---|--------------|-------|----------|
| TREES | ; | | | | |
| CODE | QTY | BOTANICAL /COMMON NAME | SIZE | CONT. | NOTES |
| GT | 8 | GLEDITSIA TRIACANTHOS VAR INERMIS HONEY LOCUST | 2" CAL | 888 | |
| | | BIORETENTION AREAS PLAI | NT SCHEDU | LE | |
| SHRUE | 38 | | | | |
| CODE | QTY | BOTANICAL /COMMON NAME | SIZE | CONT. | NOTES |
| АМ | 17 | ARONIA MELANOCARPA BLACK CHOKEBERRY | 24" MIN HT | #5 | |
| CA | 17 | CORNUS AMOMUM SILKY DOGWOOD | 24" MIN HT | #3 | |
| IW | 17 | ILEX VERTICILLATA WINTERBERRY | 24" MIN. HT. | #5 | |
| TOTAL | 51 | | | | |
| PEREN | INIALS | & GRASSES | | | |
| CODE | QTY | BOTANICAL /COMMON NAME | SIZE | CONT. | NOTES |
| ٨ | 76 | ASTER LAEVIS SMOOTH ASTER | PLUG | FLAT | 12" O.C. |
| L | 34 | LOBELIA CARDINALIS CARDINAL FLOWER | PLUG | FLAT | 18" O.C. |
| R | 30 | RUDBECKIA SUBTOMENTOSA SWEET CONEFLOWER | PLUG | FLAT | 24" O.C. |
| | 68 | SCHIZACHYRIUM SCOPARIUM LITTLE BLUESTEM | PLUG | FLAT | 18" O.C. |
| 5 | | | | _ | |
| s v | 76 | VERBENA HASTATA BLUE VERVAIN | PLUG | FLAT | 12" O.C. |

GRAPHIC SCALE: 1" = 30' PROJECT 029-014 DATE 09/27/23 SCALE DRAWN 1'' = 30'DESIGNED CHECKED KAL

SHEET

Not To Scale Remove temporary erosion control devices after the contributing drainage area is adequately vegetated.

15 30

UTILITY NOTES:

LEGEND

EXISTING RIGHT-OF-WAY

EXISTING PROPERTY LINE

- EXISTING GAS SERVICE

EXISTING STORM PIPE

EXISTING GAS METER EXISTING ELECTRIC METER EXISTING STORM MANHOLE EXISTING GAS VALVE EXISTING FIRE HYDRANT EXISTING LIGHT POLE PROP. CONTOUR - MAJOR PROP. CONTOUR - MINOR PROPOSED WATER SERVICE

- PROPOSED WATER LATERAL PROPOSED WATER VALVE

EXISTING UNDERGROUND ELECTRIC


EXISTING CABLE / COMMS WIRE EXISTING DOMESTIC WATER SERVICE


EXISTING FLOOD PLAIN BOUNDARY EXISTING TELECOMMUNICATIONS VAULT


EXISTING SANITARY MANHOLE EXISTING ELECTRIC TRANSFORMER


EXISTING FENCE

- 1. CONTRACTOR TO LOCATE AND UTILIZE EXISTING WATER SERVICE CONNECTION IF FEASIBLE.
- 2. NEW WATER SERVICE LOCATIONS SHALL BE COORDINATED WITH THE CITY OF BLAINE DEPARTMENT OF PUBLIC WORKS. 3. CONTRACTOR IS RESPONSIBLE FOR ALL REQUIRED STREET OPENING PERMITS FOR REMOVAL OF EXISTING WATER
- SERVICES AND/OR INSTALLATION OF NEW WATER SERVICES.
- 4. NEW GAS SERVICE LOCATIONS SHALL BE COORDINATED WITH THE LOCAL GAS COMPANY. 5. CONTRACTOR IS RESPONSIBLE FOR ALL REQUIRED STREET OPENING PERMITS FOR REMOVAL OF EXISTING GAS
- SERVICES AND/OR INSTALLATION OF NEW GAS SERVICES. 6. NEW SANITARY SEWER SERVICE LOCATIONS SHALL BE COORDINATED WITH THE CITY OF BLAINE DEPARTMENT OF PUBLIC WORKS.
- 7. CONTRACTOR IS RESPONSIBLE FOR ALL REQUIRED STREET OPENING PERMITS FOR REMOVAL OF EXISTING SANITARY SEWER SERVICES AND/OR INSTALLATION OF NEW SANITARY SEWER SERVICES.
- LOCATION OF ALL EXISTING AND PROPOSED SERVICES, INCLUDING BUT NOT LIMITED TO SANITARY, WATER, ELECTRIC, STORM, GAS, AND TELECOMMUNICATIONS, ARE APPROXIMATE AND MUST BE CONFIRMED INDEPENDENTLY WITH LOCAL UTILITY AGENCIES AND AUTHORITIES PRIOR TO ANY CONSTRUCTION OR EXCAVATION. ANY DISCREPANCY SHALL BE REPORTED IMMEDIATELY IN WRITING TO THE ENGINEER.
- 9. CONSTRUCTION OF SANITARY AND STORM FACILITIES SHALL BEGIN AT THE LOWEST ELEVATION (POINT OF CONNECTION) AND PROGRESS UP GRADIENT. PROPOSED CROSSINGS WITH EXISTING UTILITIES SHALL BE FIELD VERIFIED BY TEST PIT PRIOR TO COMMENCEMENT OF CONSTRUCTION.
- 10. CONTRACTOR IS RESPONSIBLE TO NOTIFY DIG SAFE 811 AT LEAST SEVENTY-TWO (72) HOURS PRIOR TO ANY EXCAVATION ON SITE. CONTRACTOR SHALL ALSO NOTIFY LOCAL UTILITY AGENCIES AND AUTHORITIES TO MARK OUT FACILITIES PRIOR TO EXCAVATION.
- 11. ALL PROPOSED UTILITIES TO BE INSTALLED UNDERGROUND UNLESS OTHERWISE SPECIFIED.
- 12. ALL SEWER AND WATER FACILITIES SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE SPECIFICATIONS OF THE CITY OF BLAINE DEPARTMENT OF PUBLIC WORKS.
- 13. WATER SERVICE MATERIALS SHALL BE SPECIFIED BY THE LOCAL WATER UTILITY. ENGINEER IS NOT RESPONSIBLE FOR THE COSTS ASSOCIATED WITH FEES AND APPURTENANCES REQUIRED BY THE LOCAL WATER UTILITY.
- 14. SANITARY SEWER MAINS SHALL BE SEPARATED FROM WATER MAINS BY AT LEAST TEN (10) FEET HORIZONTALLY. WHERE SUCH SEPARATION IS NOT POSSIBLE, SEWER AND WATER MAINS SHALL BE IN SEPARATE TRENCHES, WITH THE SEWER MAIN AT LEAST EIGHTEEN (18) INCHES BELOW THE WATER MAIN.
- 15. ALL SEWER PIPE INSTALLED WITH LESS THAN THREE (3) FEET OF COVER, GREATER THAN TWENTY (20) FEET OF COVER, OR WITHIN EIGHTEEN (18) INCHES OF A WATER MAIN SHALL BE CONSTRUCTED OF DUCTILE IRON PIPE, UNLESS OTHERWISE SPECIFIED.
- 16. WHERE SANITARY SEWER LATERAL CONNECTIONS ARE GREATER THAN TEN (10) FEET DEEP AT THE POINT OF CONNECTION TO THE MAIN, A CONCRETE DROP MANHOLE SHALL BE USED.
- 17. GAS, ELECTRIC, AND TELECOMMUNICATIONS LINES LOCATED HEREON ARE APPROXIMATE. ACTUAL LOCATION AND LAYOUT FOR GAS, ELECTRIC, AND TELECOMMUNICATIONS SHALL BE AT THE DIRECTION OF THE APPROPRIATE
- 18. MEANS, METHODS, AND MATERIALS SHALL BE DONE IN ACCORDANCE WITH THE OWNER'S SPECIFICATIONS. IF SAID SPECIFICATIONS DO NOT EXIST, ALL MEANS, METHODS, AND MATERIALS SHALL BE PROVIDED CONSISTENT WITH ACCEPTED INDUSTRY STANDARDS.











10801 Town Square Drive NE, Blaine, Minnesota 55449 763-785-6172 Fax 763-785-6139

CASTING SHALL BE MARKED SANITARY OR CO (CLEAN OUT)









City of Blaine - Engineering Department


10801 Town Square Drive NE. Blaine, Minnesota 55449 763-785-6172 Fax 763-785-6139



City of Blaine - Engineering Department


10801 Town Square Drive NE, Blaine, Minnesota 55449 763-785-6172 Fax 763-785-6139






NOTE: PAVEMENT SECTION TO MATCH, AT MINIMUM, ADJOINING

WATER AND SANITARY SEWER SERVICE TRENCH DETAIL







SHEET

CONTRACTOR IS RESPONSIBLE FOR VERIFICATION OF LOCAL REQUIRED DETAILS TO COMPLETE THE

IN CASE OF DISCREPANCIES BETWEEN THE PLAN DETAILS AND LOCAL REQUIRED DETAILS, THE LOCAL REQUIRED DETAILS SHALL SUPERSEDE. CONTRACTOR SHALL NOTIFY ENGINEER OF ANY CONFLICT IF

ANY DETAILS NEEDED FOR BIDDING AND/OR CONSTRUCTION OF THIS JOB, SHOWN OR NOT SHOWN ON THESE PLANS, ARE TO BE IN ACCORDANCE WITH LOCAL MUNICIPAL, COUNTY, STATE, AND FEDERAL REGULATIONS AND STANDARDS. IF ANY DETAIL SHOWN ON THESE PLANS DOES NOT MEET THESE STANDARDS, IT IS THE CONTRACTORS' RESPONSIBILITY TO BID AND/OR CONSTRUCT THE APPROPRIATE





City of Blaine - Engineering Department

10801 Town Square Drive NE, Blaine, Minnesota 55449 763-785-6172 Fax 763-785-6139

GENERAL DETAIL NOTE:

ALL DETAILS SHOWN ON THESE PLANS ARE FOR REFERENCE ONLY

DETAILS TO BE "OR EQUIVALENT".

REFER TO PREVIOUS SHEETS FOR ADDITIONAL NOTES.

SOIL EROSION AND SEDIMENT CONTROL NOTES:

- 1. ALL SOIL EROSION AND SEDIMENT CONTROL PRACTICES WILL BE INSTALLED IN ACCORDANCE WITH THE STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL IN MINNESOTA, AND WILL BE IN PLACE PRIOR TO ANY MAJOR SOIL DISTURBANCE OR IN THEIR PROPER SEQUENCE AND MAINTAINED UNTIL PERMANENT PROTECTION IS ESTABLISHED.
- ANY DISTURBED AREA THAT WILL BE LEFT EXPOSED FOR MORE THAN FOURTEEN (14) DAYS AND NOT SUBJECT TO CONSTRUCTION TRAFFIC SHALL IMMEDIATELY RECEIVE A TEMPORARY SEEDING. IF THE SEASON PROHIBITS TEMPORARY SEEDING, THE DISTURBED AREAS WILL BE MULCHED WITH STRAW OR HAY AND TACKED IN ACCORDANCE WITH THE MINNESOTA STANDARDS.
- 3. SEED MIXTURE TO BE PLANTED IS "OATS ONE YEAR COVER CROP (MAY AUGUST)" AND/OR "WINTER WHEAT ONE YEAR COVER CROP (AUGUST - OCTOBER)" PER THE MINNESOTA STORMWATER MANUAL TEMPORARY SEEDING AND STABILIZATION PAGE, OR APPROVED EQUAL. THE QUANTITY TO BE PLANTED FOR EACH IN THE PROJECT AREA OF APPROXIMATELY 1.11 ACRES IS IS APPROXIMATELY 111 LBS, PER THE LISTED PLANTING RATE OF 100 LBS PER ACRE.
- . PERMANENT VEGETATION IS TO BE ESTABLISHED ON EXPOSED AREAS AFTER FINAL GRADING. MULCH IS TO BE USED FOR PROTECTION UNTIL VEGETATION IS ESTABLISHED.
- 5. IMMEDIATELY FOLLOWING INITIAL DISTURBANCE OR ROUGH GRADING ALL CRITICAL AREAS (STEEP SLOPES, SANDY SOILS, WET CONDITIONS) SUBJECT TO EROSION WILL RECEIVE A TEMPORARY SEEDING.
- 6. PERMANENT SEEDING AND STABILIZATION TO BE IN ACCORDANCE WITH THE "EROSION PREVENTION PRACTICES -TEMPORARY SEEDING AND STABILIZATION" CHAPTER OF THE MINNESOTA STORMWATER MANUAL.
- 7. ALL SEDIMENTATION STRUCTURES WILL BE INSPECTED AND MAINTAINED FREQUENTLY AND REPLACEMENTS OR REPAIR SHALL BE MADE PROMPTLY AS NEEDED.
- 8. STOCKPILES SHOULD BE SITUATED SO AS NOT TO OBSTRUCT NATURAL DRAINAGE OR CAUSE OFF-SITE ENVIRONMENTAL
- 9. DURING AND AFTER CONSTRUCTION, THE APPLICANT WILL BE RESPONSIBLE FOR THE MAINTENANCE AND UPKEEP OF THE DRAINAGE STRUCTURES, VEGETATION COVER, AND ANY OTHER MEASURES DEEMED APPROPRIATE BY THE MINNESOTA POLLUTION CONTROL AGENCY. SAID RESPONSIBILITY WILL END WHEN COMPLETED WORK IS APPROVED BY THE MINNESOTA POLLUTION CONTROL AGENCY.
- 10. REMOVE ANY SEDIMENT THAT MAY BE SPILLED, DROPPED, OR TRACKED OFF THE PROJECT SITE. ALL PAVED RIGHT-OF-WAYS ADJACENT TO THE PROJECT SITE MUST BE MAINTAINED IN A CLEAN, SWEPT CONDITION THROUGHOUT CONSTRUCTION. INSTALL CRUSHED STONE PAD(S) TO HELP REDUCE OFF-SITE TRACKING OF SEDIMENT.
- 11. THE PROPERTY OWNER SHALL BE RESPONSIBLE FOR ANY EROSION OR SEDIMENTATION THAT MAY OCCUR BELOW STORMWATER OUTFALLS OR OFFSITE AS A RESULT OF CONSTRUCTION OF THE PROJECT.
- 12. IN THE CASE OF EXCESS SEDIMENT RUNOFF FROM THE SITE, THE CONTRACTOR SHALL INSTALL INLET PROTECTION AT THE DOWNSTREAM INLET.
- 13. THE CONSTRUCTION EXIT/ENTRANCE IS PROPOSED TO BE 10' WIDE AND 50' LONG, WITH 5' RADII TO 113TH CIR NE. THE CONSTRUCTION EXIT/ENTRANCE SHALL BE COMPOSED OF 1.5" TO 3" ROCKS, AND SHALL HAVE A DEPTH OF 6" WITH A FILTER FABRIC UNDER-LINER BELOW THE ROCKS. OTHER MINNESOTA APPROVED VEHICLE TRACKING BMP'S ARE ACCEPTABLE AS NEEDED.

SEQUENCE OF CONSTRUCTION:

- 1. INSTALL EROSION AND SEDIMENTATION CONTROLS.
- 2. DEMOLISH EXISTING FEATURES AS MARKED.
- 3. DEMOLISH UTILITIES IDENTIFIED AS "TO BE REMOVED."
- 4. ROUGH GRADE AREAS TO BE IMPROVED.
- INSTALL UTILITIES AS SHOWN.
- 6. CONSTRUCT CONCRETE PAD FOUNDATIONS.
- 7. INSTALL SUBBASE AND BASE COURSE OF DRIVEWAYS AND PARKING AREAS.
- 8. FINISH GRADE SITE. INSTALL SURFACE COURSE OF PAVEMENT.
- 9. REPLAT TOPSOIL. STABILIZE AND SEED EXPOSED AREAS.
- 10. REMOVE EROSION AND SEDIMENT CONTROLS.

NOTE:

LEGEND

TO FH

8-CFS ------- 8-CFS ------- 8-CFS ------- PROPOSED COMPOST FILTER SOCK 8"

TP TP TP TP TP PROPOSED TREE PROTECTION

THE EXISTENCE AND LOCATION OF ANY OVERHEAD OR UNDERGROUND UTILITY LINES, PIPES, OR STRUCTURES SHOWN ON THESE PLANS ARE OBTAINED BY A RESEARCH OF THE AVAILABLE RECORDS. EXISTING UTILITIES ARE LOCATED ON PLANS ONLY FOR THE CONVENIENCE OF THE CONTRACTOR. EXISTING UTILITY SERVICE LATERALS MAY NOT BE SHOWN ON THE PLANS. THE CONTRACTOR SHALL, AT HIS OWN EXPENSE, LOCATE ALL UNDERGROUND AND OVERHEAD INTERFERENCE'S WHICH MAY AFFECT HIS OPERATION DURING CONSTRUCTION AND SHALL TAKE ALL NECESSARY PRECAUTIONS TO AVOID DAMAGE TO THE SAME. THE CONTRACTOR SHALL USE EXTREME CAUTION WHEN WORKING NEAR GAS LINES OR OVERHEAD UTILITIES SO AS TO SAFELY PROTECT ALL PERSONNEL AND EQUIPMENT, AND SHALL BE RESPONSIBLE FOR ALL COST AND LIABILITY IN CONNECTION THEREWITH.

— EXISTING RIGHT-OF-WAY

EXISTING PROPERTY LINE

EXISTING GAS SERVICE

EXISTING GAS METER EXISTING ELECTRIC METER EXISTING GAS VALVE

EXISTING FIRE HYDRANT EXISTING LIGHT POLE PROP. CONTOUR - MAJOR PROP. CONTOUR - MINOR PROPOSED WATER SERVICE PROPOSED WATER LATERAL PROPOSED WATER VALVE

EXISTING SANITARY PIPE EXISTING STORM PIPE

EXISTING UNDERGROUND ELECTRIC

EXISTING DOMESTIC WATER SERVICE


EXISTING FLOOD PLAIN BOUNDARY EXISTING TELECOMMUNICATIONS VAULT

EXISTING ELECTRIC TRANSFORMER


EXISTING SANITARY MANHOLE EXISTING STORM MANHOLE

EXISTING CABLE / COMMS WIRE


EXISTING FENCE




AREA 'A'



AREA 'B'








PROJECT 029-014 DATE 09/27/23


SCALE DRAWN 1'' = 30'

DESIGNED CHECKED









NOTES:

GENERAL DETAIL NOTE:

2. DETAILS TO BE "OR EQUIVALENT".

1. ALL DETAILS SHOWN ON THESE PLANS ARE FOR REFERENCE ONLY.

1. PLACE STOCKPILES AT LOCATIONS AS SHOWN ON THE SOIL EROSION ANS SEDIMENT CONTROL PLAN.

2. HEIGHT SHALL NOT EXCEED 35 FEET. ALL SIDE SLOPES SHALL BE 2 TO 1

3. STOCKPILE SHALL RECEIVE A VEGETATIVE COVER IN ACCORDANCE WITH MINIMUM STABILIZATION REQUIREMENTS TO MINIMIZE EROSION.

4. COMPOST FILTER SOCK SHALL BE INSTALLED AS DETAILED HEREON. 5. LOCATION OF PROPOSED STOCKPILE WHICH AFFECT EROSION CONTROLS ARE SHOWN SCHEMATICALLY ONLY. ACTUALLY STOCKPILE LOCATION MAY CHANGE DURING CONSTRUCTION.

6. SEE SEQUENCE OF CONSTRUCTION NOTES.

MAINTENANCE AND INSPECTION
7. INSPECT STOCKPILES REGULARLY, ESPECIALLY AFTER LARGE STORMS. STABILIZE ANY AREAS THAT HAVE ERODED.


STOCKPILE DETAIL


PROJECT 029-014 DATE 09/27/23 SCALE DRAWN DESIGNED CHECKED

CONTRACTOR IS RESPONSIBLE FOR VERIFICATION OF LOCAL REQUIRED DETAILS TO COMPLETE THE 4. IN CASE OF DISCREPANCIES BETWEEN THE PLAN DETAILS AND LOCAL REQUIRED DETAILS, THE LOCAL REQUIRED DETAILS SHALL SUPERSEDE. CONTRACTOR SHALL NOTIFY ENGINEER OF ANY CONFLICT IF

5. REFER TO PREVIOUS SHEETS FOR ADDITIONAL NOTES. ANY DETAILS NEEDED FOR BIDDING AND/OR CONSTRUCTION OF THIS JOB, SHOWN OR NOT SHOWN ON THESE PLANS, ARE TO BE IN ACCORDANCE WITH LOCAL MUNICIPAL, COUNTY, STATE, AND FEDERAL REGULATIONS AND STANDARDS. IF ANY DETAIL SHOWN ON THESE PLANS DOES NOT MEET THESE STANDARDS, IT IS THE CONTRACTORS' RESPONSIBILITY TO BID AND/OR CONSTRUCT THE APPROPRIATE STANDARD DETAILS.







COON CREEK WATERSHED DISTRICT Request for Board Action

MEETING DATE: August 12, 2024

AGENDA NUMBER: 17

ITEM: Rough Draft 2025 Budget

AGENDA: Discussion

ACTION REQUESTED

1. Review, comment, and correct budget

2. Forward budget to Draft status for review at the August 14 meeting for review by the Advisory committees

PURPOSE AND SCOPE

1) To review a preliminary rough draft of the 2025 operating budget

BACKGROUND

In March the Board adopted a calendar and process for developing the 2025 budget. The process involves three phases: analysis of the parts, fine-tuning of the whole, and review and adoption of the final.

Attached is the first draft of the entire budget and the start of phase 2 of the budget process: Fine Tuning.

| Revenues | 2022 Actual | 2023 Actual | 2024 Budget | 2024 Projected | 2025 Prelim | % Chg |
|----------------------------|-------------|-------------|-------------|----------------|-------------|-------|
| Fund Balance January 1 | 2,304,676 | 1,958,079 | 1,591,018 | 1,591,018 | 1,550,793 | |
| | | | | | | |
| Property Tax | 3,027,370 | 3,187,821 | 4,965,765 | 4,965,765 | 6,207,206 | 25.0% |
| Fees & Charges | 253,820 | 530,203 | 298,423 | 298,423 | 298,423 | |
| Grants & Intergovernmental | 638,274 | 399,031 | 314,539 | 314,539 | 2,566,549 | |
| Other Revenue | 25,926 | 26,963 | 28,042 | 28,042 | 115,000 | |
| Fund Balance Used | 387,302 | 342,274 | 40,225 | 40,225 | 40,225 | |
| | 4,332,692 | 4,486,292 | 5,646,994 | 5,646,994 | 9,227,403 | |
| Total Funds Available | 6,250,066 | 6,102,097 | 7,197,787 | 7,197,787 | 10,737,971 | |
| Expenditures | | | | | | |
| Salaries & Benefits | 1,499,948 | 1,772,946 | 1,981,605 | 1,981,605 | 2,414,928 | |
| Professional Services | 939,376 | 363,632 | 589,000 | 589,000 | 489,487 | |
| Operating Expenses | 188,296 | 204,221 | 239,164 | 239,164 | 317,242 | |
| Program Costs | 1,277,544 | 2,196,554 | 2,680,517 | 2,680,517 | 5,789,607 | |
| Capital Costs | 9,600 | 31,395 | 156,708 | 156,708 | 198,174 | |
| | 3,914,764 | 4,568,748 | 5,646,994 | 5,646,994 | 9,209,437 | |
| Fund Balance December 31 | 2,335,302 | 1,533,349 | 1,550,793 | 1,550,793 | 1,528,534 | |
| Rev - Exp | 417,928 | (82,456) | - | - | 17,966 | |

ISSUES/CONCERNS/OPPORTUNITIES

- 1. <u>Initial Proposed Levy Amount</u>: The levy increase used to balance the preliminary draft is 25%.
- 2. <u>Technical Advisory Committee Comments</u>: The TAC met Thursday August 8. The DRAFT 2025 Budget was on the agenda. The comments will be shared at the Board meeting.
- 3. <u>Citizen Advisory Committee</u>: The next Citizen Advisory Committee meeting is scheduled for Wednesday, August 14. CAC comments will be included in the August 26 Board meeting.
- 4. Next Steps: This draft serves to end phase 2 (the review and correct phase) of the budget process and will serve as the Draft used during phase 3 (the review correct and refinement stage) of the annual Budget process. Phase 3 occurs during August with review by the District's Advisory Committees and ends with approval of the Draft Budget and Notice of Public Hearing and adoption at the September 9 Board meeting.

IMPLICATIONS

- The budget as proposed allows
 - o The District to maintain services and address the water quality issues.
 - o Establish an employee benefit package that allows the District to attract and retain the required talent pool.
- Any comments or corrections made tonight will be
 - o Reviewed by the CAC Wednesday
 - o Included in the Draft budget discussed on August 26.

CONCLUSIONS

The budget is a draft and requires discussion

RECOMMENDATION

- 1) Approve Distribution of this draft for Review by the Technical Advisory Committee at their August
- 2) Forward budget to Draft status for review at the August 12 meeting for review by the Advisory committees

Proposed Revenues

| | Prepared | 2021 | 2022 | 2023 | 20 | 24 | | 2025 | | Change |
|-------|-----------------------------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|--------|
| Code | 8/6/2024 12:22 | Actual | Actual | Actual | Budget | Projected | Current | Change | Request | 24-25 |
| | | | | | | | | | | |
| | Property Taxes | | | | | | | | | |
| 41101 | Administrative Levy | | | | | | | | | |
| 41102 | Insurance Levy | | | | | | | | | |
| 41103 | MWMA Levy | 2,577,244 | 2,691,777 | 3,027,370 | 4,965,765 | 4,965,765 | 4,965,765 | 1,241,441 | 6,207,206 | 25.00% |
| 41104 | Survey & Data Levy | | | | | | | | | |
| 41105 | Maintenance Levy | | | | | | | | | |
| | Total Property Taxes | 2,577,244 | 2,691,777 | 3,027,370 | 4,965,765 | 4,965,765 | 4,965,765 | 1,241,441 | 6,207,206 | 25.00% |
| | | | | | | | | | | |
| | Fees & Charges | | | | | | | | | |
| | Application Fees | 1,750 | 1,820 | 1,850 | 850 | 650 | 850 | - | 850 | |
| 53191 | Review & Inspect Fees | 262,500 | 420,966 | 550,368 | 297,500 | 218,400 | 285,600 | 11,973 | 297,573 | |
| | Total Fees | 264,250 | 422,786 | 552,218 | 298,350 | 219,050 | 286,450 | 11,973 | 298,423 | - |
| | Grants | | | | | | | | | |
| 55190 | EPA 319 Grant | | 21,000 | | | | | | _ | |
| 55190 | | | ,,,,, | | 23,135 | 23,135 | 23,135 | (12,459) | 10,676 | |
| 55190 | NKE Plan Impl 319 Grant | | | 32,071 | 160,353 | 160,353 | 160,353 | 128,300 | 288,653 | |
| 55190 | CCPSR CWF Grant | | 197,500 | 39,500 | | | | , | - | |
| 55190 | Aurelia Park CWF Grant | | 31,017 | 38,771 | | | | | _ | |
| 55190 | PCSIESF CWF Grant | | 132,000 | 33,000 | | | | | _ | |
| 55190 | | | 172,500 | 138,000 | 34,500 | 34,500 | | | _ | |
| 55190 | WBIF 41,60,57 Sub Plan | | 41,580 | 108,189 | 86,551 | 86,551 | | 86,551 | 86,551 | |
| 55190 | WCA Admin | 4,400 | 9,224 | 9,500 | 10,000 | 10,000 | | 12,000 | 12,000 | |
| 55190 | BWSR CWF WBIF Retro | , | - , | ., | -, | | | 178,000 | 178,000 | |
| 55190 | BWSR CWF WBIF (24) | | | | | | | 147,000 | 147,000 | |
| | Task Force Funding | | | | | | | | Ź | |
| | D17-SNBC Outlet Mod | | | | | | | 142,400 | 142,400 | |
| | PC-Pond Mod+ Blaine Basin | | | | | | | 618,284 | 618,284 | |
| | D39-Bridgewater SIESF | | | | | | | 1,082,985 | 1,082,985 | |
| | Total Grants | 4,400 | 604,821 | 399,031 | 314,539 | 314,539 | 183,488 | 2,383,061 | 2,566,549 | - |
| | | | | | | | | | | |
| | Other Revenue | | | | | | | | | |
| 56101 | Interest Income | 25,926 | 26,963 | 28,042 | 28,042 | 100,000 | 28,042 | 86,958 | 115,000 | |
| | Fund Balances & Other | | | | | | | | | |
| | Building | - | - | - | - | - | - | - | _ | |
| | AIS Rapid Response | 40,000 | 40,000 | 40,000 | 40,000 | 40,000 | 40,000 | - | 40,000 | |
| | Illicit Discharge Detection | 225 | 225 | 225 | 225 | 225 | 225 | - | 225 | |
| | Fund Equity Balance | 40,225 | 347,077 | 302,049 | - | - | - | - | - | |
| | Ditch Fund Balances | | | | | | | | | |
| | Ditch 54 | - | | | | _ | - | - | _ | |
| | Other Fund Balances | - | | | | | | | _ | |
| | Total Fund Balances | 80,450 | 387,302 | 342,274 | 40,225 | 40,225 | 40,225 | | 40,225 | |
| | Total Fully Datalices | 00,430 | 301,302 | 344,414 | 40,223 | 70,223 | 40,445 | - | 40,225 | |
| | TOTAL REVENUE | 2,952,270 | 4,133,649 | 4,348,935 | 5,646,921 | 5,639,579 | 5,503,970 | 3,723,433 | 9,227,403 | 0 |

Salaries & Benefits

| | Prepared | 2021 | 2022 | 2023 | 202 | 24 | | 2025 | | Change |
|-------|-----------------------------|-----------------|-----------------|-----------|-----------|-----------|-----------|---------|-----------|--------|
| Code | 8/6/2024 12:23 | Actual | Actual | Actual | Budget | Projected | Current | Change | Request | 24-25 |
| | | | | | | | | | | |
| | Salaries & Benefits | | | | | | | | | |
| 60110 | Salaries | \$ 1,333,723 | \$ 1,164,379 | 1,330,378 | 1,448,994 | 1,448,994 | 1,506,954 | 101,437 | 1,608,391 | 11% |
| 60260 | Temporary Salaries-Students | \$ 17,952 | \$ 17,129 | - | 39,000 | 39,000 | 40,560 | 1,789 | 42,349 | 9% |
| 60713 | HRA Payment | \$ 8,215 | \$ 6,762 | 14,466 | 15,117 | 15,117 | 15,722 | 146,878 | 162,600 | 976% |
| 60714 | Health Insurance | \$ 182,383 | \$ 121,640 | 208,094 | 235,020 | 235,020 | 244,421 | 69,579 | 314,000 | 34% |
| 60715 | Life Insurance | \$ 559 | \$ 300 | 512 | 526 | 526 | 547 | 2,213 | 2,760 | 425% |
| 60716 | Social Security (FICA) | \$ 101,372 | \$ 89,075 | 102,845 | 114,673 | 114,673 | 119,260 | 7,940 | 127,200 | 11% |
| 60717 | Retirement (PERA) | \$ 100,769 | \$ 84,418 | 96,674 | 107,880 | 107,880 | 112,195 | 7,483 | 119,679 | 11% |
| 60720 | Dental Insurance | \$ 7,805 | \$ 5,580 | 7,605 | 7,605 | 7,605 | 7,909 | 6,041 | 13,950 | 83% |
| 60721 | LTD Insurance | \$ 2,104 | \$ 1,048 | 1,422 | 1,790 | 1,790 | 1,862 | 10,138 | 12,000 | 570% |
| 60855 | Board & Advisory Expenses | \$ 10,050 | \$ 9,617 | 10,950 | 11,000 | 11,000 | 11,440 | 560 | 12,000 | 9% |
| | Total Salaries & Benefits | 1,764,932 | 1,499,948 | 1,772,946 | 1,981,605 | 1,981,605 | 2,060,869 | 354,059 | 2,414,928 | 22% |

Professional Services

| | | 2022 | 2023 | 2024 | | 2024 | 2025 | 2025 | | 2025 | |
|-------|----------------------|---------------|---------------|---------------|----|-----------|---------------|----------------|----|---------|-------|
| | Services | Actual | Actual | Budget | P | Projected | Current | Change |] | Request | |
| 63010 | GIS Services | \$ 104,837 | \$ 111,700 | \$ 117,286 | \$ | 116,900 | \$ 121,977 | \$ 17,134 | \$ | 139,111 | 19% |
| 63052 | Accounting/HR | \$ 5,050 | \$ 5,252 | \$ 5,252 | \$ | 75,000 | \$ 5,462 | \$ 98,783 | \$ | 104,245 | 1885% |
| 63052 | Audit | \$ 11,960 | \$ 12,438 | \$ 12,438 | \$ | 13,913 | \$ 12,936 | \$ 3,064 | \$ | 16,000 | 29% |
| 63066 | IT Services | \$ 47,250 | \$ 58,336 | \$ 58,336 | \$ | 64,790 | \$ 60,669 | \$ 20,362 | \$ | 81,031 | 39% |
| 63246 | Engineering Services | \$ 718,279 | \$ 143,758 | \$ 143,758 | \$ | 81,000 | \$ 149,508 | \$ (60,408) | \$ | 89,100 | -38% |
| 63453 | Legal Services | \$ 52,000 | \$ 54,080 | \$ 54,080 | \$ | 58,252 | \$ 56,243 | \$ 3,756 | \$ | 60,000 | 11% |
| | | \$ 939,376 | \$ 385,564 | \$ 391,150 | \$ | 409,855 | \$ 406,796 | \$ 82,691 | \$ | 489,487 | 25% |

Operating Costs

| | Prepared | 2021 | 2022 | 2023 | 20 | 24 | | 2025 | | Change |
|-------|--------------------------------------|---------|---------|---------|---------|-----------|---------|----------|---------|---------|
| Code | 8/6/2024 12:25 | Actual | Actual | Actual | Budget | Projected | Current | Change | Request | 24-25 |
| | Operating Expenses | | | | | | | | | |
| 61101 | Small Equipment (furn/off/comp/misc) | 47,641 | 23,505 | 18,020 | 37,203 | 37,203 | 38,691 | 809 | 39,500 | 6% |
| 61102 | Printing | - | - | - | 4,040 | 4,040 | 4,202 | (202) | 4,000 | -1% |
| 61105 | Cleaning & Janitorial Supp | 10,062 | 10,062 | 15,487 | 16,222 | 16,218 | 16,871 | (4) | 16,867 | 4% |
| 61110 | Gasoline/Oil/License | 15,025 | 15,025 | 16,377 | 17,377 | 16,377 | 18,072 | (2,072) | 16,000 | -8% |
| 61149 | Gen'l Supplies (office) | 18,914 | 18,914 | 19,031 | 20,033 | 12,993 | 20,834 | (10,203) | 10,632 | -47% |
| 61249 | R&M Phone Hardware | 68 | 3,000 | 2,350 | 3,450 | 3,000 | 3,588 | (538) | 3,050 | -12% |
| 61250 | R&M Buildings | 15,925 | 12,205 | 15,166 | 22,412 | 23,000 | 23,308 | 1,172 | 24,480 | 9% |
| 61251 | R&M Office Machine & Equip | 685 | 1,046 | 3,588 | 5,900 | - | 6,136 | 7,344 | 13,480 | 128% |
| 61263 | R&M Security | 1,000 | 1,030 | 1,071 | 1,125 | 1,171 | 1,170 | 1,495 | 2,665 | 137% |
| 61354 | Training & Conferences-Board/Other | 198 | 2,352 | 2,000 | 500 | 300 | 520 | (220) | 300 | -40% |
| 61355 | Training & Conferences-Staff Dev | 4,199 | 11,356 | 11,810 | 10,620 | 9,820 | 11,045 | 7,910 | 18,955 | 78% |
| 61475 | Mileage | 691 | 2,718 | 2,827 | 683 | 600 | 710 | (80) | 630 | -8% |
| 61476 | Other Travel Exp, Parking | 6 | 0 | 40 | 40 | 40 | 42 | (2) | 40 | 0% |
| 61477 | Meals & Staff Enrichment | 949 | 2,000 | 1,750 | 2,965 | 2,965 | 3,084 | 1,216 | 4,300 | 45% |
| 61552 | Bank Charges | 556 | 732 | 761 | 799 | 1,065 | 831 | 287 | 1,118 | 40% |
| 61557 | Dues & Memberships | 9,070 | 10,529 | 15,650 | 17,000 | 15,450 | 17,680 | 10,475 | 28,155 | 66% |
| 61558 | Advertising | 0 | 1,574 | 1,637 | 1,650 | 500 | 1,716 | (716) | 1,000 | -39% |
| 61559 | Subscriptions & Publications | 1,985 | 1,485 | 2,744 | 4,243 | 5,645 | 4,413 | 4,922 | 9,335 | 120% |
| 61575 | Books & Software | 7,765 | 7,765 | 18,498 | 33,558 | 33,558 | 34,900 | 6,883 | 41,784 | 25% |
| 61810 | Misc & Contingency | - | - | - | 0 | - | - | 1,750 | 1,750 | #DIV/0! |
| 62119 | Web Site Server | 960 | 889 | 1,000 | 1,995 | 1,930 | 2,075 | (185) | 1,890 | -5% |
| 62124 | Leases & Rentals | 6,078 | 5,594 | 5,818 | 3,600 | 4,692 | 3,744 | 1,003 | 4,747 | 32% |
| 62225 | Utilities-Heat/Natural Gas | 1,821 | 2,405 | 2,501 | 2,626 | 2,700 | 2,731 | 185 | 2,916 | 11% |
| 62226 | Utilities-Electric | 3,772 | 5,287 | 10,258 | 5,696 | 5,356 | 5,924 | (116) | 5,808 | 2% |
| 62228 | Utilities-Waste/Recycle Disposal | 1,169 | 1,046 | 1,300 | 1,418 | 1,550 | 1,475 | 199 | 1,674 | 18% |
| 62229 | Phones | 15,500 | 15,200 | 17,884 | 18,778 | 17,000 | 19,529 | (1,169) | 18,360 | -2% |
| 62231 | Postage | 358 | 987 | 1,027 | 975 | 500 | 1,014 | (489) | 525 | -46% |
| 62273 | Cable | 5,956 | 7,005 | 7,285 | 7,649 | 6,500 | 7,955 | (935) | 7,020 | -8% |
| 62370 | Insurance-Liability | 13,591 | 16,624 | 18,500 | 19,425 | 14,545 | 20,202 | (4,930) | 15,272 | -21% |
| 62372 | Insurance-Property | 919 | 1,004 | 4,700 | 4,935 | 8,861 | 5,132 | 4,172 | 9,304 | 89% |
| 62373 | Insurance-Work Comp | 6,364 | 5,228 | 5,437 | 5,709 | 9,913 | 5,937 | 4,471 | 10,409 | 82% |
| 62374 | Insurance-Vehicles | 845 | 941 | 1,135 | 1,192 | 1,216 | 1,240 | 37 | 1,277 | 7% |
| | Total Operating Expenses | 192,072 | 187,508 | 225,652 | 273,818 | 258,708 | 284,771 | 31,862 | 317,242 | 15% |

Program Costs

Administration

| | 2020 | 2021 | 2022 | 2024 | | 2025 | | |
|-------------------|--------|--------|--------|--------|-----------|---------|--------|---------|
| Service Providers | Actual | Actual | Actual | Budget | Projected | Current | Change | Request |
| Administraion | | | | | | | | |
| Field Supplies | 500 | 500 | 735 | 750 | 750 | 788 | (38) | 750 |
| Total | | | | | | | | |

Operations & Maintenance

| | 2020 | 2021 | 2022 | 20 | 24 | | 2025 | |
|---------------------------------|---------|---------|---------|---------|-----------|---------|----------|---------|
| Service Providers | Actual | Actual | Actual | Budget | Projected | Current | Change | Request |
| Operations & Maintenance | | | | | | | | |
| Engineering/Feasibility Studies | - | - | 30,000 | 30,000 | 30,000 | 31,500 | 300 | 31,800 |
| AOP Crossing Enhancement | | | | 0 | 0 | - | 79,500 | 79,500 |
| CC Restoration 131st to Main | | | | 0 | 0 | - | 106,000 | 106,000 |
| University Ave Pond Retrofit | | | | 0 | 0 | - | 51,100 | 51,100 |
| Woodbridge Channel Improvement | | | | 0 | 0 | - | 100,000 | 100,000 |
| Bank Repair & Stabilization | 856,208 | 593,050 | 58,240 | 125,000 | 125,000 | 131,250 | 21,125 | 152,375 |
| Ditch Repair & Maintenance | 124,021 | 58,000 | 137,280 | 100,000 | 100,000 | 105,000 | (52,000) | 53,000 |
| Non-routine Maintenance | - | 56,000 | 88,400 | 96,000 | 96,000 | 100,800 | 960 | 101,760 |
| Field Supplies | 1,000 | 600 | 4,625 | 1,400 | 1,400 | 1,470 | 30 | 1,500 |

Planning

| Planning & Special Studies | | | | | | | | |
|---|-------|-------|--------|---------|---------|--------|---------|---------|
| Boundary Adjustments | - | 3,500 | 3,500 | 3,000 | 3,000 | - | 0 | 0 |
| Water Quality Model | - | - | 70,000 | 0 | 0 | - | 210,000 | 210,000 |
| Model Updates | | | | 50,000 | 50,000 | 52,500 | 500 | 53,000 |
| Watershed Modeling Pilot Upgrade | 6,240 | 6,490 | 20,800 | 0 | 0 | - | 101,482 | 101,482 |
| Aquatic Organism Passage Enhancement Ph 2 | - | - | - | 75,000 | 75,000 | - | 0 | 0 |
| Subwatershed Planning/Assessments | - | - | - | 228,000 | 228,000 | - | 130,000 | 130,000 |
| Subwatershed Feasibility Designs | - | - | - | 0 | 0 | - | 120,000 | 120,000 |
| Channel Geomorphic Analysis | - | - | - | 0 | 0 | - | 79,500 | 79,500 |
| Drainage Atlas | | | | 0 | 0 | - | 7,950 | 7,950 |
| Water Quantity Studies | - | - | - | 0 | 0 | - | 26,500 | 26,500 |
| Economic Resource Study | | | | 125,000 | 125,000 | - | 0 | 0 |
| MN Partner Funding Research Council | - | - | - | 10,000 | 10,000 | - | 0 | 0 |
| Groundwater Study/Assessment | - | - | - | 5,000 | 5,000 | - | 90,000 | 90,000 |

Public and Governmental Affairs

| lic & Government Relations | | | | | | | | |
|--|--------|--------|--------|--------|--------|--------|---------|--------|
| <u>Information</u> | | | | | | | | |
| Springbrook I & E Implementation | - | - | - | 69,900 | 69,900 | - | 0 | (|
| Targeted Pleasure Cr Subwatershed I & E Implementation | - | - | - | 19,900 | 19,900 | - | 0 | (|
| NKE Sand Creek Trail Audience Survey | - | - | - | 15,000 | 15,000 | - | 0 | (|
| Website Updates | | | | 0 | 0 | - | 3,600 | 3,600 |
| Digital Communications | | | | 0 | 0 | - | 7,700 | 7,700 |
| Creek/Ditch Signage | - | - | - | 11,000 | 11,000 | 11,550 | (8,050) | 3,500 |
| <u>Involvement</u> | | | | | | | | |
| Audience Community Survey | 23,750 | 24,050 | 26,000 | 28,393 | 28,393 | 29,813 | 5,187 | 35,000 |
| Interactive Educational Displays | | | | | | - | 35,000 | 35,000 |
| Water Education Grants | 850 | 4,250 | 3,745 | 3,867 | 3,867 | 4,060 | (60) | 4,000 |
| Newsletter Communications | | | | 0 | 0 | - | 25,000 | 25,000 |
| Sponsorships | - | - | - | 1,750 | 1,750 | 1,838 | 262 | 2,100 |
| <u>Outreach</u> | | | | | | | | |
| Adopt-A-Drain | 10,000 | 6,500 | 6,864 | 6,000 | 6,000 | 6,300 | (800) | 5,500 |
| Pet Waste | 7,435 | 17,500 | 18,000 | 10,288 | 10,288 | 10,802 | 10,198 | 21,000 |
| Field Supplies | 1,103 | 2,444 | 6,614 | 3,815 | 3,815 | 4,006 | (1,456) | 2,550 |

Water Quality

| | 2020 | 2021 | 2022 | 20 | 24 | | 2025 | |
|---|--------|--------|--------|---------|-----------|---------|-----------|-----------|
| Service Providers | Actual | Actual | Actual | Budget | Projected | Current | Change | Request |
| Water Quality | | | | | | | | |
| AIS Rapid Response | 3,092 | - | 5,000 | 20,000 | 20,000 | 21,000 | 200 | 21,200 |
| Lake Plan Implementation | 1,215 | 2,776 | 2,887 | 5,000 | 5,000 | 5,250 | 50 | 5,300 |
| Monitoring | 89,113 | 96,400 | 99,746 | 110,489 | 110,489 | 116,013 | 1,105 | 117,118 |
| WQ Cost Share Program | 55,418 | 76,000 | 75,000 | 215,000 | 215,000 | 225,750 | 64,250 | 290,000 |
| Groundwater-Surface Water Chlorides Pilot | - | - | - | 35,000 | 35,000 | 36,750 | 37,662 | 74,412 |
| Biomonitoring | | | | 0 | 0 | - | 32,000 | 32,000 |
| Pond Performance Evaluation | | | | 0 | 0 | - | 5,000 | 5,000 |
| Street Sweepings Testing | - | - | - | 15,000 | 15,000 | - | 0 | 0 |
| Contaminents of Emerging Concern | - | - | - | 50,000 | 50,000 | - | 0 | 0 |
| Winter Chloride Monitoring | - | - | - | 6,000 | 6,000 | - | 0 | 0 |
| PC MNDot Pond Outlet Modification | - | - | - | 21,000 | 21,000 | - | 0 | 0 |
| Springbrook Nature Center Outlet Modification | - | - | - | 22,500 | 22,500 | - | 0 | 0 |
| Sand Creek AOP crossing Enhancement @ Xeon | - | - | - | 115,000 | 115,000 | - | 0 | 0 |
| Field Supplies | 3,000 | 3,666 | 7,547 | 2,566 | 2,566 | 2,694 | 1,256 | 3,950 |
| Multi-Revenue Source Projects | | | | | | | | |
| CRD Reg Park LCC Corridor Restoration-Expansion | | | | 0 | 0 | - | 695,000 | 695,000 |
| Springbrook Cr Subwatershed plan | | | | 90,000 | 90,000 | 94,500 | 158,200 | 252,700 |
| Pleasure Cr Subwatershed plan | | | | 87,500 | 87,500 | 91,875 | 717,935 | 809,810 |
| Subwatershed Planning-D39 | | | | 0 | 0 | - | 1,482,500 | 1,482,500 |

Watershed Development

| | 2020 | 2021 | 2022 | 2024 | | 2025 | | |
|--|--------|--------|--------|---------|-----------|---------|----------|---------|
| Service Providers | Actual | Actual | Actual | Budget | Projected | Current | Change | Request |
| Watershed Development | | | | | | | | |
| Illicit Discharge Detection | 590 | 800 | 850 | 900 | 900 | 900 | 0 | 900 |
| Groundwater-Surface Water Dewatering Study | - | - | - | 15,000 | 15,000 | - | 0 | 0 |
| District Rule Amendment | | | | 0 | 0 | - | 7,950 | 7,950 |
| Engineering | - | - | - | 400,000 | 400,000 | 420,000 | (70,000) | 350,000 |
| Field Supplies | 1,025 | 500 | 950 | 500 | 500 | 525 | 75 | 600 |

Capital Equipment

| | Prepared | 2021 | 2022 | 2023 | | 2024 | | | 2025 | | Change |
|-------|--------------------------------|--------|--------|--------|---------|-----------|---------|---------|---------|---------|---------|
| Code | 6/26/2024 10:57 | Actual | Actual | Actual | Budget | Projected | Var. | Current | Change | Request | 24-25 |
| | Capital Equipment | | | | | | | | | | |
| 65180 | Building Improvements | 28,000 | 0 | 8,000 | 97,350 | 97,350 | 0% | 30,350 | 44,496 | 74,846 | -23% |
| | Blinds | 8,000 | 0 | - | 0 | | | - | - | | |
| | Landscaping | 2,000 | 0 | 8,000 | 0 | | | - | 10,000 | | |
| | Keyless Entry-Rekey | | | | 20,900 | | | - | - | | |
| | Handicap Doors | | | | 11,100 | | | - | - | | |
| | Hex Pave/Auxilary parking | | | | 21,000 | | | 21,000 | 24,000 | | |
| | Rear Parking Paving | | | | 35,000 | | | - | - | | |
| | Parking Lot Netting | | | | 9,350 | | | 9,350 | 1,496 | | |
| | 3 bathroom fixtures/counters | | | | | | | - | 9,000 | | |
| 65230 | Monitoring & Field | 0 | 0 | 13,795 | 14,000 | 14,000 | 0% | - | 54,828 | 54,828 | 292% |
| | Portable Velocity/Depth Sensor | | | - | 14,000 | - | | - | - | | |
| | Backpack Electrofisher | | | | | | | - | 14,828 | | |
| | GNSS Receiver | | | | | | | - | 40,000 | | |
| 65250 | Vehicle | 0 | 55,000 | 0 | 0 | _ | #DIV/0! | - | 41,500 | 41,500 | 100% |
| | SUV - Truck(s) | | 55,000 | - | | - | | - | 41,500 | | |
| 65270 | Telecommunications | 0 | 0 | - | 0 | - | #DIV/0! | - | - | | #DIV/0! |
| | | | | | | | | - | - | | |
| 65340 | Office Equipment/Furniture | 0 | 0 | - | 16,000 | 16,000 | 0% | - | - | - | 0% |
| | Training Tables & Chairs | | | | 16,000 | | | - | - | | |
| 65380 | Computers & Equipment | 15,095 | 11,100 | - | 0 | - | #DIV/0! | - | 12,000 | 12,000 | 100% |
| | Monitors/computers | 15,095 | 11,100 | - | | - | | - | - | | |
| | Sharpboard | | | | | | | - | 12,000 | | |
| 65390 | Software | 0 | 0 | - | 29,358 | 29,358 | 0% | - | 15,000 | 15,000 | -49% |
| | MS4 Modules | | | | 0 | | | - | 15,000 | | |
| | Sage IntAcct | | | | 14,358 | | | - | - | | |
| | Website Migration | | | | 15,000 | | | - | - | | |
| | Total Capital Equipment | 43,095 | 66,100 | 21,795 | 156,708 | 156,708 | 0% | 30,350 | 167,824 | 198,174 | 26% |

COON CREEK WATERSHED DISTRICT Request for Board Action

MEETING DATE: August 12, 2024

AGENDA NUMBER: 18

ITEM: Oak Glen Creek Inspection Report

POLICY IMPACT: Policy FISCAL IMPACT: Budgeted

REQUEST

Receive inspection report.

BACKGROUND

This inspection is part of the District's Operations and Maintenance (O&M) program and the National Pollutant Discharge Elimination System (NPDES) requirement of inspecting 20% of the open channels annually.

Oak Glen Creek is located in Fridley. The channel is 0.35 miles (1,831 feet) Drainage area is 1.03 square miles (659.2 acres)


0 Public Laterals

IDENTIFIED MAINTENANCE NEEDS

| Need | Count | Cost Estimate | Immediate | Repair | Monitor |
|-------------------|-------|---------------|-----------|---------|---------|
| Obstruction | 4 | \$5,000 | \$2,000 | \$1,000 | \$2,000 |
| Ditch Repair | 0 | \$0 | \$0 | \$0 | \$0 |
| Bank Failure | 1 | \$4,700 | \$0 | \$4,700 | \$0 |
| Illicit Discharge | 0 | \$0 | \$0 | \$0 | \$0 |
| Beaver | 0 | \$0 | \$0 | \$0 | \$0 |
| Other | 2 | \$0 | \$0 | \$0 | \$0 |
| | 7 | \$9,700 | \$2,000 | \$5,700 | \$2,000 |

RECOMMENDATION

1. Receive report.



P:\Oper & Maint\inventory and Inspection\Oak Glen Creek\2024\Routine Inspection\Maps\General\General2.mxd

COON CREEK WATERSHED DISTRICT Request for Board Action

MEETING DATE: August 12, 2024

AGENDA NUMBER: 19

ITEM: Woodcrest Creek Inspection Report

POLICY IMPACT: Policy FISCAL IMPACT: Budgeted

REQUEST

Receive inspection report.

BACKGROUND

This inspection is part of the District's Operations and Maintenance (O&M) program and the National Pollutant Discharge Elimination System (NPDES) requirement of inspecting 20% of the open channels annually.

Woodcrest Creek is located in Coon Rapids.

The channel is 1.13 miles (5981 feet)

Drainage area is 1.27 square miles (810.7 acres)

0 Public Laterals

IDENTIFIED MAINTENANCE NEEDS

| Need | Count | Cost Estimate | Immediate | Repair | Monitor |
|-------------------|-------|---------------|-----------|----------|----------|
| Obstruction | 10 | \$16,000 | \$1,000 | \$13,000 | \$2,000 |
| Ditch Repair | 0 | \$0 | \$0 | \$0 | \$0 |
| Bank Failure | 8 | \$40,705 | \$0 | \$31,980 | \$8,725 |
| Illicit Discharge | 4 | \$0 | \$0 | \$0 | \$0 |
| Beaver | 0 | \$0 | \$0 | \$0 | \$0 |
| Other | 16 | \$0 | \$0 | \$0 | \$0 |
| | 38 | \$56,705 | \$1,000 | \$44,980 | \$10,725 |

RECOMMENDATION

1. Receive report.

Woodcrest Creek General UNIVERSITY BLAINE **COON RAPIDS** COON RAPIDS Immediate Repair Private Ditch Maintenance Req. Public Ditch Monitor Roads No Problem Subwatershed BLAINE **CCWD Boundary** COON RAPIDS 2,500 Feet 1,250 10 Miles

P:\Oper & Maint\Inventory and Inspection\Woodcrest\2024\Routine Inspection\Maps\GeneralGeneral2.mxd